NOTIFICATION OF ADDENDUM ADDENDUM NO. 1 DATED 1/05/2015

Control	6281-41-001
Project	RMC - 628141001
Highway	US0084
County	BROWN

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an adendum notification which details the changes and the respective proposal pages which were added and/ or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

```
SUBJECT: PLANS AND PROPOSAL ADDENDUMS
       PROJECT: RMC - 628141001 CONTROL: 6281-41-001
       COUNTY: BROWN
       LETTING: 01/06/2015
      REFERENCE NO: 0105
                         PROPOSAL ADDENDUMS
  PROPOSAL COVER
X BID INSERTS (SH. NO.: 2, 3, 4, 7, 8
X GENERAL NOTES (SH. NO.: A, B, C, D, E
_ SPEC LIST
             (SH. NO.:
_ SPECIAL PROVISIONS:
   ADDED:
      DELETED:
  SPECIAL SPECIFICATIONS:
   ADDED:
      DELETED:
X OTHER: ESTIMATE & QUANTITY SHEET AND ROADWAY SUMMARY CHANGES
DESCRIPTION OF ABOVE CHANGES
(INCLUDING PLANS SHEET CHANGES)
****BID INSERTS ******
REVISED QUANTITY FOR THE FOLLOWING ITEM NUMBERS 3278-2001 AND 3278-2002
****GENERAL NOTES*****
REVISED SHEETS 2-4
****PLAN SHEETS****
REVISED SHEET 7 AND 8
```

)

1-1

	ITEM-CODE		ЭE				DEDE
ALT	ITEM NO	DESC CODE	S.P. NO.	UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	316	2721	016	LOAD, HAUL & DISTRB AGGR (GR 4) DOLLARS and CENTS	CY	819.100	1
	500	2001	011	MOBILIZATION DOLLARS and CENTS	LS	1.000	2
	502	2001	033	BARRICADES, SIGNS AND TRAFFIC HANDLING DOLLARS and CENTS	МО	3.000	3
	662	2113		WK ZN PAV MRK SHT TERM (TAB) TY W DOLLARS and CENTS	EA	5,388.000	4
	662	2115		WK ZN PAV MRK SHT TERM (TAB) TY Y-2 DOLLARS and CENTS	EA	27,409.000	5
	662	2145		WK ZN PAV MRK ST (TAB) TY W ALT 3X DOLLARS and CENTS	EA	59,263.000	6
	666	2153		REF PAV MRK TY II (W) 8" (SLD) DOLLARS and CENTS	LF	19,351.000	7
	666	2156		EF PAV MRK TY II (W) 18" (SLD) DOLLARS CENTS		90.000	8
	666	2157		REF PAV MRK TY II (W) 24" (SLD) DOLLARS and CENTS	LF	256.000	9
	666	2169		REF PAV MRK TY II (W) (RR XING) DOLLARS and CENTS	EA	4.000	10

	ITEM-CODE							DEDE
ALT	ITEM NO	DESC CODE	S.P. NO.	UNIT BID PRICE ONLY. WRITTEN IN WORDS		UNIT	APPROX QUANTITIES	DEPT USE ONLY
	666	2178		REF PAV MRK TY II (Y) 4" (SLE and	REF PAV MRK TY II (Y) 4" (SLD) DOLLARS CENTS		44,604.000	11
	668	2018		PREFAB PAV MRK TY A (W) (12 and	PREFAB PAV MRK TY A (W) (12") (SLD) DOLLARS and CENTS		2,536.000	12
	668	2019		PREFAB PAV MRK TY A (W) (18 and	REFAB PAV MRK TY A (W) (18") (SLD) DOLLARS nd CENTS		763.000	13
	668	2117		PREFAB PAV MRK TY C (W) (18	REFAB PAV MRK TY C (W) (18")(YLD TRI) DOLLARS nd CENTS		22.000	14
	668	2118		PREFAB PAV MRK TY C (W) (36 and	PREFAB PAV MRK TY C (W) (36")(YLD TRI) DOLLARS and CENTS		12.000	15
	672	2012	034	REFL PAV MRKR TY I-C	DOLLARS CENTS	EA	1,896.000	16
	672	2015	034	REFL PAV MRKR TY II-A-A	DOLLARS CENTS	EA	18,136.000	17
	672	2022	034	TRAFFIC BUTTON TY II-C-R and	DOLLARS CENTS	EA	682.000	18
	3278	2001		ASPH (TIER I) and	DOLLARS CENTS	GAL	146,143.000	19
1	3278	2002		ASPH (TIER II) and	DOLLARS CENTS	GAL	706,746.000	20
	3278	2031		AGGR (TIER I) and	DOLLARS CENTS	CY	2,769.600	21

	ITEM-CODE		ЭE					DEPT
ALT	ITEM NO	DESC CODE	S.P. NO.	UNIT BID PRICE ONLY. WRITTEN IN WORDS		UNIT	APPROX QUANTITIES	USE ONLY
1	3278	2032			OLLARS ENTS	CY	16,750.200	22
	8251	2025	005		DOLLARS		24,370.000	23
	8251	2026	005	E PM W/RET REQ TY II (W) 4" (SLD) DOLLARS CENTS		LF	721,760.000	24
	8251	2029	005		C) OLLARS ENTS	LF	122,556.000	25
	8251	2030	005		O) OLLARS ENTS	LF	887,879.000	26
					OLLARS ENTS			
	3278	2096			OLLARS ENTS	GAL	846,090.100	27
	3278	2097		AGGR (TIER II)(TY B GR 4 OR TY L GR 4) DOLLARS and CENTS		CY	16,750.200	28

Project Number: RMC - 628141001 Sheet A

County: BROWN Control: 6281-41-001

Highway: US0084

GENERAL NOTES:

BASIS OF ESTIMATE – BASE BID

ITEM	DESCRIPTION	LOCATION	RATE
316	LOAD HAUL AND DISTRIBUTE	All	1 CY/120 SY
3278	ASPH (TIER I)	All	0.34 Gal/ SY
3278	AGGR (TY PB GR 4 or TY PL GR 4)	All	1 CY/ 120 SY
3278	ASPH (TIER I) or (TIER II)	All	0.36 Gal/ SY
3278	AGGR (TY PB GR4 or TY PL GR 4)	All	1 CY/ 120 SY

BASIS OF ESTIMATE – ALTERNATE BID

ITEM	DESCRIPTION	LOCATION	RATE
3278	ASPH (TIER II) (EMUL)	All	0.40 Gal/ SY
3278	AGGR (TY B GR 4 or TY L GR 4)	All	1 CY/ 120 SY

REFERENCES 1, 5 shall be ASPH (TIER I) AC Asphalt with GR 4 Aggregate.

REFERENCE 9 shall be ASPH (TIER I) AC Asphalt with GR 4 Aggregate Load

Haul and Distribute.

REFERENCES 2-4, 6-8, 10-36 may be either ASPH (TIER II) AC or EMUL Asphalt

with GR 4 Aggregate.

GENERAL

The latest start date for this project is <u>May 18, 2015</u>. All work for this project must be completed by <u>August 31, 2015</u>, due to fiscal year funding for Routine Maintenance Contracts.

Contract time is calculated using all alternate bid items as well as base bid items. Therefore, No additional time will be added for work performed on alternate bid items.

Contractor shall schedule projects such that no roadway work is performed in the vicinity of the following local festivals during the anticipated dates shown below unless otherwise approved by the Engineer. Coordinate any adjustments to the schedule with the Engineer if the anticipated dates change.

Project Number: RMC - 628141001 Sheet B

County: BROWN Control: 6281-41-001

Highway: US0084

Festival	City	Start Date	End Date
May fest	Bangs	5/1/2015	5/3/2015
Brownwood Reunion	Brownwood	9/19/2015	9/21/2015
July 4 th Parade	Brady	7/4/2015	7/4/2015
Labor Day Street Dance	Brady	8/29/2015	8/29/2015
Frontier Days	Santa Anna	5/15/2015	5/17/2015
Coleman Rodeo	Coleman	6/11/2015	6/13/2015
Spring Ho-down	Lampasas	7/6/2015	7/12/2015
Stars & Stripes	Richland Springs	7/3/2015	7/5/2015
Peach & Melon	DeLeon	8/4/2015	8/8/2015
Frontier Days	Breckenridge	4/30/2015	5/2/2015

GENERAL CONSTRUCTION

The Contractor's responsibility toward preparing the pavement for seal coat on all projects with no curb and gutter will be limited to normal sweeping with the usual rotary-broom equipment. All grass, weeds, etc. at the pavement edges will be removed by state forces.

The Contractor's responsibility toward preparing the pavement for seal coat for Urban Projects with curb and gutter will be normal sweeping with the usual rotary-broom equipment. After the placement of the Seal Coat trash, dirt, and excess rock shall be removed from the curb and gutter and sidewalks in manner approved by the Engineer.

All roadway and intersections shall be swept after each roadway is completed or as directed by the Engineer.

After each roadway is completed all paper joints shall be removed when each roadway is complete or as directed by the Engineer.

Cover or protect all bridge joints prior to sealing. Joint covering and all loose rock shall be removed after sealing. This work will not be paid for directly but will be considered subsidiary to Item 3278.

The Engineer shall calculate the length of rock lands and distributor shots for each project. The Contractor shall measure and mark the rock land and distributor shots on the project, unless otherwise directed by the Engineer.

ITEM 300 ASPHALTS, OILS AND EMULSIONS

The Engineer will run Test Method TEX 513-C (Saybolt Furol viscosity) for acceptance on emulsion sampled at the job sites. The Engineer will determine the sample location and test frequency.

Project Number: RMC - 628141001 Sheet C

County: BROWN Control: 6281-41-001

Highway: US0084

ITEM 302 AGGREGATES FOR SURFACE TREATMENTS

Flakiness index shall be 12 maximum.

All precoated aggregate shall use PG 64-22 asphalt.

ITEM 316 SURFACE TREATMENTS

STOCK PILE LOCATIONS (for material furnished by TxDOT)				
COUNTY REF # HWY LOCATION				
Eastland	9	FM 2689	FM 2689 @ JCT FM 2526 AND FM 2689 @ JCT CR 575	

ITEM 502 BARRICADES, SIGNS AND TRAFFIC HANDLING

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement

The Contractor's attention is called to the Traffic Control Details for Seal Coat operations plan sheet TCP (7-1)-13. These signs are in addition to the signs and barricades required by BC or TCP standard sheets. The Contractor will be required to install and uncover these signs the day surfacing operations on the travel lanes begin on each given roadway or up to 72 hours prior and remove and/or cover these signs the day the Contractor is notified that the permanent striping has been placed. The Contractor has up to five (5) days to permanently remove all construction signs from the project after final striping has been approved by the Engineer. After five (5) days, State Forces shall remove the signs and bill the Contractor for actual man hours, equipment utilization, storage and disposal fees, and any incidentals incurred by the State Forces.

Noncompliance may result in non-payment in accordance with Article 502.4.B and temporary suspension of all work until compliance is obtained. Time charges will continue.

On all TCP sheets requiring FCW20-7a (flagger symbol) with a distance placard, the distance placard may be omitted. The FCW20-7a signs shall at all times be positioned between the minimum sign distance X shown on the TCP or not more than 1000 feet from the flagger.

Flags attached to CW20-1D (Road Work Ahead) may be omitted unless otherwise directed.

Project Number: RMC - 628141001 Sheet D

County: BROWN Control: 6281-41-001

Highway: US0084

Traffic Control for all Temporary Tab placement and removal, Raised Reflective Pavement Marker placement and removal, brooming, and striping operations shall comply with requirements for mobile operations unless otherwise directed.

Flashing arrow panels shall be used instead of the shadow vehicles as shown on TCP (1-1 thru 1-4)-12 standards.

Type III barricades will not be required as shown on TCP standards. Channelizing devices shall be cones.

Channelizing devices will be required on tapers for lane transitions or other locations as directed by the Engineer.

The Contractor may be required to furnish flaggers with two-way radios to handle one-way traffic safely and efficiently through the work zone.

The pilot car shall be used during seal coat operations on any highway deemed necessary as directed by the Engineer.

The Contractor shall provide truck mounted attenuators on all shadow vehicles as shown on TCP (3-1 thru 3-3)-13 standard sheets.

In case of inclement weather during daylight hours while the Contractor is still on the project, it shall be the responsibility of the Contractor to handle traffic in a manner to minimize any damage to the seal coat.

ITEM 666 WORK ZONE PAVEMENT MARKINGS

Temporary tabs shall be placed in accordance with TCP (7-1)-13 standard for the seal coat operations and shall have double covers.

Temporary tabs shall not be placed on a road more than 24 hours prior to the seal coat operations beginning on that road.

Temporary tabs shall be removed once permanent reflectorized pavement markers have been placed.

ITEM 1122 TEMPORARY EROSION, SEDIMENTATION AND WATER POLLUTION PREVENTION AND CONTROL

Stockpile sites may be cleared of cover vegetation, but the vegetation root system shall not be destroyed.

Project Number: RMC - 628141001 Sheet E

County: BROWN Control: 6281-41-001

Highway: US0084

The SW3P for this project shall consist of using Contractor Force Account or Agreed Unit Price if erosion control is deemed necessary and shall be as directed by the Engineer.

ITEM 3278 SURFACE TREATMENTS

The Contractor shall furnish the distributor nozzles. The nozzles shall be furnished such that the nozzles outside the wheel paths of the travelway shall place 22 to 32 % more by volume than the nozzles over the wheel paths or as directed.

Engineer will witness Transverse Distribution Test Tex-922-K, Part III as directed.

The asphalt rates shown hereon are for average conditions. The rate may be varied as determined by the Engineer to obtain proper embedment of aggregate.

Intersections shall be sealed prior to sealing the main lanes and/or shoulders.

Asphalt shall be applied on intersections with the asphalt distributor bar to the maximum extent possible.

ITEM 8251 REFLECTORIZED PAVEMENT MARKINGS WITH RETROREFLECTIVE REQUIREMENTS

A Mobile Retroreflectometer is not required for this project. The Contractor shall provide traffic control for Retroreflectivity readings.