

NOTIFICATION OF ADDENDUM

ADDENDUM NO. 1

DATED 2/25/2014

Control	6268-48-001
Project	RMC - 626848001
Highway	FM2185
County	CULBERSON

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: RMC - 626848001

CONTROL: 6268-48-001

COUNTY: CULBERSON

LETTING: 02/27/2014

REFERENCE NO: 0225

PROPOSAL ADDENDUMS

_ PROPOSAL COVER

_ BID INSERTS (SH. NO.:

X GENERAL NOTES (SH. NO.: Page 2 of 2

_ SPEC LIST (SH. NO.:

_ SPECIAL PROVISIONS:

ADDED:

DELETED:

_ SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

X OTHER: Addition to Item 8 - Time charges will not commence until all
necessary permits are obtained by the contractor.

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

Project Number: RMC 6268-48-001

SHEET

COUNTY: CULBERSON

Control: 6268-48-001

HIGHWAY: FM 2185, ETC.

GENERAL NOTES:

General Project Description – This project consists of crushing, loading, and hauling, and stockpiling recycled reclaimed asphalt pavement (RAP) provided by the Department on FM 1111, FM 2809, FM 2185 in **Hudspeth and Culberson Counties**.

The project will be mainly managed by **Alpine Area Office:**

Christopher Weber, P.E. Alpine AE
2400 N. Hwy. 118
Alpine, Texas 79830
(432) 837-3391

Ruben Florez, Van Horn MSS
US 90, 1.5 Miles South of IH 10
Van Horn, TX 79855
(432) 283-2501

Each Contract awarded by the Department stands on its own and as such, is separate from other contracts. A contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

General Requirements

This Routine Maintenance Contract is for **specialty type work** consists of crushing, loading, hauling, and stockpiling recycled reclaimed asphalt pavement (RAP) at locations shown on the plans. The Department owned RAP stockpiles are available at FM 2529 (McCombs Street). The Contractor will process the RAP material at the stockpile location on FM 2529 (McCombs Street). After crushing and screening the RAP material as per **Special Specification 3281** it will be hauled to FM 1111, FM 2809, FM 2185 at locations and quantities shown on the plans.

Perform all work for this Contract in accordance with the Texas Department of Transportation Standard Specifications for Construction and Maintenance of Highways, Streets and Bridges (2004) and all applicable State Standards.

Bid item and associated quantities have been provided within this Contract in order to establish bid prices for the proposed work. Actual work performed as directed shall be paid utilizing these prices with no further compensation made regardless of the final quantities.

Maintain the entire project area in a neat and orderly manner throughout the duration of the work.

Where nighttime work is approved, provide adequate lighting for the entire work site as directed.

GENERAL NOTES

SHEET A

Project Number: RMC 6268-48-001

SHEET

COUNTY: CULBERSON

Control: 6268-48-001

HIGHWAY: FM 2185, ETC.

ITEM 2 - INSTRUCTIONS TO BIDDERS

This Contract includes plan sheets that are not part of the bid proposal:

View plans on-line or download from the web at:
<http://www.dot.state.tx.us/business/plansonline/plansonline.htm>

Order plans from any of the plan reproduction companies shown on the web at:
<http://www.dot.state.tx.us/gsd/plans/companies.htm>

Any questions concerning the preparation and submission of the proposal forms, contact:

Margie Cedillo
Contract Manager
Texas Department of Transportation
El Paso District Headquarters
13301 Gateway Blvd. West
El Paso, Texas 79928
(915) 790-4367

Each completed proposal shall be placed, together with the proposal guaranty or bid bond, in a sealed envelope with each proposal so marked as to indicate its contents. When submitted by mail, this envelope shall be addressed to address shown above.

Proposals will be accepted at the Texas Department of Transportation El Paso District Headquarters until **1:30 P.M., February 27, 2014**, then publicly opened and read prior to the closing of business on the same date.

A bid summation will be available via telephone by contacting the El Paso Maintenance Management office at (915) 790-4367.

If the bidder has any questions concerning the specification of work requirement of the Contract **contact:**

Ken Barnett, P.E.
El Paso District Maintenance Engineer
Texas Department of Transportation
El Paso District Headquarters
13301 Gateway Blvd. West
El Paso, Texas 79928
(915) 790-4300

GENERAL NOTES

SHEET B

Project Number: RMC 6268-48-001

SHEET

COUNTY: CULBERSON

Control: 6268-48-001

HIGHWAY: FM 2185, ETC.

ITEM 3 - AWARD AND EXECUTION

The Contract duration is for **2 months**. Time will start on the day of the pre-work meeting and will continue until the work is completed.

ITEM 4 - SCOPE OF WORK

Schedule and perform all work to assure proper drainage during the course of construction operations. All labor, tools, equipment and supervision required, to ensure drainage, removal, and handling of water shall be considered incidental work.

Repair any existing pavement, utilities, structures, etc., damaged as a result of operations, at no additional cost to the Department.

ITEM 7 - LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC

Comply with all OSHA and EPA regulations as well as all local laws, ordinances, federal and state requirements.

OSHA regulations prohibit operations that bring people or equipment within 10 feet of an energized electrical line. Where workers and/or equipment may be close to an energized electrical line, notify the electrical power company and make all necessary adjustments to ensure the safety of workers near the energized line.

Do not discharge any liquid pollutant from vehicles onto the roadside. Immediately clean spills and dispose in compliance with local, state, and federal regulations to the satisfaction of the Engineer at no additional cost to the Department.

ITEM 8 - PROSECUTION AND PROGRESS

This project to be completed in **40** days in accordance with **Section 8.3.A.4, "Standard Workweek."**

Prior to beginning operations, schedule and attend a preconstruction conference with the Engineer. Provide the Department a written outline of the proposed sequence of work (Bar Chart Schedule and an estimated progress schedule).

Time charges on this Contract will not commence until all necessary permits are obtained by the Contractor. Mobilize immediately after permits are obtained. Multiple crews may be necessary to accomplish the Contract requirement.

All quantities of materials are for estimating purposes and actual quantities shall be determined in the field by the Engineer.

Existing pavement, utilities, structures, etc., damaged as a result of the operations, will be repaired at no additional cost to the Department.

GENERAL NOTES

SHEET C

Project Number: RMC 6268-48-001

SHEET

COUNTY: CULBERSON

Control: 6268-48-001

HIGHWAY: FM 2185, ETC.

ITEM 500 - MOBILIZATION

The Contractor shall be paid in accordance with the associated Item based on work performed. This shall fully compensate the Contractor for all mobilization requirements to initiate the Contract.

ITEM 502 - BARRICADES, SIGNS AND TRAFFIC HANDLING

For information pertaining to channelization, signing, spacing details, and flagging procedures required to regulate, warn, and guide traffic through project, refer to the "Barricade and Construction" Standards and to the current *Texas Manual on Uniform Traffic Control Devices*.

Remove signs that do not apply to current conditions at the end of each day's work (do not lay down signs within clear zone).

GENERAL NOTES

SHEET D