

# NOTIFICATION OF ADDENDUM

## ADDENDUM NO. 1

**DATED 3/13/2006**

<b>Control</b>	<b>6143-47-001</b>
<b>Project</b>	<b>RMC - 614347001</b>
<b>Highway</b>	<b>SH0060</b>
<b>County</b>	<b>WHARTON</b>

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum by entering the date, which appears at the top of this letter on the Addendum Acknowledgement Form, contained in your bid proposal.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: RMC - 614347001

CONTROL: 6143-47-001

COUNTY: WHARTON

LETTING: 03/22/2006

REFERENCE NO: 0313

**PROPOSAL ADDENDUMS**

-----

- PROPOSAL COVER
- BID INSERTS (SH. NO.: )
- GENERAL NOTES (SH. NO.: A )

- SPEC LIST (SH. NO.: )
- SPECIAL PROVISIONS: )
- ADDED:

DELETED:

- SPECIAL SPECIFICATIONS:
- ADDED:

DELETED:

OTHER: Plan Sheet 2 and 4

DESCRIPTION OF ABOVE CHANGES  
(INCLUDING PLANS SHEET CHANGES)

Plan Sheet 2 General Notes:  
 Item 502 Barricades, Signs, and Traffic Handling  
 The second paragraph is deleted in its entirety and replaced with:  
 Shadow vehicles with truck mounted attentuators (TMA) will be required.  
 \*\*\*\*\*

Plan Sheet 4 Traffic Control Plan (YKM District) 3-97 is deleted and  
 replaced with Traffic Control Plan (YKM District) 9-03

**Project Number:** RMC 6143 47 001

**County:** Wharton, Matagorda, Austin, Victoria, Jackson

**Highway:** Various

## **GENERAL NOTES:**

Perform cleaning and sealing cracks as defined in Item 712 "CLEANING AND SEALING JOINTS AND CRACKS (ASPHALT CONCRETE)" of the 2004 Texas Standard Specifications and these General Notes.

Provide sufficient staff and equipment to concurrently process each contract at all times in the event of multiple contract awards. Each contract stands on its own and as such, is separate from other contracts.

Notify the specific office in which work will be performed by telephone each morning by 8:15 a.m. that work is scheduled with work location and time arrival or reason for not working that day.

Do not store materials or equipment in TxDOT yards. Do not heat sealant materials within TxDOT yards.

Remove materials or debris within the work limits not incorporated in the project from the right of way and dispose in an acceptable manner.

### **Item 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING**

Furnish and install all signs, barricades, and other incidentals necessary for proper traffic control. The traffic control plan for this project shall consist of the traffic control plan sheets and the barricade and construction standards listed on the title sheet. All warning signs shall be factory made and in satisfactory condition.

Shadow vehicles with truck mounted attenuators (TMA) will be required.

Pilot cars are required on Yoakum District TCP-One Lane Roadway unless otherwise directed.

Not more than one lane will be blocked at any time at a specific work site, unless otherwise authorized. Limit lane closures to 2 miles in length unless otherwise directed. The lane closure length in town sections will be determined by the engineer. Intersection traffic control and signing shall be in accordance with the BC sheets.

Provide sequential arrow boards for each lane closure of closure. Provide a standby unit in good working condition at the jobsite ready for immediate use. Additional devices may be needed to supplement these requirements.

Traffic control is considered subsidiary to the various bid items.

**Project Number:** RMC 6143 47 001

**County:** Wharton, Matagorda, Austin, Victoria, Jackson

**Highway:** Various

**Item 712. CLEANING AND SEALING JOINTS AND CRACKS (ASPHALT CONCRETE)**

Furnish and apply Class B rubber asphalt crack sealer in accordance with Item 300.2.H.

Furnish fine aggregate in accordance with Item 340.2.A.3. as directed.

Use a crew experienced in the work of crack sealing operations and in the necessary traffic control.

Working days are based on placing a minimum of 10 lane miles of sealing compound per day.

Keep all roadways clean of debris and open to traffic at the end of each workday.

Equip vehicles with highly visible, omni directional strobe lights.

**Project Number:** RMC 6143 47 001

**County:** Wharton, Matagorda, Austin, Victoria, Jackson

**Highway:** Various

**Estimated work limits for Wharton County. Richard Zahn at 979/532-3141**

HIGHWAY	APPROXIMATE LIMITS	APPROX. LANE MILES
SH 60 S	FM 1299 to FM 442 (RM 508 - RM 515 main lanes & shoulders)	30.0
UA 90	SH 60 to Colorado C/L (RM 636 – RM 647 shoulders only)	22.0
US 59 N	FM 961 to RM 573 (RM 566 – RM 573 right lane and shoulder)	14.0
	Section Total	66.0

**Estimated work limits for Matagorda County. Andy Brzozowski at 979/245-8338**

HIGHWAY	APPROXIMATE LIMITS	APPROX. LANE MILES
FM 1728	FM 1301 to SH 35	20.0
	Section Total	20.0

**Estimated work limits for Austin County. Frank White at 979/865-3101**

HIGHWAY	APPROXIMATE LIMITS	APPROX. LANE MILES
FM 1456	SH 36 to 1.5 miles south	3.0
FM 529	SH 159 to Bellville CL	0.6
FM 1457	Skull Creek Rd to Krebs Rd	2.5
FM 389	FM 1457 to Washington C/L	7.0
FM 1094	FM 109 to 1.5 miles east	3.0
FM 1094	FM 949 to 0.6 miles east	0.6
FM 1458	Strauss Rd to 1.3 miles south	2.6
FM 1093 E	SH 36 to Brazos River	7.5
SH 60	SH 36 to San Bernard River	5.0
	Section Total	31.8

**Project Number:** RMC 6143 47 001

**County:** Wharton, Matagorda, Austin, Victoria, Jackson

**Highway:** Various

**Estimated work limits for Victoria County. Ronnie Roecker at 361/573-6681**

HIGHWAY	APPROXIMATE LIMITS	APPROX. LANE MILES
SH 185	Diebel Addition (southbound lane and shoulder)	0.8
US 77	Refugio C/L to 11 mi north (inside lane & shoulder)	11.0
BU 77	0.2 mi north of Jct US 59/77 to 0.1 mile north of Stubbs School Rd (shoulders only)	3.2
US 77	SL 463 to US 87 (westbound frontage road. right & left lanes)	3.7
US 77	under US 87 overpass (by R&R)	0.2
SL 463	FM 1315 to BU 77 (Navarro) (westbound frontage road – right and left lanes)	1.8
US 59	Ramps and frontage at LP 463	1.7
BU 59	Navarro St to Laurent St.	2.5
FM 1685	From BU 59 to 1.6 miles west (outside lanes only)	3.2
	Section Total	28.1

**Estimated work limits for Jackson County. Bobby Mozisek at 361/782-2322**

HIGHWAY	APPROXIMATE LIMITS	APPROX. LANE MILES
SL 521	US 59 exit ramp (Bradford's) to US 59 on ramp (Love's)	14.7
SL 522	US 59 NB exit ramp to US 59 on ramp (Travel America)	10.5
FM 616	FM 1593 to LaWard CL	8.8
FM 616	Vanderbilt to Lavaca River Bridge	4.2
	Section Total	38.2