

NOTIFICATION OF ADDENDUM

ADDENDUM NO. 1

DATED 2/26/2016

Control	0372-01-096
Project	NH 2016(803)
Highway	US 77
County	SAN PATRICIO

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: NH 2016(803)

CONTROL: 0372-01-096

COUNTY: SAN PATRICIO

LETTING: 03/04/2016

REFERENCE NO: 0225

PROPOSAL ADDENDUMS

PROPOSAL COVER

BID INSERTS (SH. NO.:

X GENERAL NOTES (SH. NO.: E & J (PLAN SHEETS 3B & 3D)

SPEC LIST (SH. NO.:

SPECIAL PROVISIONS:

ADDED:

DELETED:

SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

X OTHER: PLAN SHEETS 2, 3B, 3D, 10 & 11

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

GENERAL NOTES SHEET E (PLAN SHEET 3B): ADDED NOTE TO ITEM 134.

GENERAL NOTES SHEET J (PLAN SHEET 3D): ADDED NOTE TO ITEM 502.

PLAN SHEET 2: MODIFIED BACKFILL DETAIL.

PLAN SHEET 10 & 11: CHANGED SIGN SIZE FOR ALL YIELD SIGNS.

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

GENERAL NOTES:

Find, for your information and convenience, tools such as forms, software, materials, and various other information provided by the Department at <http://www.txdot.gov/business.html>. Please note that these tools are updated periodically and your attention is directed to the latest edition.

In the event of a called evacuation, emergencies, impending adverse weather or as directed, do not perform any work without written authorization. The District reserves the right to suspend all work in support of evacuations or emergencies occurring from other parts of the state. Any work performed, other than work directed by the Department, is unauthorized work in accordance with Item 5.

Sweep, clean and remove any construction waste, surplus materials or debris from the roadway and right of way at the end of each day unless otherwise approved. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Asphalt application season will be established in accordance with Item 316.4.4 Adverse Weather Conditions or as directed by the engineer.

Cut existing pavement using a saw or other approved method to ensure a neat transverse and/or longitudinal line to assure a smooth tie-in with new pavement. Cut to a minimum depth of the final lift thickness. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Promptly pick up and properly dispose of paper and other materials used for pavement joints.

All pavement markings shall be in accordance with the latest edition of Texas MUTCD.

ITEM 2

It is recommended that prospective bidders examine the specified work locations with the Engineer to view the nature of the work, the need for close coordination with the various

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

utilities, traffic control considerations, and other factors influencing the prosecution of the work.

Submit pre-letting questions by email only to Charles.Benavidez@txdot.gov and Armando.Bosquez@txdot.gov that contains "CSJ 0372-01-096 CONTRACTOR QUESTIONS" in the subject line. An electronic file containing pre-letting questions and TxDOT answers will be provided on TxDOT's FTP site.

In addition, an electronic file containing pre-letting questions and answers will be uploaded to the following site that can be downloaded by using the Login Name and Password as follows:

Website Address (to be typed into Windows Explorer): <ftp://username@ftp.txdot.gov>
Username: SINTON-AO-ro
Password: WOP497

ITEM 5

Field verify all dimensions and notify Engineer prior to initiating any work.

Verify the locations of utilities, underground or overhead, shown within the limits of the right-of-way. Adhere to OSHA Standards when working within the vicinity of overhead power lines. Coordinate with the utility companies and notify the Engineer of any possible conflicts. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

The 811 call services for utility locations do not include TxDOT facilities. The contractor shall contact the Corpus Christi District Signal Section (361-739-6044) for coordination with TxDOT underground lines.

Notify the Engineer immediately of utility conflicts in accordance with Item 5.6. Refer to Item 4.5 for consideration of differing site conditions.

The responsibility for the construction surveying on this contract will be in accordance with Item 5.9.3, "Method C".

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

ITEM 7

The work performed for Item 7.2.4, "Public Safety and Convenience" will not be measured or paid for directly, but will be subsidiary to pertinent Items.

When working at street, farm-to-market, state highway, and county road intersections, schedule work to minimize intersection closures. During nonworking hours, all public road intersections will be open to the traveling public.

The total disturbed area for this project is 9.2 acres. The disturbed area in this project, all project locations in the Contract, and Contractor project specific locations (PSLs), within 1 mile of the project limits, for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain any required authorization from the TCEQ for any Contractor PSLs for construction support activities on or off ROW. When the total area disturbed for all projects in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the ROW to the Engineer.

Comply with the Texas Aggregate Quarry and Pit Safety Act for waste areas or material source areas resulting from this project.

ITEM 8

Prepare the progress schedule using the Critical Path Method (CPM). Submit (2) two 11" x 17" hard copies and an electronic file of the original or updated progress schedule. Submit the original progress schedule seven (7) days before the Preconstruction Conference.

Submit an updated progress schedule as directed to show proposed major changes, changes affecting compliance with the contract requirements, or changes affecting the critical path/controlling item of work.

Working days will be computed and charge in accordance with Article 8.3.1.4, "Standard Workweek".

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

Work above traffic is not allowed.

Nighttime work is not permitted.

Notify the Engineer at least 48 hours in advance of weekend work.

ITEM 9

Monthly progress payments will be made for items of work completed by the 28th day of each month. Any work completed after the 28th will be included for payment in the subsequent monthly progress estimate.

Submit signed request for compensation of material-on-hand (MOH), including any requests from subcontractors, suppliers, or fabricators for MOH, at least two (2) working days prior to the end of the month on the Departments approved forms.

ITEM 134

Use backfill material with a plasticity index (PI) ranging from 15 to 35. Notify the Engineer of the proposed material sources and of changes to material sources. The Engineer may sample and test project materials at any time before compaction throughout the duration of the project to assure specification compliance.

Windrow the existing topsoil and grass along the edge of the grading operations or as directed. After grading operations are completed, spread the topsoil and grass uniformly on all slopes and ditch lines. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Manipulate and compact backfill material in accordance with Item 132.3.4.1, "Ordinary Compaction". The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

Furnish asphalt for erosion control meeting SS-1 requirements per Item 300. Apply Asphalt after final finishing of the backfill material and in accordance with details shown on the typical sections. Apply at a rate of 0.10 gal/sy. Asphalt will be subsidiary to Item 134

ITEM 302

Provide aggregates with a minimum surface aggregate classification (SAC) of "B" unless otherwise shown. The SAC for sources on the Department's Aggregate Quality Monitoring Program (AQMP) is listed in the Department's Bituminous Rated Source Quality Catalogue (BRSQC). SAC requirements apply to aggregates used on all final roadway surfaces, including shoulders.

When using asphalt emulsion, use a precoat material for the aggregates as approved.

ITEM 316

Clean aggregates showing signs of excessive dust from the stockpile or while handling during construction. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Do not place surface treatment on exposed concrete structures unless directed.

Furnish a distributor equipped with a hand hose in working condition.

When using asphalt emulsion, a minimum 24-hour curing period is required before placing any subsequent asphalt courses.

Stockpiling of aggregates may begin after the execution of the Authorization to Begin Work or issuance of the work order.

Remove vegetation and blade pavement edges prior to surfacing operations. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Broom and clean sealed sections of roadway and all adjacent paved surfaces, including the gutter line, of any surplus aggregate before opening to traffic or as directed.

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

ITEM 341

The use of Recycled Asphalt Shingles (RAS) will not be allowed.

Provide aggregates with a minimum surface aggregate classification (SAC) of "B" and trackless tack unless otherwise shown. SAC requirements apply to aggregates used on all final roadway surfaces, including shoulders.

Use of Contractor-owned RAP including HMA plant waste will be permitted after the material from Item 354 has been exhausted or as approved by the Engineer

Department-owned RAP generated through required work on the Contract is available for the Contractor's use.

Perform any necessary tests to ensure RAP is appropriate for use.

Any RAP remaining from the contract is to remain with the Contractor.

Use crushed gravel screenings with or in lieu of stone screenings.

Use a cut-off chute when placing hot-mix asphalt on narrow width locations unless approved.

Construct longitudinal joints with a joint maker providing a maximum one (1) inch vertical edge (1/2 inch desirable) with an adjacent 6:1 taper. Construct the outside edge with a 6:1 taper or backfill within the same day.

Unless otherwise approved by the Engineer, a tack coat will be placed on all lifts in accordance to 341.4.7.2 Tack Coat. Trackless Tack will be used as tack coat. This work will not be paid for directly but will be subsidiary to Item 341.

Immediately after coring, remove all moisture and debris from each core hole, tack the inside vertical face of each core hole with AC or PG asphalt, and place hot mix in lifts not to exceed three inches or as directed by the Engineer. Use slide hammering or other approved method(s) to achieve compaction.

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

The Engineer reserves the right to test all sources even if the source is listed in the Bituminous Source Rated Quality Catalog.

Provide the testing lab samples to calibrate the ignition oven no later than five (5) working days prior to mix design verification.

For tests specified by the Engineer, enter testing data in Department-provided electronic testing template spreadsheets. Submit electronically to the Engineer at the interval directed by the Engineer.

ITEM 344

The use Recycled Asphalt Shingles (RAS) will not be allowed on surface mixtures.

Provide aggregates with a minimum surface aggregate classification (SAC) of "A" unless otherwise shown. SAC requirements apply to aggregates used on all final roadway surfaces, including shoulders.

Use of Contractor-owned RAP including HMA plant waste will be permitted after the material from Item 354 has been exhausted or as approved by the Engineer

Department-owned RAP generated through required work on the Contract is available for the Contractor's use.

Perform any necessary tests to ensure RAP is appropriate for use.

Any RAP remaining from the contract is to remain with the Contractor.

Use crushed gravel screenings with or in lieu of stone screenings.

Use a cut-off chute when placing hot-mix asphalt on narrow width locations unless approved.

Construct longitudinal joints with a joint maker providing a maximum one (1) inch vertical edge (1/2 inch desirable) with an adjacent 6:1 taper. Construct the outside edge with a 6:1 taper or backfill within the same day.

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

Unless otherwise approved by the Engineer, a tack coat will be placed on all lifts in accordance to 344.4.7.2 Tack Coat. RC-250 will be used as tack coat. This work will not be paid for directly but will be subsidiary to Item 344.

Immediately after coring, remove all moisture and debris from each core hole, tack the inside vertical face of each core hole with AC or PG asphalt, and place hot mix in lifts not to exceed three inches or as directed by the Engineer. Use slide hammering or other approved method(s) to achieve compaction.

The Engineer reserves the right to test all sources even if the source is listed in the Bituminous Source Rated Quality Catalog.

Provide the testing lab samples to calibrate the ignition oven no later than five (5) working days prior to mix design verification.

Unfractionated RAP will not be allowed in either surface or non-surface mixtures.

For tests specified by the Engineer, enter testing data in Department-provided electronic testing template spreadsheets. Submit electronically to the Engineer at the interval directed by the Engineer.

ITEM 351

Use of motor grader will not be permitted unless approved.

ITEM 354

Incorporate the RAP, backfill for pavement edges, or as approved. Any excess RAP will become the property of the Contractor.

Perform any necessary tests to ensure RAP is appropriate for use.

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

ITEM 432

Saw cut the existing riprap to ensure a neat transverse and/or longitudinal line to assure a smooth tie-in with new riprap. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Reinforce concrete riprap with 4 x 4 – W2.9 x W2.9 welded wire fabric or with No. 3 reinforcing bars spaced at a maximum of 12 inch in each direction.

ITEM 462

Use cold-applied, plastic asphalt sewer joint compound for all joints. Provide sandproof tape for all pipe placed in cohesionless backfill material as approved, or provide gaskets that conform to Item 464.2.7.3.

The work performed for concrete collars will not be measured or paid for directly, but will be subsidiary to pertinent Items.

ITEM 467

Place safety end treatments with a uniform slope.

Provide 5/8” x 6” galvanized hooked bolts with 2 hex nuts at a spacing not to exceed 24 inches center to center for metal pipes with riprap sloped headwalls. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Reinforce concrete riprap with 4 x 4 – W2.9 x W2.9 welded wire fabric or with No. 3 reinforcing bars spaced at a maximum of 12 inch in each direction.

ITEM 500

"Materials on Hand" payments are not considered when determining partial payments.

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

ITEM 502

Furnish additional barricades, signs, and traffic handling as directed. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Traffic control for daytime lane closures shall be in accordance with TCP 2 Series Standards. Traffic control shall include temporary rumble strips in accordance with WZ (RS)-14.

When advanced warning flashing arrow panels are specified, furnish one (1) standby unit in good condition at the job site for immediate use.

The Contractor's Responsible Person (CRP) or his representative(s) shall be located within one hour of traveling time to the project site. The Contractor shall notify the Engineer in writing of the name, physical address, and telephone number of this employee or these employees. The Engineer shall furnish this information to local law enforcement officials.

Maintain traffic control devices by taking corrective action as soon as possible. Complete corrective action within 48 hours of written notification regardless of the day of the week involved unless otherwise directed.

Provide a positive means of communication between flaggers unless otherwise approved.

Attach stop/slow paddle to a staff with a minimum length of 6 feet to the bottom of the sign.

The use of a pilot vehicle in conjunction with flaggers will be permitted. If used, provide positive and unrestricted communication between the driver of the pilot vehicle and the flaggers. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

ITEM 504

No field office will be required for this project.

Provide one (1) Type D Structure (Asphalt Mix Control Laboratory).

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

Portable toilets will not be allowed.

Secure all exterior openings with bars.

Apply for and secure permits necessary for the buildings, and pay all utility meter deposits and service bills. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Provide 2 sets of keys for all facilities.

Provide 2 standard size office desks, 4 office chairs, 2 bookcases, and 2 filing cabinets as approved. Provide solar screens, blinds, or shades.

Provide internet connectivity, a printer/fax/scan/copier, and a telephone.

Provide hot water or a hot water dispenser capable of generating one (1) gallon of water at 140 degrees Fahrenheit with acceptable water pressure.

Provide Safety Equipment as follows:

(1) ONE EYE WASH STATION

(2) ONE FIRST AID KIT

Provide doors with a minimum width of 36 inches and 80 inches in height. Secure all exterior openings with bars.

Asphalt content will be measured by Ignition Method.

ITEM 506

Designate in writing a Contractor Responsible Person (CRP) for implementing, maintaining, and reviewing environmental requirements.

ITEM 533

Construct shoulder texturing at a distance of 6 inches from the edge line in accordance to RS (1)-13 Option 4.

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

ITEM 540

Complete each location during the working day. No exposed bridge rail or guard fence ends will be permitted at the end of the working day or unattended during the working day.

Mixing of wood post types and shapes will not be permitted at the same location.

Type II Galvanization coatings will be used.

ITEM 542

Disassemble, deliver and neatly stack salvageable materials at Sinton Maintenance Office, 1157 US Hwy 181 Sinton, TX 78387. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

ITEM 544

The method of placing steel tubes in drilled holes is not permitted.

ITEM 585

Use Surface Test Type B and Pay Adjustment Schedule 2 to evaluate ride quality of the travel lanes in accordance with Item 585, "Ride Quality for Pavement Surfaces."

Use latest version of approved Ride Quality Software.

For QC Testing, provide inertial profiler results the same working day after paving.

For QA Testing, provide the Engineer the opportunity to witness the testing. Provide a seat for the Engineer in the test vehicle or arrange for the Engineer to follow the test vehicle if requested.

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

ITEM 644

Use crash worthy supports as shown on the BC sheets, the CWZTCD, or as directed for signs relocated using temporary supports. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Disassemble, deliver and neatly stack salvageable materials at Sinton Maintenance Office, 1157 US Hwy 181 Sinton, TX 78387. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

All slip base and hardware including but not limited to nuts, bolts, screws, and washers will be galvanized. All sign and housing components will be galvanized.

ITEM 662

Use temporary flexible-reflective roadway marker tabs at the beginning and end of no passing zones as shown on the TCP (7-1)-13 for seal coats and WZ(STPM)-13 for hot mix overlays.

ITEM 666

Before planing the roadway, the Contractor will be responsible for noting and recording the locations and configuration of all existing pavement markings for use in installing the final permanent pavement markings. All roadways are to be striped as existing, unless shown otherwise in the plans or as determined by the Engineer.

Place pavement markings no later than 14 calendar days after the placement of the surface. When inclement weather prohibits placement of markings, the 14-day period may be extended until weather permits proper application.

ITEM 730

Provide full-width mowing for a period of 2 cycles or as directed.

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

ITEM 752

Coordinate tree trimming and brush removal activities with the Engineer prior to beginning work. Ensure canopies that remain are uniform. No uneven canopies will be accepted. Prune trees and shrubs as directed. Use accepted pruning practices in accordance with TRB-15(1), Item 192, and as defined by the National Arborist Association.

ITEM 6001

Furnish the portable changeable message signs displaying the correct message at least seven (7) days prior to beginning work or as directed.

The Contractor's Responsible Person (CRP) will maintain full control of messages at all times.

The Engineer will provide the signs message text to use at each sign.

Provide cellular phone connection.

A minimum of 2 PCMS will be required. However, additional units may be necessary depending on the work in progress.

Standby time will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Portable changeable message signs may be moved and message changed at any time as deemed necessary by the Engineer. This will be considered subsidiary to Item 6001.

Project Number: NH 2016(803)

Sheet

County: San Patricio

Control: 0372-01-096

Highway: US 77

SPECIFICATION DATA

UNIT WEIGHT ESTIMATES

2" SUPERPAVE MIXTURES SP-D SAC-A PG70-22-----	220 LBS/SY
3" D-GR HMA TY-B SAC-B PG70-22-----	330 LBS/SY
ITEM 247 – FL BS (CMP IN PLC) (TY A GR 1-2)(FNAL POS)-----	136 LBS/CF

COMPACTION REQUIREMENTS FOR BASE COURSE

ITEM 247—FL BS (CMP IN PLC)(TYA GR1-2) (FNAL POS)	
DENSITY-----	100% MIN
LIFTS-----	ALL

PRIME COAT

ASPHALT, TYPE -----	MC-30
AVERAGE ASPHALT RATE (GAL/SY) -----	0.20

SURFACE TREATMENT DATA

ONE COURSE UNDERSEAL

ASPHALT TYPE-----	ASPH (AC-15P, HFRS-2P. OR CRS-2P)
ASPHALT RATE (GAL/SY) -----	0.35 – 0.43
AVERAGE ASPHALT RATE (GAL/SY)-----	0.390
AGGREGATE RATE (CY/SY)-----	1/110
AGGREGATE TYPE -----	PB
AGGREGATE GRADE-----	4 OR 4S SAC B

This page intentionally left blank.