

NOTIFICATION OF ADDENDUM

ADDENDUM NO. 1

DATED 4/02/2010

Control	6207-41-001
Project	RMC - 620741001
Highway	FM3280
County	JACKSON

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: RMC - 620741001

CONTROL: 6207-41-001

COUNTY: JACKSON

LETTING: 04/08/2010

REFERENCE NO: 0402

PROPOSAL ADDENDUMS

_ PROPOSAL COVER

X BID INSERTS (SH. NO.: 1-2 and 2-2)

X GENERAL NOTES (SH. NO.: Sheet B and C)

X SPEC LIST (SH. NO.: 1-2 and 2-2)

_ SPECIAL PROVISIONS:

ADDED:

DELETED:

_ SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

X OTHER: Plan Sheets 2, 2A, 3, and 18

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

Bid items deleted: 464-2005-003 RC PIPE (CL III)(24 IN)
464-2064-003 RC PIPE (ARCH)(CL III)(DES 3)
467-2224 SET (TY II)(24 IN)(RCP)(4:1)(C)
467-2323 SET (TY II)(DES 3)(CMP)(4:1)(C)

Bid items replaced: 460-2037 CMP AR (GAL STL BIT COAT DES 4)
467-2324 SET (TY II)(DES 4)(CMP)(4:1)(C)

General Notes and plan sheets to reflect the above.

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	132	2005		EMBANKMENT (FINAL)(ORD COMP)(TY C) DOLLARS and CENTS	CY	18.000	1
	150	2002		BLADING DOLLARS and CENTS	HR	10.000	2
	164	2001	002	BROADCAST SEED (PERM) (RURAL) (SANDY) DOLLARS and CENTS	SY	300.000	3
	168	2001		VEGETATIVE WATERING DOLLARS and CENTS	MG	1.600	4
	400	2005		CEM STABIL BKFL DOLLARS and CENTS	CY	3.000	5
	407	2001		SHEET PILING (PZ-27) DOLLARS and CENTS	SF	675.000	6
	432	2027		RIPRAP (SPECIAL) DOLLARS and CENTS	CY	121.000	7
	460	2037		CMP AR (GAL STL BIT COAT DES 4) DOLLARS and CENTS	LF	72.000	8
	467	2324		SET (TY II)(DES 4)(CMP)(4:1)(C) DOLLARS and CENTS	EA	18.000	9
	500	2001	005	MOBILIZATION DOLLARS and CENTS	LS	1.000	10

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	502	2001	033	BARRICADES, SIGNS AND TRAFFIC HAN- DLING DOLLARS CENTS and	MO	2.000	11
	506	2022	011	EARTHWORK (ERSN & SEDM CONT, IN VEH) DOLLARS CENTS and	CY	3.000	12
	506	2034	011	TEMPORARY SEDIMENT CONTROL FENCE DOLLARS CENTS and	LF	300.000	13

Project Number: RMC 6207 41 001

County: Jackson, Etc.

Highway: FM 3280, Etc.

GENERAL NOTES:

If the contractor elects to work on a structure when the stream is flowing, near normal flow shall be maintained by a method approved by the engineer. Labor and materials involved in this work will not be paid for directly, but will be considered subsidiary to the various bid items of the contract.

Individual structures will be extended on one side at a time through completion before construction work is begun on the opposite side unless otherwise directed.

Do not commence work on the road before sunrise and arrange work so that no machinery will be on any traveled roadway after sunset.

Leave all traffic lanes open to traffic at night, weekends and holidays unless otherwise approved.

Furnish a certified copy of the legal gross weight of each vehicle hauling materials to the project and certified measurements for all trucks hauling material by volume.

Place the seeding after completion of embankment and/or structure work and prior to beginning work at the next location unless otherwise directed.

Unless otherwise approved, maintain a minimum safety clearance from the edge of the travelway for material stockpiled in proximity of traffic lanes based on the current average traffic count of the particular highway as follows:

0 - 1500 = 16 feet
Over 1500 = 30 feet

In the event the above requirements cannot be met, make arrangements to stockpile material off the right of way.

The Department will provide the cylinder testing machine for this project. Deliver the test specimens to the engineer's curing facilities as directed.

Do not clean out concrete trucks within the right of way.

ITEM 132: EMBANKMENT

Furnish Type C embankment consisting of suitable earth material such as loam, clay or other such material that will form a stable embankment and has a plasticity index of at least 10 but not more than 40.

Project Number: RMC 6207 41 001

County: Jackson, Etc.

Highway: FM 3280, Etc.

ITEM 150: BLADING

Sprinkling and rolling which may be required during the operation of Item 150 will not be measured or paid for directly, but will be considered subsidiary to this item.

ITEM 400: EXCAVATION AND BACKFILL FOR STRUCTURES

Provide material that meets the requirements for Item 247 "Flexible Base" Ty A, for cement stabilized backfill aggregate.

ITEM 407: SHEET PILE

Sheet piling for the contractor's use on FM 2235 will be provided by the State. The sheet pile will be available for pick up at the Calhoun County maintenance yard, located on SH 35 in Port Lavaca.

ITEM 421: HYDRAULIC CEMENT CONCRETE

Do not air entrain all concrete.

ITEM 432: RIPRAP

Riprap for this project will consist of Stone Protection riprap, grouted in place as directed by the Engineer.

Filter fabric, as shown in section 432.3, will be required for this item.

Cofferdam will not be paid for directly, but will be considered subsidiary to Item 432.

ITEM 460: CORRUGATED METAL PIPE

Corrugations shall be 2 2/3 by 1/2 inch and minimum of 16 gauge.

Project Number: RMC 6207 41 001

County: Jackson, Etc.

Highway: FM 3280, Etc.

ITEM 467: SAFETY END TREATMENT

If required, concrete collars, as approved, will be used at pipe joints. Collars will be reinforced as directed. No direct compensation will be made for concrete collars and they will be subsidiary to the pertinent items.

Precast safety end treatment sections will not be allowed.

Provide reinforced concrete riprap for all pipe safety end treatments. Round corners on safety end treatment riprap to a minimum 12 inch radius as directed. The riprap will not be paid for directly but will be subsidiary to Item 467.

Provide and use a form along the cut end of the pipe when placing the adjacent reinforced concrete riprap for reinforced concrete pipe safety end treatment sections.

ITEM 502: BARRICADES, SIGNS, AND TRAFFIC HANDLING

Provide suitable warning lights mounted high enough to be visible from all directions on all construction equipment, including pilot vehicles, and operate warning lights when the equipment is within the right of way. Equip other equipment such as trucks, trailers, autos, etc., with emergency flashers and use emergency flashers while within the work area.

Use 48"X48" diamond shaped construction warning signs unless otherwise approved.

ITEM 506: TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS

Since less than 1 acre of soil is disturbed by this project, the storm water pollution prevention plan (SW3P) for this project will consist of using the following items as directed.

ITEM 506: Earthwork For Erosion Control (For Silt Removal)

ITEM 506: Temporary Sediment Control Fence

Project Number: RMC 6207 41 001

County: Jackson, Etc.

Highway: FM 3280, Etc.

B A S I S O F E S T I M A T E

ITEM | DESCRIPTION | RATE | BASIS | QUANTITY | UNIT

FM3280

150	BLADING		EST	10	HR
164	BROADCAST SEED (PERM) (RURAL) (SANDY)				
	STA 19+21.65			100	SY
	STA 52+30			100	SY
	STA 53+20.74			100	SY
				=====	
				300	SY
168	VEGETATIVE WATERING				
	13.58 MG/AC/MO X 2 MO X 0.06 AC			1.6	MG
506	TEMPORARY SEDIMENT CONTROL FENCE				
	APPROXIMATELY 50 LF X 3 STRUCTURE LOCATIONS			150	LF

FM1679

506	TEMPORARY SEDIMENT CONTROL FENCE			75	LF
-----	----------------------------------	--	--	----	----

FM2235

506	TEMPORARY SEDIMENT CONTROL FENCE			75	LF
506	EARTHWORK (ERSN & SEDM CONT, IN VEH)		EST	3	CY

CONTROL : 6207-41-001
PROJECT : RMC - 620741001
HIGHWAY : FM3280
COUNTY : JACKSON

TEXAS DEPARTMENT OF TRANSPORTATION

GOVERNING SPECIFICATIONS AND SPECIAL PROVISIONS

ALL SPECIFICATIONS AND SPECIAL PROVISIONS APPLICABLE TO THIS PROJECT ARE IDENTIFIED AS FOLLOWS:

STANDARD SPECIFICATIONS: ADOPTED BY THE TEXAS DEPARTMENT OF
----- TRANSPORTATION JUNE 1, 2004.
STANDARD SPECIFICATIONS ARE INCORPORATED
INTO THE CONTRACT BY REFERENCE.

ITEMS 1 TO 9 INCL., GENERAL REQUIREMENTS AND COVENANTS
ITEM 132 EMBANKMENT (100)(204)(210)(216)(400)
ITEM 150 BLADING <204><210>
ITEM 164 SEEDING FOR EROSION CONTROL (166)(168)
ITEM 168 VEGETATIVE WATERING
ITEM 400 EXCAVATION AND BACKFILL FOR STRUCTURES (132)<247>(401)
(420)(421)
ITEM 407 STEEL PILING (404)(448)
ITEM 432 RIPRAP <420><421><427>
ITEM 460 CORRUGATED METAL PIPE (400)<476>
ITEM 467 SAFETY END TREATMENT (400)<420><421><430><432><440><460>
<464>
ITEM 500 MOBILIZATION
ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING
ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL
CONTROLS

SPECIAL PROVISIONS: SPECIAL PROVISIONS WILL GOVERN AND TAKE
----- PRECEDENCE OVER THE SPECIFICATIONS ENUMERATED
HEREON WHEREVER IN CONFLICT THEREWITH.

SPECIAL PROVISION "SCHEDULE OF LIQUIDATED DAMAGES" (000--1493)
SPECIAL PROVISION "DEPARTMENT DIVISION MAILING AND PHYSICAL ADDRESS"
(000---011)
SPECIAL PROVISION TO ITEM 1 (001---011)
SPECIAL PROVISION TO ITEM 2 (002---017)
SPECIAL PROVISIONS TO ITEM 3 (003---023)(003---033)
SPECIAL PROVISION TO ITEM 4 (004---013)

SPECIAL PROVISION	TO ITEM	5	(005---004)
SPECIAL PROVISION	TO ITEM	6	(006---030)
SPECIAL PROVISIONS	TO ITEM	7	(007---213)(007---639)
SPECIAL PROVISIONS	TO ITEM	9	(009---002)(009---012)(009---015)
SPECIAL PROVISION	TO ITEM	100	(100---002)
SPECIAL PROVISION	TO ITEM	164	(164---002)
SPECIAL PROVISION	TO ITEM	166	(166---001)
SPECIAL PROVISION	TO ITEM	247	(247---003)
SPECIAL PROVISION	TO ITEM	420	(420---002)
SPECIAL PROVISION	TO ITEM	421	(421---035)
SPECIAL PROVISION	TO ITEM	448	(448---002)
SPECIAL PROVISION	TO ITEM	500	(500---005)
SPECIAL PROVISION	TO ITEM	502	(502---033)
SPECIAL PROVISION	TO ITEM	506	(506---011)

SPECIAL SPECIFICATIONS:

GENERAL: THE ABOVE-LISTED SPECIFICATION ITEMS ARE THOSE UNDER WHICH
 ----- PAYMENT IS TO BE MADE. THESE, TOGETHER WITH SUCH OTHER
 PERTINENT ITEMS, IF ANY, AS MAY BE REFERRED TO IN THE ABOVE-
 LISTED SPECIFICATION ITEMS, AND INCLUDING THE SPECIAL
 PROVISIONS LISTED ABOVE, CONSTITUTE THE COMPLETE SPECIFI-
 CATIONS FOR THIS PROJECT.