

# **NOTIFICATION OF ADDENDUM**

## **ADDENDUM NO. 1**

**DATED 4/01/2008**

<b>Control</b>	<b>6174-17-001</b>
<b>Project</b>	<b>RMC - 617417001</b>
<b>Highway</b>	<b>SH0071</b>
<b>County</b>	<b>TRAVIS</b>

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: RMC - 617417001

CONTROL: 6174-17-001

COUNTY: TRAVIS

LETTING: 04/07/2008

REFERENCE NO: 0401

**PROPOSAL ADDENDUMS**

-----  
\_ PROPOSAL COVER  
X BID INSERTS (SH. NO.: Sheet 1 )  
X GENERAL NOTES (SH. NO.: Sheet 1 )  
  
X SPEC LIST (SH. NO.: Sheets 1 and 2 )  
\_ SPECIAL PROVISIONS:  
\_ ADDED:  
  
DELETED:  
  
\_ SPECIAL SPECIFICATIONS:  
\_ ADDED:  
  
DELETED:  
  
\_ OTHER:

DESCRIPTION OF ABOVE CHANGES  
(INCLUDING PLANS SHEET CHANGES)

BID LINE ITEM 666-2096 REFL PAV MRK TY I (W) (WORD) (100 MIL), 68 EA, AT \$125.00 EA, HAS BEEN REPLACED BY ITEM 668-2116 PRE FAB PAV MRK TY C (W) (WORD), 68 EA, ESTIMATED AT \$225.00 EA. THE SPECIAL PROVISION 668-001 HAS BEEN ADDED, REMOVING THE PLAN QUANTITY REQUIREMENT. THE GENERAL NOTES HAVE BEEN REVISED TO ADD: "THIS WORK SHALL BE COMPLETED BY AUGUST 31, 2008." PLAN SHEETS HAVE BEEN EDITED TO REFLECT THESE CHANGES.

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	350	2001	006	MICROSURFACING  DOLLARS and CENTS	TON	110.000	1
	506	2026	010	FRNT END LOADER WORK (ERSN & SEDM CONT)  DOLLARS and CENTS	HR	2.000	2
	506	2034	010	TEMPORARY SEDIMENT CONTROL FENCE  DOLLARS and CENTS	LF	50.000	3
	666	2012	001	REFL PAV MRK TY I (W) 4" (SLD)(100MIL)  DOLLARS and CENTS	LF	3,478.000	4
	668	2002		PREFAB PAV MRK (ACC PRK)(BLU & WHT)LRG  DOLLARS and CENTS	EA	6.000	5
	668	2116	001	PREFAB PAV MRK TY C (W) (WORD)  DOLLARS and CENTS	EA	68.000	6

**County:** TRAVIS**Control:** 6174-17-001**Highway:****Basis of Estimate**

<b>Item</b>	<b>Description</b>	<b>Rate **</b>	<b>Basis</b>	<b>Quantity</b>
350	Microsurfacing	25 LB/SY	8,774 SY	110 TONS

**\*\* For Informational Purposes Only**

Commence work upon the issuance of a work order by the engineer. The working days listed below will rule for the completion of work.

The Contractor will be given written notice to begin work on this project. Begin work within seven (7) calendar days after such notification.

The Contractor will have 15 working days to complete this work.

This work shall be completed by August 31, 2008.

Provide a minimum of 24 hours notice to the Engineer prior to scheduling any work that requires inspection at the plant or the project.

Mobilization for this contract will not be paid for directly but will be considered subsidiary to Item 350.

Provide a minimum of 5 days notice to the facilities manager at Flight Services prior to scheduling any work that requires closing of parking lots or roadways.

Provide an English speaking superintendent to be at the project site at all times during the work.

Perform all work in accordance to standards and specifications found in the plans, or as directed by the Engineer.

Accrue Contract time charges through the Contractor's completion of the final punchlist.

Meet weekly with the Engineer to notify him or her of planned work for the upcoming week.

Equip all construction equipment in roadway work with a permanently mounted 360° revolving or strobe warning light with amber lens. Light will have a minimum lens height and diameter of 5 in. and mounting height of not less than 6 ft. above the roadway surface and be visible from all sides. Attach at each side of the rear end of the construction equipment an approved orange warning flag mounted not less than 6 ft. above the roadway surface.

**County:** TRAVIS**Control:** 6174-17-001**Highway:**

Remove any construction debris and surplus material generated by the construction work within the project limits. Perform this work as directed. Consider subsidiary to the pertinent Items.

Remove all litter within the project location on a daily basis so as to keep the site of the work in a neat and presentable condition at all times. This work will be considered subsidiary to the various bid items.

The quantities of areas to be constructed, as shown in the plans, are approximate and may need to be adjusted in the field, as directed by the Engineer.

Protect all areas of the right of way, which are not included in the actual limits of the proposed construction areas from destruction. Exercise care to prevent damage to trees, vegetation, and other natural surroundings. Areas not to be disturbed will be as directed. Restore any area disturbed as a result of the Contractor's operations to a condition as good as, or better than before the beginning of work.

All locations used for storing construction equipment, materials, and stockpiles of any type within the right of way will be as directed. Use of right of way for these purposes will be restricted to those locations where driver sight distance to businesses and side street intersections is not obstructed and at other locations where an unsightly appearance will not exist.

**Storm Water Pollution Prevention Plan / Water Pollution Abatement Plan (SW3P/WPAP) notes**

In the event that significant contamination is encountered based on odors, visual evidence, or vapor monitoring, immediately contact the Engineer in accordance with Item 4.3 of the general provisions of the standard specifications for construction and maintenance of highways, streets, and bridges. The Engineer may suspend work wholly or in part to determine the coordination/management for the testing, removal and disposal of hazardous materials that might be necessary according to all applicable rules, laws and regulations.

Restrict construction vehicles from traversing or utilizing existing roadways, unprotected construction areas, and areas with vegetative cover.

Maintain vehicles at designated maintenance sites, unless otherwise approved.

Transport any soils contaminated during construction of the proposed project from the site and properly dispose of off-site, off the recharge zone, and off any area draining to the recharge zone of the Edwards Aquifer.

Collect wastewater generated on-site by chemical toilets and transport off the recharge zone and dispose of properly.

**County:** TRAVIS**Control:** 6174-17-001**Highway:**

Locate above-ground storage tanks kept on-site for construction purposes over bermed impervious liners as to not allow any leakage into underlying soils. Additionally, the containment shall be sized to capture 150% of the total volume of fluids stored on-site within the storage area.

**ITEM 350 - Microsurfacing**

Do not perform work on this item when the weather, as indicated by National Oceanic and Atmospheric Administration (NOAA), states a Chance of Rain of 40% or Greater.

Fill ruts, utility cuts, and depressions in the existing surface in a separate pass from the final surface.

**ITEM 502 - Barricades, Signs, and Traffic Handling**

Place one TY III Barricade 8 ft. at each stockpile of material that is placed on the right of way and is located within 30 ft. of the traveled way.

Maintain access to all streets and driveways at all times, unless otherwise approved. Consider subsidiary to the pertinent Items.

Repair barricades 48 hours after barricade report has been delivered to the Contractor. Repair barricades to the satisfaction of the Engineer. Failure to comply will cause all work to cease.

**ITEM 506 - Temporary Erosion, Sedimentation, and Environmental Controls**

Obtain the Engineer's approval for proposed methods used for erosion control before starting each phase of construction.

Consider the SW3P for this project to consist of the following items as directed:

Temporary Sediment Control Fence

**ITEM 666 - Reflectorized Pavement Markings**

Apply Type I Reflectorized Pavement Markings at least 7 days after applying the final surface course, unless otherwise directed.

Reference existing channel islands, gores, and lane striping before commencing work. Provide referencing that will include a sketch of the layout to the Engineer. Obtain approval for placement of guidemarks from the Engineer before installing any permanent pavement markings. Consider subsidiary to the pertinent Items.

**County:** TRAVIS

**Control:** 6174-17-001

**Highway:**

**ITEM 5010 - Transportable Cellular Telephones**

Furnish the inspector with 1 cellular phone small enough to carry on a belt holster. Obtain the Engineer's approval for the proposed cellular phone service plan before putting it into service. Consider subsidiary to the pertinent Items.

Plans for this contract are available for review at the following location:

Texas Department of Transportation  
Austin District Office  
7901 N. IH 35, Building No. 2  
Austin, Texas 78753

The TxDOT contact person is Rosie Beck at 512-832-7057 or Becky Smith at 512-832-7131.

CONTROL : 6174-17-001  
PROJECT : RMC - 617417001  
HIGHWAY : SH0071  
COUNTY : TRAVIS

TEXAS DEPARTMENT OF TRANSPORTATION

**GOVERNING SPECIFICATIONS AND SPECIAL PROVISIONS**

ALL SPECIFICATIONS AND SPECIAL PROVISIONS APPLICABLE TO THIS PROJECT  
ARE IDENTIFIED AS FOLLOWS:

STANDARD SPECIFICATIONS: ADOPTED BY THE TEXAS DEPARTMENT OF  
----- TRANSPORTATION JUNE 1, 2004.  
STANDARD SPECIFICATIONS ARE INCORPORATED  
INTO THE CONTRACT BY REFERENCE.

ITEMS 1 TO 9 INCL., GENERAL REQUIREMENTS AND COVENANTS  
ITEM 350 MICROSURFACING (300)<500><502>(520)  
ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL  
CONTROLS  
ITEM 666 REFLECTORIZED PAVEMENT MARKINGS (316) (318) (662) (677) (678)  
ITEM 668 PREFABRICATED PAVEMENT MARKINGS

SPECIAL PROVISIONS: SPECIAL PROVISIONS WILL GOVERN AND TAKE  
----- PRECEDENCE OVER THE SPECIFICATIONS ENUMERATED  
HEREON WHEREVER IN CONFLICT THEREWITH.

SPECIAL PROVISION "SCHEDULE OF LIQUIDATED DAMAGES" (000--1002)  
SPECIAL PROVISION "DEPARTMENT DIVISION MAILING AND PHYSICAL ADDRESS"  
(000---011)  
SPECIAL PROVISION TO ITEM 1 (001---005)  
SPECIAL PROVISION TO ITEM 3 (003---023)  
SPECIAL PROVISION TO ITEM 4 (004---012)  
SPECIAL PROVISION TO ITEM 5 (005---004)  
SPECIAL PROVISION TO ITEM 6 (006---030)  
SPECIAL PROVISIONS TO ITEM 7 (007---213) (007---297)  
SPECIAL PROVISIONS TO ITEM 9 (009---012) (009---015)  
SPECIAL PROVISION TO ITEM 350 (350---006)  
SPECIAL PROVISION TO ITEM 500 (500---004)  
SPECIAL PROVISIONS TO ITEM 502 (502---006) (502---033)  
SPECIAL PROVISION TO ITEM 506 (506---010)  
SPECIAL PROVISION TO ITEM 666 (666---001)  
SPECIAL PROVISION TO ITEM 668 (668---001)



SPECIAL SPECIFICATIONS:

-----

GENERAL: THE ABOVE-LISTED SPECIFICATION ITEMS ARE THOSE UNDER WHICH  
----- PAYMENT IS TO BE MADE. THESE, TOGETHER WITH SUCH OTHER  
PERTINENT ITEMS, IF ANY, AS MAY BE REFERRED TO IN THE ABOVE-  
LISTED SPECIFICATION ITEMS, AND INCLUDING THE SPECIAL  
PROVISIONS LISTED ABOVE, CONSTITUTE THE COMPLETE SPECIFI-  
CATIONS FOR THIS PROJECT.