

# NOTIFICATION OF ADDENDUM

## ADDENDUM NO. 1

**DATED 5/20/2016**

<b>Control</b>	<b>6300-06-001</b>
<b>Project</b>	<b>RMC - 630006001</b>
<b>Highway</b>	<b>IH0027</b>
<b>County</b>	<b>LUBBOCK</b>

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: RMC - 630006001

CONTROL: 6300-06-001

COUNTY: LUBBOCK

LETTING: 05/27/2016

REFERENCE NO: 0520

**PROPOSAL ADDENDUMS**

-----

PROPOSAL COVER

BID INSERTS (SH. NO.:

X GENERAL NOTES (SH. NO.: General Notes 2-2D

SPEC LIST (SH. NO.:

SPECIAL PROVISIONS:

ADDED:

DELETED:

SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

OTHER:

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

**GENERAL NOTES:**

**General Requirements and Covenants - Items 1 thru 9**

**Project Description** – This project consists of cleaning and sweeping, Spur 327, LP 289, US 62 and IH 0027 in Lubbock, Hale and Swisher Counties.

**TxDOT Project Supervisor** – The project will be managed

by: Will Barnett, P.E.

135 Slaton Road

Lubbock, TX 79404-5201

PH (806) 748-4496

Fax (806) 748-4381

**Contract Prosecution** - Each contract awarded by the Department stands on its own and as such, is separate from other contracts. A contractor awarded multiple contracts, must be capable and sufficiently staffed to concurrently process any or all contracts at the same time.

**Item 2 – Instructions to Bidders**

View the plans on-line or download from the web at:

<http://www.dot.state.tx.us/business/plansonline/plansonline.htm>

Order plans from any of the plan reproduction companies shown on the web at:

[http://www.dot.state.tx.us/business/contractors\\_consultants/repro\\_companies.htm](http://www.dot.state.tx.us/business/contractors_consultants/repro_companies.htm)

By signing this proposal, a bidder acknowledges that he/she has a copy of the “Standard Specifications for Construction of Highways, Streets and Bridges”, adopted by the Texas Department of Transportation, November 1, 2014. This specification book may be purchased from the Department.

This project includes plan sheets that are not part of the bid proposal.

**Item 3 – Award and Execution of Contract**

This contract will be a 216 working day project. No further work will be performed after this date, unless mutually agreed between the contractor and the department.

This Contract includes work required under multiple work orders. TxDOT will determine the state dates and will issue the work orders accordingly. Time requirements for each work order will be:

- 24 days per quarterly cycle for type A, B, C and D in Lubbock (outside the city), Hale and Swisher Counties

- 15 days per monthly cycle for type A and B sweeping only in Lubbock city limits

Failure to complete the work within the number of working days for each work order will result in liquidated damages as in accordance with Article 8.6

Each cycle stand alone as to the number of working days allowed for that cycle.

**Item 7 – Legal Relations and Responsibilities**

Dispose of all waste materials in compliance with local, state and federal regulations. Submit a list of all approved waste sites to the Engineer for review.

Provide copies of all weight tickets showing the landfill and amount of material dumped to the Engineer up on request. Dumping fees will be considered subsidiary to the various items of this contract.

**Item 8 - Prosecution and Progress**

Monthly schedule updates are a very important aspect of managing the progress of this project. The Engineer may withhold the monthly estimate if the schedule update has not been received.

Working days will be computed and charged in accordance with Article 8.3.1.4 standard Workweek.

Work on this contract will not be continuous and will be accomplished at the direction of the Engineer.

Peak Hours		Off-Peak Hours	
7 to 9 AM Monday through Friday	4 to 6 PM Monday through Friday	9AM to 4PM and 6 PM to 7 AM Monday through Friday	All day Saturday and Sunday

Work is allowed to be performed during the nighttime, with Engineer’s approval. Work that interferes with traffic is required to be performed during off-peak hours, 6:00 pm until 7:00 am. If agreed upon in writing by both parties to the contract, the contract may be extended for an additional period of time not exceed the original contract time period. The extended contract

will be for the original bid quantities, terms and conditions plus any approved change orders.

The original execution date of the contract will be used as the base month.

When the contract is extended by agreement of both parties, provide a Performance Bond, if required and payment Bond in the amount of the extension before the additional work begins.

Notify the inspector and each section 24 hours prior to beginning operations on roadways maintained by that section.

Do not perform sweeping operations after 5:00 pm Friday afternoon without permission from TxDOT. Request for Saturday work must be made no later than Thursday at 5:00 pm. Under no circumstances will the contractor be allowed to perform work from 6:00 pm Saturday through 6:00 pm Sunday.

Designate an on-site representative who will have full authority to speak and make decisions on the behalf of the contractor. Provide the telephone number of the contractor and his representative the Engineer at the pre-work meeting.

### **Item 500 - Mobilization**

For this project mobilization will be subsidiary to the various bid items.

### **Item 502 - Barricades, Signs And Traffic Handling**

For this project, Barricades, Signs, and Traffic Handling will be subsidiary to the various bid items.

Furnish and install all signs, barricades and other incidentals necessary for proper traffic control in accordance with part VI of the "Texas Manual on Uniform Traffic Control Devices for Streets and Highways" and barricade and construction standard sheets. Additional signs and barricades as directed by the Engineer will be considered subsidiary to various bid items.

Provide shadow vehicles equipped with Truck Mounted Attenuators (TMA) as shown on Traffic Control Plan (TCP) standards.

TMA's used for this project shall comply with requirements found in the Complaint Work Zone Traffic Control Devices list, which can be found at the following website.

<http://www.txdot.gov/business/resources/materials/producer-list.html>

**Item 738 – Cleaning and Sweeping Highways**

Provide shadow vehicles with truck mounted or trailer attenuators behind sweepers at all times.

Use water at all times during sweeping operations. Furnish water that is free from oils, acids, and organic matter, or other deleterious substances. The costs for supplying water will not be paid for directly but will be considered subsidiary to the various bid items.

Remove all debris from the sweeping path, by any method necessary. Refer to the 2014 Spec book Item 738 for definition of debris. This work will not be paid for directly, but will be considered subsidiary to the bid items.

Do not dump or stock-pile debris on the right of way.

Clean and sweep all roads listed in the plans according to the following schedule:

<b>Monthly</b>	<b>Quarterly</b>
Tracts 1-11	Tracts 12 - 50

A work order will be issued for each cycles of cleaning and sweeping. The tract numbers to be swept will be listed in the work order.

Handwork will be used as determined by the Engineer, but not for debris removal. A separate work order will be executed for handwork.

**Project Number: RMC 630006001**

**County: Lubbock**

**Highway: IH 0027**

**Sheet 2**

**Control: 6300-06-001**

This page intentionally left blank.