# NOTIFICATION OF ADDENDUM ADDENDUM NO. 1 DATED 5/16/2012

6242-53-001
RMC - 624253001
LP0375
EL PASO

### Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an adendum notification which details the changes and the respective proposal pages which were added and/ or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

```
SUBJECT: PLANS AND PROPOSAL ADDENDUMS
      PROJECT: RMC - 624253001 CONTROL: 6242-53-001
      COUNTY: EL PASO
      LETTING: 05/21/2012
      REFERENCE NO: 0516
                         PROPOSAL ADDENDUMS
  PROPOSAL COVER
X BID INSERTS (SH. NO.: 1 - 1
X GENERAL NOTES (SH. NO.: 2B - 2D
_ SPEC LIST (SH. NO.:
_ SPECIAL PROVISIONS:
  ADDED:
      DELETED:
_ SPECIAL SPECIFICATIONS:
  ADDED:
      DELETED:
X OTHER: PLAN SHEETS 3 AND 4
DESCRIPTION OF ABOVE CHANGES
```

)

1-1

(INCLUDING PLANS SHEET CHANGES)

	ITEM-CODE							DEPT
ALT	ITEM NO	DESC CODE	S.P. NO.	UNIT BID PRICE ONLY. WRITTEN IN WORDS		UNIT	APPROX QUANTITIES	USE ONLY
	500	2001		MOBILIZATION and	DOLLARS CENTS	LS	1.000	1
	502	2001		BARRICADES, SIGNS AND TRADLING and	FFIC HAN- DOLLARS CENTS	МО	3.000	2
	644	2001		IN SM RD SN SUP&AM TY10BW	VG(1)SA(P) DOLLARS CENTS	EA	148.000	3
	644	2060		REMOVE SM RD SN SUP & AM and	DOLLARS CENTS	EA	148.000	4

Project Number: RMC 6242-53-001 Highway: LP 375

County: El Paso Control: 6242-53-001

### **GENERAL NOTES:**

IF THE BIDDER HAS ANY QUESTIONS CONCERNING THE PREPARATION AND SUBMISSION OF THE PROPOSAL FORMS, CONTACT:

TEXAS DEPARTMENT OF TRANSPORTATION MONICA DUBRULE, CONTRACT MANAGER 13301 GATEWAY BLVD. WEST EL PASO, TEXAS 79924 (915) 790-4367

IF THE BIDDER HAS ANY QUESTIONS CONCERNING THE SPECIFICATION OF WORK REQUIREMENTS OF THE CONTRACT CONTACT:

TEXAS DEPARTMENT OF TRANSPORATION GUILLERMO GARCIA, P.E. 13301 GATEWAY BLVD. WEST EL PASO, TEXAS (915) 790-4385

EACH COMPLETED PROPOSAL SHALL BE PLACED, TOGETHER WITH THE PROPOSAL GUARANTY OR BID BOND, IN A SEALED ENVELOPE WITH EACH PROPOSAL SO MARKED AS TO INDICATE ITS CONTENTS. WHEN SUBMITTED BY MAIL, THIS ENVELOPE SHALL BE ADDRESSED TO:

TEXAS DEPARTMENT OF TRANSPORTATION ATTN: MONICA DUBRULE 13301 GATEWAY BLVD. WEST EL PASO, TEXAS 79928

PROPOSALS WILL BE ACCEPTED AT THE TEXAS DEPARTMENT OF TRANSPORTATION EL PASO DISTRICT HEADQUARTERS AT 13301 GATEWAY WEST BLVD., EL PASO, TEXAS, UNTIL 1:30 P.M., MAY 21, 2012, THEN PUBLICLY OPENED AND READ PRIOR TO THE CLOSING OF BUSINESS ON THE SAME DATE.

A BID SUMMATION WILL BE AVAILABLE VIA TELEPHONE BY CONTACTING THE EL PASO MAINTENANCE MANAGEMENT OFFICE AT (915) 790-4367.

## **GENERAL**

THE WORK WILL CONSIST OF THE REFURBISHMENT AND INSTALLATION OF GROUND MOUNTED SIGNS.

UPON COMPLETION OF THE WORK, OR AT TIMES DESIGNATED BY THE ENGINEER, CLEAN AND REMOVE ALL EXCESS DIRT AND ALL RUBBISH FROM THE LOCATION, GENERATED BY THIS CONTRACT. RESTORE ALL PUBLIC AND PRIVATE PROPERTY DAMAGED DURING THE PROSECUTION OF THE WORK IN A MANNER ACCEPTABLE TO THE ENGINEER. LEAVE EACH WORK SITE IN A NEAT AND PRESENTABLE CONDITION THROUGHOUT THE DURATION OF THE CONTRACT.

Project Number: RMC 6242-53-001 Highway: LP 375

County: El Paso Control: 6242-53-001

## ITEM 7 - LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC

PRESERVE ALL LANDSCAPING.

## **ITEM 8 - PROSECUTION AND PROGRESS**

## PROJECT CONTRACT TIME FOR COMPLETION

THIS PROJECT IS TO BE COMPLETED BY AUGUST 31, 2012 AND WILL BE ACCEPTED WHEN FULLY COMPLETED AND FINISHED TO THE SATISFACTION OF THE ENGINEER. THE CONTRACTOR WILL BE REQUIRED TO MOBILIZE, ORDER SIGN FABRICATION, ETC., IMMEDIATELY UPON ISSUANCE OF WORK ORDER IN ORDER TO COMPLETE WORK BY AUGUST 31, 2012.

SUBMIT A PROPOSED SEQUENCE OF CONSTRUCTION FOR APPROVAL UPON ISSUANCE OF A WORK ORDER. A BAR CHART WILL BE ACCEPTABLE. NO CHANGES WILL BE PERMITTED IN THE APPROVED SEQUENCE, EXCEPT, AS APPROVED IN WRITING.

WORKING DAYS SHALL BE COMPUTED AND CHARGED IN ACCORDANCE TO ARTICLE 8.3.A.2.

## ITEM 9 - MEASUREMENT AND PAYMENT

SUBMIT MATERIAL-ON-HAND PAYMENT REQUESTS AT LEAST THREE WORKING DAYS BEFORE THE END OF THE MONTH FOR PAYMENT CONSIDERATION ON THAT MONTH'S ESTIMATE

# ITEM 502 - BARRICADES, SIGNS AND TRAFFIC HANDLING

FURNISH AND INSTALL ALL SIGNS, BARRICADES AND OTHER INCIDENTALS NECESSARY FOR PROPER TRAFFIC CONTROL, IN ACCORDANCE WITH PART 6 OF THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AND IN ACCORDANCE WITH THE STANDARD PLAN SHEETS. ADDITIONAL DEVICES MAY BE NEEDED TO SUPPLEMENT THESE REQUIREMENTS. ALL WARNING SIGNS SHALL BE FACTORY MADE AND IN SATISFACTORY CONDITION.

THE G20-1 W/PLAQUE OR G20-5T ALONG WITH THE G20-6 CONTRACTOR'S NAME SIGN SHALL BE LOCATED AT OR NEAR THE PROJECT LIMITS AND WILL REMAIN IN POSITION FOR THE DURATION OF THE PROJECT EVEN THOUGH CERTAIN OTHER ADVANCE WARNING SIGNS, ETC., WILL BE REPOSITIONED, REMOVED, OR COVERED WITHIN THE PROJECT LIMITS AS CONSTRUCTION NECESSITATES OR AS DIRECTED.

MAINTAIN SHOULDERS AND MEDIAN AREAS IN A CONDITION CAPABLE OF SERVING AS EMERGENCY PATHS AS APPROVED. THIS WORK WILL BE SUBSIDIARY TO THIS ITEM.

LANE CLOSURES WILL NOT BE ALLOWED BETWEEN 7 AM AND 9 AM AND 4 PM AND 6 PM, UNLESS OTHERWISE DIRECTED IN WRITING.

WHEN A TRAFFIC CONTROL PLAN (TCP) STANDARD REQUIRES THE USE OF ONE OF THE FOLLOWING DEVICES, A TYPE III BARRICADES, CHANNELIZING DEVICES OR SHADOW VEHICLE WITH ORANGE FLAGS OR WARNING LIGHTS, USE A SHADOW VEHICLE EQUIPPED WITH A TRUCK MOUNTED ATTENUATOR (TMA).

FOR ADDITIONAL INFORMATION PERTAINING TO CHANNELIZATION, SIGNING, SPACING DETAILS AND FLAGGING PROCEDURES REQUIRED TO REGULATE, WARN AND GUIDE TRAFFIC THROUGH PROJECT, REFER TO THE "BARRICADE AND CONSTUCTION STANDARDS" AND TO THE CURRENT "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES."

General Notes Sheet 2A General Notes Sheet 2B

Project Number: RMC 6242-53-001 Highway: LP 375

County: El Paso Control: 6242-53-001

ERACT TEMPORARY TRAFFIC CONTROL SIGNS IN LOCATIONS THAT WILL NOT OBSTRUCT THE TRAVELING PUBLIC'S VIEW OF THE PERMANENT ROADWAY SIGNING OR OBSTRUCT SIGHT DISTANCE AT INTERSECTIONS AND CURVES.

REMOVE OR COVER SIGNS THAT DO NOT APPLY AT THE END OR EACH DAY'S WORK.

ALL LANE CLOSURES MUST FOLLOW TXDOT STANDARDS AND THE TXMUTCD.

## ITEM 636 – ALUMINUM SIGNS

ALL WARNINGS SIGNS MUST USE TYPE E (FLUORESCENT PRISMATIC) SHEETING CONFORMING TO DMS-8300.

ALL SIGNS LISTED IN THE SMALL SIGNS SUMMARY IS AN ESTIMATE OF THE NUMBER OF SIGN TYPES ONLY. MULTIPLE SIGNS WILL BE MOUNTED ON A SINGLE POST IN WHICH THE CONTRACTOR WILL HAVE TO MATCH THE NEW SIGNS TO THE EXISTING SIGNS, UNLESS OTHER WISE SPECIFIED ON THE LOCATION MAP NOTES COLUMN.

THE INSTALLATION OF ALL PROPOSED SIGNS SHALL MATCH EXISTING MINIMUM CLEARANCE FROM THE PROJECTED EDGE OF PAVEMENT TO THE BOTTOM OF SIGN. FLASHER ASSEMBLIES THAT CAN NOT ACOMMODATE THE SIGN SIZE SPECIFIED CAN USE A SMALLER SIGN. IN EITHER CASE, THE CONTRACTOR MUST NOTIFY THE ENGINEER FOR APPROVAL. THE INSTALLATION OF ALL PROPOSED SIGNS SHALL CONFORM TO TXDOT STANDARDS AND THE CURRENT TEXAS MUTCD.

FOR STANDARD SMALL SIGN DETAILS ANS DIMNESIONS REFER TO THE "STANDARD HIGHWAYS SIGN DESIGNS FOR TEXAS (SHSD), A SUPPLEMENT TO THE TEXAS MANUEL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD)".

EXISTING SIGNS MAY NOT BE REMOVED UNTIL THE PROPOSED SIGNS HAVE BEEN INSTALLED.

ALL MATERIAL REMOVED WILL BECOME THE CONTRACTOR'S PROPERTY UNLESS OTHERWISE SPECIFIED BY THE ENGINEER.

## ITEM 644 – "SMALL ROADSIDE SIGN SUPPORTS AND ASSEMBLIES"

REMOVAL AND INSTALLATION OF MULTIPE SIGNS ON A POST WILL BE SUBSIDIARY TO THE ITEM, "SMALL ROADSIDE SIGN SUPPORTS AND ASSEMBLIES".

FOR ANY SIGN SUPPORT AND ASSEMBLY THAT HAS A REFERENCE MARKER ATTACHED CAN NOT BE MOVED FROM ITS EXISTING LOCATION. THE EXISTING SIGN SUPPORT AND ASSEMBLY WILL HAVE TO BE REMOVED FIRST TO PLACE THE NEW SIGN SUPPORT AND ASSEMBLY AT THE EXACT LOCATION OF THE EXISTING SIGN.

PROVIDE TEXAS UNIVERSIAL TRIANGULAR SLIP BASE FOR ALL SIGNS

FOR THIS PROJECT, THE CONTRACTOR WILL BE ALLOWED TO USE A PORTABLE, MOTOR DRIVEN CONCRETE MIXER FOR BATCHES OF CONCRETE LESS THAN 2 CUBIC YARDS. FOR SMALL PLACEMENTS LESS THAN 0.5 CUBIC YARDS, THE CONTRACTOR CAN HAND MIX THE CONCRETE IN A SUITABLE CONTAINER. THE CONRETE SHALL BE CLASS A OR A BAGGED CONCRETE PRODUCT MEETING THE REQUIREMENTS OF DMS-4655 FOR TYPE C - GENERAL PURPOSE REPAIRS WITH A MINIMUM 3 – DAY COMPRESSIVE STRENGTH OF 3,600 PSI.

Project Number: RMC 6242-53-001 Highway: LP 375

County: El Paso Control: 6242-53-001

AFTER SIGN SUPPORT WITH SIGNS ATTACHED HAVE BEEN ERECTED, WASH INDIVIDUAL UNITS REQUIRING CLEANING WITH AN APPROVED CLEANING SOLUTION TO REMOVE ALL GREASE, OIL, DIRT, SMEARS, STREAKS AND OTHER FOREIGN PARTICLES.

THE CONTRACTOR MAY ENCOUNTER ROCK DRILLING AT TRANSMOUNTAIN LOCATIONS.

ALL MATERIAL REMOVED WILL BECOME THE CONTRACTOR'S PROPERTY UNLESS OTHERWISE SPECIFIED BY THE ENGINEER.

General Notes Sheet 2C General Notes Sheet 2D

