

NOTIFICATION OF ADDENDUM

ADDENDUM NO. 1

DATED 4/27/2016

Control	2452-01-056, ETC.
Project	C 2452-1-56, ETC.
Highway	SL 1604
County	BEXAR

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: C 2452-1-56

CONTROL: 2452-01-056

COUNTY: BEXAR

LETTING: 05/03/2016

REFERENCE NO: 0426

PROPOSAL ADDENDUMS

X PROPOSAL COVER

X BID INSERTS (SH. NO.: 2-31 THRU 29-31))

X GENERAL NOTES (SH. NO.: A THRU HH))

X SPEC LIST (SH. NO.: 1-4 AND 3-4))

X SPECIAL PROVISIONS:

ADDED: 000---008, 000---009

DELETED: 000---003, 000---004, 000---005, 000---006, 000---007,
000---241

— SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

X OTHER: PLAN SHEET AND OTHER CHANGES

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

NEW SBE GOAL Y

***** PROPOSAL COVER *****

REVISED PROJECT NUMBER

***** BID INSERTS *****

ALL BID INSERTS PROPOSAL SHEETS AND ALL E&Q PLAN SHEETS (15, 15A -15G) ARE BEING REPLACED AS PART OF THIS ADDENDUM

REVISED QUANTITY FOR THE FOLLOWING BID ITEMS 401-6001, 416-6001, 416-6004, 416-6029, 420-6013, 420-6025, 422-6015, 432-6045, 450-6023, 454-6001, 540-6001, 544-6001, 610-6272, 740-6004, AND 4052-6001.

ADDED THE FOLLOWING BID ITEMS: 420-6066, 610-6104 (REPLACES 610-6015 (SAME QUANTITY), 618-6068 (REPLACES 618-6069, SAME QUANTITY)

DELETED FOLLOWING BID ITEM: 7077-6042

**** GENERAL NOTES ****

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

(CONTINUED)

ALL GENERAL NOTES SHEET NOTES HAVE SHIFTED

SHEET A: EXPANDED THE BREAKDOWN BY LOCATION IN THE BASIS OF ESTIMATE FOR ACP

SHEET B: ADDED MODIFIED STANDARD SHEET BAS-A(MOD) TO LIST OF MODIFIED SHEETS

SHEET O: ADDED TY C EMBANKMENT PROPERTIES NOTE TO ITEM 423 NOTES

SHEET X: REVISED FIRST NOTE FOR ITEM 4051 WITH CPS CONTACT INFORMATION AND DE-ENERGIZING TIME FRAME RESTRICTIONS

SHEET Y: ADDED NOTE FOR ITEM 7077 FOR REMOVAL OF AC PIPE

**** SPEC LIST ****

SHEET 1 CHANGE PROJECT NUMBER IN HEADING FROM FEDERAL TO STATE

SHEET 3: REMOVED REQUIRED CONTRACT PROVISIONS, FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273, MAY, 2012), SP 000-003, SP 000-004, SP 000-005, SP 000-006, SP 000-007, AND SP 000-241; ADDED SP 000-008, AND SP 000-009

**** PLAN SHEETS ****

SHEET 0001: REVISED FROM FEDERAL TO STATE TITLE SHEET

SHEET 0002: REVISED STANDARDS FOR SHEETS 219, 220 AND 221

SHEET 0012: UPDATED PAVEMENT DETAIL

SHEETS 14, 14A THRU 14P: REVISED GENERAL NOTES SHEETS; SEE GENERAL NOTE REVISIONS ABOVE FOR REFERENCE TO CHANGES MADE

SHEETS 15, 15A THRU 15G: REVISED E&Q SHEETS; SEE BID TAB ITEM REVISIONS ABOVE FOR REFERENCE TO CHANGES MADE

SHEET 0021: REVISED QUANTITY FOR ITEMS 432-6045, 540-6001 & 544-6001; ADDED ITEMS 450-6023 & 420-6066

SHEET 0023: ADDED ITEMS 420-6066 & 450-6023

SHEET 0024: REVISED QUANTITY FOR ITEMS 740-6004 & 4052-6001

SHEET 0028: REVISED QUANTITY FOR ITEMS 416-6029 & 610-6272; CHANGED ITEM 610-6015 TO 610-6104; CHANGE ITEM 618-6069 TO 618-6068

SHEET 0039C-0039D: REVISED QUANTITY FOR ITEMS 416-6001, 416-6004, 420-6013, 420-6025 & 422-6015

SHEET 0219: REPLACED ACZ(350)-13 WITH TAU-II(N)-16

SHEET 0220: REPLACED ABSORB-14 AND REPLACED WITH TRACC(N)-16
DESCRIPTION OF ABOVE CHANGES (CONTINUED)
(INCLUDING PLANS SHEET CHANGES)

SHEET 0221: REPLACED WZ(RS)-14 WITH WZ(RS)-16

SHEET 0279-0288: ADDED A PATTERN AND LEGEND FOR VEGETATION AND
LIME TREATMENT

SHEET 0289: ADDED A PATTERN AND LEGEND FOR VEGETATION AND LIME TREATMENT;
REVISED QUANTITY FOR ITEMS 432-6045, 540-6001 & 544-6001;
ADDED ITEMS 420-6066 & 450-6023

SHEET 0290: ADDED A PATTERN AND LEGEND FOR VEGETATION AND LIME TREATMENT;
ADDED ITEMS 420-6066 & 450-6023

SHEET 0291: ADDED A PATTERN AND LEGEND FOR VEGETATION AND LIME TREATMENT;
REVISED QUANTITY FOR ITEMS 432-6045, 540-6001 & 544-6001;
ADDED ITEMS 420-6066 & 450-6023

SHEET 0292-0299: ADDED A PATTERN AND LEGEND FOR VEGETATION AND LIME
TREATMENT

SHEET 0463: ADDED DETAIL FOR PLAN VIEW AT FLUSH OPENING

SHEET 0464: UPDATED CALLOUT FOR THE NOTCH OUTS TO SPECIFY RECESSED OR
FLUSHED

SHEET 0465-0468: UPDATED CALLOUT FOR THE NOTCH OUTS TO SPECIFY RECESSED
OR FLUSHED

SHEET 0469: ADDED FLUSH PANEL OPENING DETAILS, MODIFIED DIMENSIONS AT
GRADE BEAM

SHEET 0470: ADDED DETAILS FOR FLUSH WALL PANEL

SHEET 0471: ADDED FIBERGLASS PANEL DETAIL AND MODIFIED DIMENSIONS ON
GRADE BEAM

SHEET 0472: MOVED NOTE 10 FROM SHEET 5 OF 5

SHEET 0473: MODIFIED INCORRECT 8 - #8 TO 12 - #9 VERTICAL REINFORCING
STEEL AND MOVED NOTE TO SOUND WALL GENERAL NOTES

SHEET 0499-0500: ADDED ITEMS 0420-6066 & 450-6023

SHEET 0505: UPDATED NOTE 3 FOR GROUND IMPROVEMENT AND REMOVED
RETAINING WALL G FROM THE LIST OF WALLS

SHEET 0673: REVISED BAS-C TO BAS-A

SHEET 0674: REVISED QUANTITY FOR ITEMS 416-6001, 416-6004 & 422-6015

SHEET 0678: CORRECTED DECK THICKNESS CALLOUT TO 8 1/2"

SHEET 0679: REVISED BAS-C TO BAS-A

DESCRIPTION OF ABOVE CHANGES
(INCLUDING PLANS SHEET CHANGES)

(CONTINUED)

SHEET 0680: REVISED QUANTITY FOR ITEMS 420-6013, 420-6025 & 422-6015

SHEET 0682 & 0684: REVISED ABUTMENT QUANTITY

SHEET 0685: MODIFIED CONCRETE VOLUME FOR H=1FT (CONTRACTOR INFO ONLY)

SHEET 0687: UPDATED 36" DRILL SHAFT QUANTITIES AND REVISED FROM BAS-C TO BAS-A

SHEET 0688: REVISED QUANTITY FOR ITEMS 0416-6001, 420-6013, 420-6025 & 422-6015

SHEET 0690 & 0692: REVISED ABUTMENT QUANTITY

SHEET 0693: MODIFIED CONCRETE VOLUME FOR H=1FT (CONTRACTOR INFO ONLY)

SHEET 0696: REVISED BAS-C TO BAS-A

SHEET 0704: CORRECTED GIRDER NUMBER CALL OUT ON TRANSVERSE SECTION

SHEET 0705: ADDED HILL COUNTRY THEME AESTHETIC DETAILS FOR MILITARY, WISEMAN AND POTRANCO BRIDGES

SHEET 0706: REVISED BAS-C TO BAS-A

SHEET 0714: CORRECTED GIRDER NUMBER CALL OUT ON TRANSVERSE SECTION

SHEET 0715: REVISED BAS-C TO BAS-A

SHEET 0716: ADDED ITEM 0416-6001; REVISED QUANTITY FOR ITEM 0420-6013; CORRECTED SPAN 2 GIRDER LENGTH ON GIRDER REPORT

SHEET 0717-0718: REMOVED 11' CANTILEVER WINGWALL DETAILS, ADDED 16' FOUNDED WINGWALL DETAILS. UPDATED CONCRETE AND REINFORCEMENT QUANTITIES FOR THE LONGER WINGWALLS

SHEET 0719: ADDED HILL COUNTRY THEME AESTHETIC DETAILS FOR MILITARY, WISEMAND AND POTRANCO BRIDGES

SHEET 0721: REVISED BAS-C TO BAS-A

SHEET 0722: ADDED ITEM 0416-6001; REVISED QUANTITY FOR ITEM 0420-6013; CORRECTED SPAN 2 GIRDER LENGTH ON GIRDER REPORT

SHEET 0723-0724: REMOVED 11' CANTILEVER WINGWALL DETAILS, ADDED 16' FOUNDED WINGWALL DETAILS. UPDATED CONCRETE AND REINFORCEMENT QUANTITIES FOR THE LONGER WINGWALLS

SHEET 0725: ADDED HILL COUNTRY THEME AESTHETIC DETAILS FOR MILITARY,
WISEMAND AND POTRANCO BRIDGES

SHEET 0727: REVISED BAS-C TO BAS-A

SHEET 0728: ADDED ITEM 0416-6001; REVISED QUANTITY FOR ITEMS 416-6004 &
DESCRIPTION OF ABOVE CHANGES (CONTINUED)
(INCLUDING PLANS SHEET CHANGES)

420-6013

SHEET 0729-0732: REMOVED 11' CANTILEVER WINGWALL DETAILS,
ADDED 16' FOUNDED WINGWALL DETAILS. UPDATED CONCRETE AND REINFORCEMENT
QUANTITIES FOR THE LONGER WINGWALLS

SHEET 0735: REVISED BAS-C TO BAS-A

SHEET 0736: ADDED ITEM 0416-6001; REVISED QUANTITY FOR ITEMS 416-6004 &
420-6013

SHEET 0737-0740: REMOVED 11' CANTILEVER WINGWALL DETAILS;
ADDED 16' FOUNDED WINGWALL DETAILS. UPDATED CONCRETE AND REINFORCEMENT
QUANTITIES FOR THE LONGER WINGWALLS

SHEET 0775: REPLACED BAS-A WITH BAS-A (MOD)

SHEET 0931-0947: REVISED QUANTITY SUMMARY BOX WITH CORRECT BID ITEMS

SHEET 1014: ADDED BID ITEM 0401-6001

Control	2452-01-056, ETC.
Project	C 2452-1-56, ETC.
Highway	SL 1604
County	BEXAR

PROPOSAL TO THE TEXAS TRANSPORTATION COMMISSION

2014 SPECIFICATIONS

WORK CONSISTING OF GRADE, STRUCTURES, BASE, SURFACE & SIGN BEXAR COUNTY, TEXAS

The quantities in the proposal are approximate. The quantities of work and materials may be increased or decreased as considered necessary to complete the work as planned and contemplated.

This project is to be completed in 751 working days and will be accepted when fully completed and finished to the satisfaction of the Executive Director or designee.

Provide a proposal guaranty in the form of a Cashier's Check, Teller's Check (including an Official Check) or Bank Money Order on a State or National Bank or Savings and Loan Association, or State or Federally chartered Credit Union made payable to the Texas Transportation Commission in the following amount:

ONE HUNDRED THOUSAND (Dollars) (\$100,000)

A bid bond may be used as the required proposal guaranty. The bond form may be detached from the proposal for completion. The proposal may not be disassembled to remove the bond form. The bond must be in accordance with Item 2 of the specifications.

Any addenda issued amending this proposal and/or the plans that have been acknowledged by the bidder, become part of this proposal.

By signing the proposal the bidder certifies:

1. the only persons or parties interested in this proposal are those named and the bidder has not directly or indirectly participated in collusion, entered into an agreement or otherwise taken any action in restraint of free competitive bidding in connection with the above captioned project.
2. in the event of the award of a contract, the organization represented will secure bonds for the full amount of the contract.
3. the signatory represents and warrants that they are an authorized signatory for the organization for which the bid is submitted and they have full and complete authority to submit this bid on behalf of their firm.
4. that the certifications and representations contained in the proposal are true and accurate and the bidder intends the proposal to be taken as a genuine government record.

• **Signed:** **

(1) _____ (2) _____ (3) _____

Print Name:

(1) _____ (2) _____ (3) _____

Title:

(1) _____ (2) _____ (3) _____

Company:

(1) _____ (2) _____ (3) _____

- Signatures to comply with Item 2 of the specifications.

**Note: Complete (1) for single venture, through (2) for joint venture and through (3) for triple venture.

* **When the working days field contains an asterisk (*) refer to the Special Provisions and General Notes.**

NOTICE TO CONTRACTORS

ANY CONTRACTORS INTENDING TO BID ON ANY WORK TO BE AWARDED BY THIS DEPARTMENT MUST SUBMIT A SATISFACTORY “AUDITED FINANCIAL STATEMENT” AND “EXPERIENCE QUESTIONNAIRE” AT LEAST TEN DAYS PRIOR TO THE LETTING DATE.

UNIT PRICES MUST BE SUBMITTED IN ACCORDANCE WITH ITEM 2 OF THE STANDARD SPECIFICATIONS OR SPECIAL PROVISION TO ITEM 2 FOR EACH ITEM LISTED IN THIS PROPOSAL.

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	100	6002		PREPARING ROW DOLLARS and CENTS	STA	213.000	1
	104	6009		REMOVING CONC (RIPRAP) DOLLARS and CENTS	SY	1,499.000	2
	110	6001		EXCAVATION (ROADWAY) DOLLARS and CENTS	CY	152,588.000	3
	110	6002		EXCAVATION (CHANNEL) DOLLARS and CENTS	CY	9,354.000	4
	132	6003		EMBANKMENT (FINAL)(ORD COMP)(TY B) DOLLARS and CENTS	CY	935,618.000	5
	161	6017		COMPOST MANUF TOPSOIL (4") DOLLARS and CENTS	SY	349,204.000	6
	164	6039		DRILL SEEDING (PERM) (URBAN) (CLAY) DOLLARS and CENTS	SY	349,204.000	7
	164	6051		DRILL SEED (TEMP)(WARM OR COOL) DOLLARS and CENTS	SY	158,497.000	8
	168	6001		VEGETATIVE WATERING DOLLARS and CENTS	MG	5,449.000	9
	247	6053		FL BS (CMP IN PLC)(TYD GR1-2)(FNAL POS) DOLLARS and CENTS	CY	87,000.000	10
	260	6002		LIME (HYDRATED LIME (SLURRY)) DOLLARS and CENTS	TON	3,848.000	11
	260	6011		LIME TRT (EXST MATL) (12") DOLLARS and CENTS	SY	96,621.000	12

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	310	6009		PRIME COAT (MC-30) DOLLARS and CENTS	GAL	75,323.000	13
	316	6029		ASPH (RC-250) DOLLARS and CENTS	GAL	115,847.000	14
	316	6193		AGGR(TY-D GR-5 SAC-B) DOLLARS and CENTS	CY	3,928.000	15
	341	6010		D-GR HMA TY-B PG70-22 DOLLARS and CENTS	TON	10,289.000	16
	341	6028		D-GR HMA TY-C PG70-22 DOLLARS and CENTS	TON	56,281.000	17
	341	6041		D-GR HMA TY-D SAC-A PG70-22 DOLLARS and CENTS	TON	42,522.000	18
	354	6045		PLANE ASPH CONC PAV (2") DOLLARS and CENTS	SY	129,994.000	19
	400	6005		CEM STABIL BKFL DOLLARS and CENTS	CY	1,399.800	20
	400	6006		CUT & RESTORING PAV DOLLARS and CENTS	SY	584.000	21
	401	6001		FLOWABLE BACKFILL DOLLARS and CENTS	CY	1,524.000	22
	402	6001		TRENCH EXCAVATION PROTECTION DOLLARS and CENTS	LF	8,009.000	23
	403	6001		TEMPORARY SPL SHORING DOLLARS and CENTS	SF	19,777.000	24

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	416	6001		DRILL SHAFT (18 IN) DOLLARS and CENTS	LF	1,792.000	25
	416	6003		DRILL SHAFT (30 IN) DOLLARS and CENTS	LF	1,988.000	26
	416	6004		DRILL SHAFT (36 IN) DOLLARS and CENTS	LF	5,590.000	27
	416	6005		DRILL SHAFT (42 IN) DOLLARS and CENTS	LF	80.000	28
	416	6006		DRILL SHAFT (48 IN) DOLLARS and CENTS	LF	1,616.000	29
	416	6008		DRILL SHAFT (60 IN) DOLLARS and CENTS	LF	500.000	30
	416	6015		DRILL SHAFT (NON - REINFORCED) (12 IN) DOLLARS and CENTS	LF	98.000	31
	416	6018		DRILL SHAFT (SIGN MTS) (24 IN) DOLLARS and CENTS	LF	13.000	32
	416	6022		DRILL SHAFT (SIGN MTS) (48 IN) DOLLARS and CENTS	LF	40.000	33
	416	6029		DRILL SHAFT (RDWY ILL POLE) (30 IN) DOLLARS and CENTS	LF	980.000	34
	416	6031		DRILL SHAFT (TRF SIG POLE) (30 IN) DOLLARS and CENTS	LF	33.000	35
	416	6032		DRILL SHAFT (TRF SIG POLE) (36 IN) DOLLARS and CENTS	LF	195.000	36

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	420	6003		CL A CONC (MISC) DOLLARS and CENTS	SY	20.000	37
	420	6013		CL C CONC (ABUT) DOLLARS and CENTS	CY	631.600	38
	420	6025		CL C CONC (BENT) DOLLARS and CENTS	CY	972.800	39
	420	6037		CL C CONC (COLUMN) DOLLARS and CENTS	CY	346.000	40
	420	6066		CL C CONC (RAIL FOUNDATION) DOLLARS and CENTS	CY	1,398.000	41
	422	6001		REINF CONC SLAB DOLLARS and CENTS	SF	134,400.000	42
	422	6013		BRIDGE SIDEWALK DOLLARS and CENTS	SF	1,680.000	43
	422	6015		APPROACH SLAB DOLLARS and CENTS	CY	834.400	44
	423	6001		RETAINING WALL (MSE) DOLLARS and CENTS	SF	52,526.000	45
	423	6003		RETAINING WALL (TEMP WALL) DOLLARS and CENTS	SF	55,791.000	46
	423	6005		RETAINING WALL (SPREAD FOOTING) DOLLARS and CENTS	SF	4,748.000	47
	425	6035		PRESTR CONC GIRDER (TX28) DOLLARS and CENTS	LF	2,623.500	48

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	425	6036		PRESTR CONC GIRDER (TX34) and DOLLARS CENTS	LF	3,816.640	49
	425	6038		PRESTR CONC GIRDER (TX46) and DOLLARS CENTS	LF	15,316.380	50
	427	6002		CONCRETE PAINT FINISH and DOLLARS CENTS	SF	14,495.000	51
	432	6001		RIPRAP (CONC)(4 IN) and DOLLARS CENTS	CY	1,753.000	52
	432	6002		RIPRAP (CONC)(5 IN) and DOLLARS CENTS	CY	1,242.000	53
	432	6006		RIPRAP (CONC)(CL B) and DOLLARS CENTS	CY	11.250	54
	432	6033		RIPRAP (STONE PROTECTION)(18 IN) and DOLLARS CENTS	CY	1,831.000	55
	432	6045		RIPRAP (MOW STRIP)(4 IN) and DOLLARS CENTS	CY	328.000	56
	442	6007		STR STEEL (MISC NON - BRIDGE) and DOLLARS CENTS	LB	400.000	57
	442	6008		STR STEEL (MISCELLANEOUS BRIDGE) and DOLLARS CENTS	LB	2,272.000	58
	450	6006		RAIL (TY T223) and DOLLARS CENTS	LF	521.000	59
	450	6023		RAIL (TY SSTR) and DOLLARS CENTS	LF	14,219.000	60

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	450	6024		RAIL (TY SSTR)(HPC) DOLLARS and CENTS	LF	14.000	61
	450	6032		RAIL (TY C223) DOLLARS and CENTS	LF	863.000	62
	450	6062		RAIL (TY SSTR)(MOD) DOLLARS and CENTS	LF	80.000	63
	454	6001		SEALED EXPANSION JOINT (4 IN) (SEJ - A) DOLLARS and CENTS	LF	885.360	64
	459	6006		GABION MATTRESSES (GALV)(9 IN) DOLLARS and CENTS	SY	185.000	65
	460	6002		CMP (GAL STL 18 IN) DOLLARS and CENTS	LF	26.000	66
	462	6007		CONC BOX CULV (5 FT X 3 FT) DOLLARS and CENTS	LF	369.000	67
	462	6008		CONC BOX CULV (5 FT X 4 FT) DOLLARS and CENTS	LF	271.000	68
	462	6009		CONC BOX CULV (5 FT X 5 FT) DOLLARS and CENTS	LF	528.000	69
	462	6032		CONC BOX CULV (10 FT X 8 FT) DOLLARS and CENTS	LF	1,261.000	70
	464	6005		RC PIPE (CL III)(24 IN) DOLLARS and CENTS	LF	5,223.000	71
	464	6007		RC PIPE (CL III)(30 IN) DOLLARS and CENTS	LF	662.000	72

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	464	6008		RC PIPE (CL III)(36 IN) DOLLARS and CENTS	LF	377.000	73
	464	6009		RC PIPE (CL III)(42 IN) DOLLARS and CENTS	LF	2,008.000	74
	464	6010		RC PIPE (CL III)(48 IN) DOLLARS and CENTS	LF	375.000	75
	464	6018		RC PIPE (CL IV)(24 IN) DOLLARS and CENTS	LF	38.000	76
	464	6020		RC PIPE (CL IV)(36 IN) DOLLARS and CENTS	LF	241.000	77
	464	6029		RC PIPE (CL V)(48 IN) DOLLARS and CENTS	LF	249.000	78
	465	6002		MANH (COMPL)(PRM)(48IN) DOLLARS and CENTS	EA	9.000	79
	465	6003		MANH (COMPL)(PRM)(60IN) DOLLARS and CENTS	EA	3.000	80
	465	6006		JCTBOX(COMPL)(PJB)(4FTX4FT) DOLLARS and CENTS	EA	34.000	81
	465	6011		JCTBOX(COMPL)(PJB)(6FTX6FT) DOLLARS and CENTS	EA	10.000	82
	465	6024		INLET (COMPL)(PCO)(5FT)(BOTH) DOLLARS and CENTS	EA	12.000	83
	465	6040		INLET (COMPL)(PCU)(5FT)(BOTH) DOLLARS and CENTS	EA	3.000	84

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	465	6045		INLET (COMPL)(PMBD)(4FT) DOLLARS and CENTS	EA	8.000	85
	465	6077		INLET (COMPL)(PSL)(RC)(8FTX8FT) DOLLARS and CENTS	EA	3.000	86
	465	6115		INLET (STG I)(PSL)(S1)(5FTX5FT-4FTX4FT) DOLLARS and CENTS	EA	5.000	87
	465	6126		INLET (COMPL)(PSL)(FG)(3FTX3FT-3FTX- 3FT) DOLLARS and CENTS	EA	3.000	88
	465	6128		INLET (COMPL)(PSL)(FG)(4FTX4FT-4FTX- 4FT) DOLLARS and CENTS	EA	18.000	89
	465	6233		INLET (COMP) (TY SIDEWALK BRIDGE) DOLLARS and CENTS	EA	6.000	90
	466	6136		HEADWALL (CH - PW - S) (DIA= 48 IN) DOLLARS and CENTS	EA	2.000	91
	466	6165		WINGWALL (FW - S) (HW=4 FT) DOLLARS and CENTS	EA	1.000	92
	466	6167		WINGWALL (FW - S) (HW=6 FT) DOLLARS and CENTS	EA	1.000	93
	466	6172		WINGWALL (PW - 1) (HW=11 FT) DOLLARS and CENTS	EA	1.000	94
	466	6173		WINGWALL (PW - 1) (HW=12 FT) DOLLARS and CENTS	EA	1.000	95
	466	6180		WINGWALL (PW - 1) (HW=5 FT) DOLLARS and CENTS	EA	1.000	96

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	467	6391		SET (TY II) (24 IN) (RCP) (4: 1) (P) DOLLARS and CENTS	EA	5.000	97
	467	6420		SET (TY II) (30 IN) (RCP) (4: 1) (P) DOLLARS and CENTS	EA	2.000	98
	467	6451		SET (TY II) (36 IN) (RCP) (4: 1) (P) DOLLARS and CENTS	EA	1.000	99
	467	6464		SET (TY II) (42 IN) (RCP) (4: 1) (P) DOLLARS and CENTS	EA	5.000	100
	496	6002		REMOV STR (INLET) DOLLARS and CENTS	EA	11.000	101
	496	6004		REMOV STR (SET) DOLLARS and CENTS	EA	37.000	102
	496	6005		REMOV STR (WINGWALL) DOLLARS and CENTS	EA	4.000	103
	496	6007		REMOV STR (PIPE) DOLLARS and CENTS	LF	2,378.000	104
	496	6008		REMOV STR (BOX CULVERT) DOLLARS and CENTS	LF	2,344.000	105
	500	6001		MOBILIZATION DOLLARS and CENTS	LS	1.000	106
	502	6001		BARRICADES, SIGNS AND TRAFFIC HAN- DLING DOLLARS and CENTS	MO	29.000	107
	506	6002	003	ROCK FILTER DAMS (INSTALL) (TY 2) DOLLARS and CENTS	LF	480.000	108

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	506	6003	003	ROCK FILTER DAMS (INSTALL) (TY 3) DOLLARS and CENTS	LF	3,772.000	109
	506	6011	003	ROCK FILTER DAMS (REMOVE) DOLLARS and CENTS	LF	4,252.000	110
	506	6020	003	CONSTRUCTION EXITS (INSTALL) (TY 1) DOLLARS and CENTS	SY	17,792.000	111
	506	6024	003	CONSTRUCTION EXITS (REMOVE) DOLLARS and CENTS	SY	17,792.000	112
	506	6038	003	TEMP SEDMT CONT FENCE (INSTALL) DOLLARS and CENTS	LF	36,512.000	113
	506	6039	003	TEMP SEDMT CONT FENCE (REMOVE) DOLLARS and CENTS	LF	36,512.000	114
	506	6040	003	BIODEG EROSN CONT LOGS (INSTL) (8") DOLLARS and CENTS	LF	592.000	115
	506	6043	003	BIODEG EROSN CONT LOGS (REMOVE) DOLLARS and CENTS	LF	592.000	116
	508	6001		CONSTRUCTING DETOURS DOLLARS and CENTS	SY	16,542.000	117
	512	6001		PORT CTB (FUR & INST)(SGL SLOPE)(TY 1) DOLLARS and CENTS	LF	21,960.000	118
	512	6009		PORT CTB (FUR & INST)(LOW PROF)(TY 1) DOLLARS and CENTS	LF	7,100.000	119
	512	6010		PORT CTB (FUR & INST)(LOW PROF)(TY 2) DOLLARS and CENTS	LF	960.000	120

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	512	6025		PORT CTB (MOVE)(SGL SLP)(TY 1) DOLLARS and CENTS	LF	18,630.000	121
	512	6049		PORT CTB (REMOVE)(SGL SLP)(TY 1) DOLLARS and CENTS	LF	21,960.000	122
	512	6057		PORT CTB (REMOVE)(LOW PROF)(TY 1) DOLLARS and CENTS	LF	7,100.000	123
	512	6058		PORT CTB (REMOVE)(LOW PROF)(TY 2) DOLLARS and CENTS	LF	960.000	124
	528	6001		COLORED TEXTURED CONC (4") DOLLARS and CENTS	SY	309.000	125
	529	6001		CONC CURB (TY 1) DOLLARS and CENTS	LF	43,012.000	126
	530	6004		DRIVEWAYS (CONC) DOLLARS and CENTS	SY	4,472.000	127
	530	6006		DRIVEWAYS (SURF TREAT) DOLLARS and CENTS	SY	3,861.000	128
	531	6001		CONC SIDEWALKS (4") DOLLARS and CENTS	SY	25,771.000	129
	531	6004		CURB RAMPS (TY 1) DOLLARS and CENTS	EA	14.000	130
	531	6005		CURB RAMPS (TY 2) DOLLARS and CENTS	EA	16.000	131
	531	6013		CURB RAMPS (TY 10) DOLLARS and CENTS	EA	8.000	132

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	531	6016		CURB RAMPS (TY 21) DOLLARS and CENTS	EA	2.000	133
	531	6017		CURB RAMPS (TY 22) DOLLARS and CENTS	EA	13.000	134
	536	6002		CONC MEDIAN DOLLARS and CENTS	SY	13,057.000	135
	536	6004		CONC DIRECTIONAL ISLAND DOLLARS and CENTS	SY	947.000	136
	540	6001		MTL W-BEAM GD FEN (TIM POST) DOLLARS and CENTS	LF	6,663.000	137
	540	6006		MTL BEAM GD FEN TRANS (THRIE-BEAM) DOLLARS and CENTS	EA	22.000	138
	540	6016		DOWNSTREAM ANCHOR TERMINAL SEC- TION DOLLARS and CENTS	EA	20.000	139
	540	6018		MTL BM GD FEN TRANS (NON - SYM) DOLLARS and CENTS	EA	1.000	140
	543	6001		CABLE BARRIER SYSTEM (TL-3) DOLLARS and CENTS	LF	17,190.000	141
	543	6019		CABLE BARRIER TERMINAL SECTION (TL- 3) DOLLARS and CENTS	EA	10.000	142
	544	6001		GUARDRAIL END TREATMENT (INSTALL) DOLLARS and CENTS	EA	34.000	143
	545	6001		CRASH CUSH ATTEN (INSTL) DOLLARS and CENTS	EA	17.000	144

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	545	6003		CRASH CUSH ATTEN (MOVE & RESET) DOLLARS and CENTS	EA	12.000	145
	545	6005		CRASH CUSH ATTEN (REMOVE) DOLLARS and CENTS	EA	18.000	146
	545	6012		CRASH CUSH ATTEN (INSTL)(R)(N)(TL2) DOLLARS and CENTS	EA	1.000	147
	610	6004		RELOCATE RD IL ASM (TRANS-BASE) DOLLARS and CENTS	EA	2.000	148
	610	6009		REMOVE RD IL ASM (TRANS-BASE) DOLLARS and CENTS	EA	10.000	149
	610	6104		IN RD IL (U/P) (TY 1) (150W EQ) LED DOLLARS and CENTS	EA	24.000	150
	610	6264		IN RD IL (TY SP) 48S-10 (400W EQ) LED DOLLARS and CENTS	EA	8.000	151
	610	6272		IN RD IL (TY SA) 50B-10 (400W EQ) LED DOLLARS and CENTS	EA	2.000	152
	610	6288		IN RD IL (TY SA) 50T-10 (400W EQ) LED DOLLARS and CENTS	EA	31.000	153
	610	6289		IN RD IL (TY SA) 50T-10-10(400W EQ)LED DOLLARS and CENTS	EA	68.000	154
	617	6002		TEMP RD IL (RD IL ASM) DOLLARS and CENTS	MO	10.000	155
	618	6023		CONDT (PVC) (SCH 40) (2") DOLLARS and CENTS	LF	21,930.000	156

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	618	6024		CONDT (PVC) (SCH 40) (2") (BORE) DOLLARS and CENTS	LF	8,380.000	157
	618	6025		CONDT (PVC) (SCH 40) (2") (CONC ENCSE) DOLLARS and CENTS	LF	75,910.000	158
	618	6046		CONDT (PVC) (SCH 80) (2") DOLLARS and CENTS	LF	2,530.000	159
	618	6047		CONDT (PVC) (SCH 80) (2") (BORE) DOLLARS and CENTS	LF	3,131.000	160
	618	6053		CONDT (PVC) (SCH 80) (3") DOLLARS and CENTS	LF	730.000	161
	618	6054		CONDT (PVC) (SCH 80) (3") (BORE) DOLLARS and CENTS	LF	4,400.000	162
	618	6068		CONDT (RM) (1 1/2") DOLLARS and CENTS	LF	3,637.000	163
	618	6071		CONDT (RM) (2") (BORE) DOLLARS and CENTS	LF	1,045.000	164
	620	6008		ELEC CONDR (NO.8) INSULATED DOLLARS and CENTS	LF	61,744.000	165
	620	6009		ELEC CONDR (NO.6) BARE DOLLARS and CENTS	LF	5,900.000	166
	620	6010		ELEC CONDR (NO.6) INSULATED DOLLARS and CENTS	LF	33,798.000	167
	620	6012		ELEC CONDR (NO.4) INSULATED DOLLARS and CENTS	LF	7,917.000	168

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	624	6002		GROUND BOX TY A (122311)W/APRON DOLLARS and CENTS	EA	68.000	169
	624	6009		GROUND BOX TY D (162922) DOLLARS and CENTS	EA	27.000	170
	624	6010		GROUND BOX TY D (162922)W/APRON DOLLARS and CENTS	EA	5.000	171
	628	6002		REMOVE ELECTRICAL SERVICES DOLLARS and CENTS	EA	1.000	172
	628	6072		ELC SRV TY A 240/480 100(NS)AL(T)OC(O) DOLLARS and CENTS	EA	4.000	173
	628	6164		ELC SRV TY D 120/240 070(NS)AL(E)PS(U) DOLLARS and CENTS	EA	3.000	174
	628	6229		ELC SRV TY D 120/240 100(NS)GS(N)TP(O) DOLLARS and CENTS	EA	9.000	175
	636	6001		ALUMINUM SIGNS (TY A) DOLLARS and CENTS	SF	18.000	176
	636	6002		ALUMINUM SIGNS (TY G) DOLLARS and CENTS	SF	597.000	177
	636	6003		ALUMINUM SIGNS (TY O) DOLLARS and CENTS	SF	1,674.000	178
	644	6001		IN SM RD SN SUP&AM TY10BWG(1)SA(P) DOLLARS and CENTS	EA	53.000	179
	644	6002		IN SM RD SN SUP&AM TY10BWG(1)SA(P- BM) DOLLARS and CENTS	EA	5.000	180

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	644	6004		IN SM RD SN SUP&AM TY10BWG(1)SA(T) DOLLARS and CENTS	EA	135.000	181
	644	6007		IN SM RD SN SUP&AM TY10BWG(1)SA(U) DOLLARS and CENTS	EA	6.000	182
	644	6030		IN SM RD SN SUP&AM TYS80(1)SA(T) DOLLARS and CENTS	EA	12.000	183
	644	6033		IN SM RD SN SUP&AM TYS80(1)SA(U) DOLLARS and CENTS	EA	2.000	184
	644	6034		IN SM RD SN SUP&AM TYS80(1)SA(U-1EXT) DOLLARS and CENTS	EA	2.000	185
	644	6038		IN SM RD SN SUP&AM TYS80(1)SA(U-EXAL) DOLLARS and CENTS	EA	9.000	186
	644	6064		IN BRIDGE MNT CLEARANCE SGN ASSM(TY N) DOLLARS and CENTS	EA	24.000	187
	644	6076		REMOVE SM RD SN SUP&AM DOLLARS and CENTS	EA	196.000	188
	647	6001		INSTALL LRSS (STRUCT STEEL) DOLLARS and CENTS	LB	3,372.000	189
	647	6003		REMOVE LRSA DOLLARS and CENTS	EA	16.000	190
	650	6028		INS OH SN SUP(30 FT BAL TEE) DOLLARS and CENTS	EA	2.000	191
	650	6041		INS OH SN SUP(35 FT CANT)(SPAN ONLY) DOLLARS and CENTS	EA	1.000	192

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	650	6048		INS OH SN SUP(40 FT CANT)(SPAN ONLY) DOLLARS and CENTS	EA	1.000	193
	650	6101		INS OH SN SUP(90 FT BRDG)(SPAN ONLY) DOLLARS and CENTS	EA	4.000	194
	650	6111		INS OH SN SUP(100 FT BRDG)(SPAN ONLY) DOLLARS and CENTS	EA	1.000	195
	650	6116		INS OH SN SUP(105 FT BRDG)(SPAN ONLY) DOLLARS and CENTS	EA	1.000	196
	658	6001		INSTL DEL ASSM (D-SW)SZ 1(FLX)GND DOLLARS and CENTS	EA	90.000	197
	658	6019		INSTL DEL ASSM (D-SY)SZ 1(FLX)GND(BR) DOLLARS and CENTS	EA	75.000	198
	658	6036		INSTL DEL ASSM (D-DW)SZ 1(FLX)GND DOLLARS and CENTS	EA	30.000	199
	658	6041		INSTL DEL ASSM (D-DY)SZ 1(FLX)GND DOLLARS and CENTS	EA	3.000	200
	658	6048		INSTL OM ASSM (OM-2Z)(FLX)GND DOLLARS and CENTS	EA	18.000	201
	658	6050		INSTL OM ASSM (OM-2Z)(FLX)SRF DOLLARS and CENTS	EA	44.000	202
	658	6063		INSTL DEL ASSM (D-SW)SZ 1(BRF)GF2(BR) DOLLARS and CENTS	EA	41.000	203
	658	6065		INSTL DEL ASSM (D-SY)SZ 1(BRF)GF2(BR) DOLLARS and CENTS	EA	189.000	204

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	658	6069		INSTL DEL ASSM (D-SW)SZ (BRF)CTB (BR) DOLLARS and CENTS	EA	30.000	205
	658	6070		INSTL DEL ASSM (D-SY)SZ (BRF)CTB (BR) DOLLARS and CENTS	EA	31.000	206
	662	6002		WK ZN PAV MRK NON-REMOV (W)4"(DOT) DOLLARS and CENTS	LF	450.000	207
	662	6005		WK ZN PAV MRK NON-REMOV (W)6"(BRK) DOLLARS and CENTS	LF	13,222.000	208
	662	6008		WK ZN PAV MRK NON-REMOV (W)6"(SLD) DOLLARS and CENTS	LF	13,452.000	209
	662	6012		WK ZN PAV MRK NON-REMOV (W)8"(SLD) DOLLARS and CENTS	LF	12,975.000	210
	662	6017		WK ZN PAV MRK NON-REMOV (W)(ARROW) DOLLARS and CENTS	EA	52.000	211
	662	6029		WK ZN PAV MRK NON-REMOV(W)(WORD) DOLLARS and CENTS	EA	25.000	212
	662	6037		WK ZN PAV MRK NON-REMOV (Y)6"(SLD) DOLLARS and CENTS	LF	40,150.000	213
	662	6043		WK ZN PAV MRK NON-REMOV (Y)(MED NOSE) DOLLARS and CENTS	EA	1.000	214
	662	6048		WK ZN PAV MRK REMOV (REFL) TY I-C DOLLARS and CENTS	EA	1,182.000	215
	666	6006		REFL PAV MRK TY I (W)4"(DOT)(100MIL) DOLLARS and CENTS	LF	1,172.000	216

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	666	6033		REFL PAV MRK TY I (W)8"(LNDP)(100MIL) DOLLARS and CENTS	LF	528.000	217
	666	6036		REFL PAV MRK TY I (W)8"(SLD)(100MIL) DOLLARS and CENTS	LF	30,357.000	218
	666	6039		REFL PAV MRK TY I (W)12"(LNDP)(100MIL) DOLLARS and CENTS	LF	2,056.000	219
	666	6042		REFL PAV MRK TY I (W)12"(SLD)(100MIL) DOLLARS and CENTS	LF	3,882.000	220
	666	6048		REFL PAV MRK TY I (W)24"(SLD)(100MIL) DOLLARS and CENTS	LF	3,223.000	221
	666	6054		REFL PAV MRK TY I (W)(ARROW)(100MIL) DOLLARS and CENTS	EA	64.000	222
	666	6057		REFL PAV MRK TY I(W)(DBL ARROW)(100MIL) DOLLARS and CENTS	EA	22.000	223
	666	6063		REFL PAV MRK TY I(W)(UTURN ARW)(100MIL) DOLLARS and CENTS	EA	12.000	224
	666	6078		REFL PAV MRK TY I (W)(WORD)(100MIL) DOLLARS and CENTS	EA	59.000	225
	666	6138		REFL PAV MRK TY I (Y)8"(SLD)(100MIL) DOLLARS and CENTS	LF	220.000	226
	666	6147		REFL PAV MRK TY I (Y)24"(SLD)(100MIL) DOLLARS and CENTS	LF	231.000	227
	666	6156		REFL PAV MRK TY I(Y)(MED NOSE)(100MIL) DOLLARS and CENTS	EA	2.000	228

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	666	6224		PAVEMENT SEALER 4" DOLLARS and CENTS	LF	143,758.000	229
	666	6225		PAVEMENT SEALER 6" DOLLARS and CENTS	LF	15,330.000	230
	666	6226		PAVEMENT SEALER 8" DOLLARS and CENTS	LF	30,577.000	231
	666	6230		PAVEMENT SEALER 24" DOLLARS and CENTS	LF	3,454.000	232
	666	6231		PAVEMENT SEALER (ARROW) DOLLARS and CENTS	EA	64.000	233
	666	6232		PAVEMENT SEALER (WORD) DOLLARS and CENTS	EA	59.000	234
	666	6233		PAVEMENT SEALER (MED NOSE) DOLLARS and CENTS	EA	2.000	235
	666	6234		PAVEMENT SEALER (DBL ARROW) DOLLARS and CENTS	EA	22.000	236
	666	6236		PAVEMENT SEALER (UTURN ARROW) DOLLARS and CENTS	EA	12.000	237
	666	6300		RE PM W/RET REQ TY I (W)4"(BRK)(100MIL) DOLLARS and CENTS	LF	17,920.000	238
	666	6303		RE PM W/RET REQ TY I (W)4"(SLD)(100MIL) DOLLARS and CENTS	LF	44,644.000	239
	666	6306		RE PM W/RET REQ TY I (W)6"(BRK)(100MIL) DOLLARS and CENTS	LF	15,330.000	240

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	666	6315		RE PM W/RET REQ TY I (Y)4"(SLD)(100MIL) DOLLARS and CENTS	LF	80,022.000	241
	672	6008		REFL PAV MRKR TY I-R DOLLARS and CENTS	EA	28.000	242
	672	6009		REFL PAV MRKR TY II-A-A DOLLARS and CENTS	EA	138.000	243
	672	6010		REFL PAV MRKR TY II-C-R DOLLARS and CENTS	EA	3,061.000	244
	677	6002		ELIM EXT PAV MRK & MRKS (6") DOLLARS and CENTS	LF	18,553.000	245
	677	6003		ELIM EXT PAV MRK & MRKS (8") DOLLARS and CENTS	LF	1,421.000	246
	677	6007		ELIM EXT PAV MRK & MRKS (24") DOLLARS and CENTS	LF	210.000	247
	677	6008		ELIM EXT PAV MRK & MRKS (ARROW) DOLLARS and CENTS	EA	3.000	248
	677	6012		ELIM EXT PAV MRK & MRKS (WORD) DOLLARS and CENTS	EA	5.000	249
	680	6002		INSTALL HWY TRF SIG (ISOLATED) DOLLARS and CENTS	EA	3.000	250
	680	6004		REMOVING TRAFFIC SIGNALS DOLLARS and CENTS	EA	3.000	251
	681	6001		TEMP TRAF SIGNALS DOLLARS and CENTS	EA	3.000	252

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	682	6001		VEH SIG SEC (12")LED(GRN) DOLLARS and CENTS	EA	48.000	253
	682	6002		VEH SIG SEC (12")LED(GRN ARW) DOLLARS and CENTS	EA	6.000	254
	682	6003		VEH SIG SEC (12")LED(YEL) DOLLARS and CENTS	EA	48.000	255
	682	6004		VEH SIG SEC (12")LED(YEL ARW) DOLLARS and CENTS	EA	6.000	256
	682	6005		VEH SIG SEC (12")LED(RED) DOLLARS and CENTS	EA	48.000	257
	682	6018		PED SIG SEC (LED)(COUNTDOWN) DOLLARS and CENTS	EA	36.000	258
	682	6023		BACK PLATE (12")(3 SEC) DOLLARS and CENTS	EA	42.000	259
	682	6025		BACK PLATE (12")(5 SEC) DOLLARS and CENTS	EA	6.000	260
	684	6035		TRF SIG CBL (TY A)(14 AWG)(9 CONDR) DOLLARS and CENTS	LF	21,830.000	261
	686	6033		INS TRF SIG PL AM(S)1 ARM(32') DOLLARS and CENTS	EA	3.000	262
	686	6037		INS TRF SIG PL AM(S)1 ARM(36') DOLLARS and CENTS	EA	3.000	263
	686	6041		INS TRF SIG PL AM(S)1 ARM(40') DOLLARS and CENTS	EA	6.000	264

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	686	6045		INS TRF SIG PL AM(S)1 ARM(44') DOLLARS and CENTS	EA	5.000	265
	686	6049		INS TRF SIG PL AM(S)1 ARM(48') DOLLARS and CENTS	EA	1.000	266
	687	6001		PED POLE ASSEMBLY DOLLARS and CENTS	EA	15.000	267
	688	6001		PED DETECT PUSH BUTTON (APS) DOLLARS and CENTS	EA	36.000	268
	688	6003		PED DETECTOR CONTROLLER UNIT DOLLARS and CENTS	EA	3.000	269
	690	6006		REMOVAL OF GROUND BOXES DOLLARS and CENTS	EA	1.000	270
	730	6002		FULL - WIDTH MOWING DOLLARS and CENTS	AC	62.000	271
	734	6002		LITTER REMOVAL DOLLARS and CENTS	CYC	29.000	272
	740	6004		ANTI - GRAFFITI COATING(PERMNENT-TY II) DOLLARS and CENTS	SF	34,645.000	273
	4051	6001		SOUND WALL DOLLARS and CENTS	SF	15,792.000	274
	4052	6001		FIBERGLASS SOUND WALL DOLLARS and CENTS	SF	1,458.000	275
	6001	6001		PORTABLE CHANGEABLE MESSAGE SIGN DOLLARS and CENTS	DAY	518.000	276

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	6003	6001		ITS SYSTEM SUPPORT EQUIPMENT DOLLARS and CENTS	LS	1.000	277
	6010	6001		CCTV FIELD EQUIPMENT (ANALOG) DOLLARS and CENTS	EA	4.000	278
	6025	6001		RADAR PRESENCE DETECTOR DOLLARS and CENTS	EA	18.000	279
	6025	6002		RADAR PRESENCE DETECTOR COMM CABLE DOLLARS and CENTS	LF	11,800.000	280
	6028	6001		INSTALL DMS (POLE MTD CABINET) DOLLARS and CENTS	EA	2.000	281
	6029	6001	002	RADAR VEHICLE SENSING DEVICE DOLLARS and CENTS	EA	8.000	282
	6057	6001		RADAR ADVANCED DETECTION DEVICE DOLLARS and CENTS	EA	12.000	283
	6058	6001		BBU SYSTEM (EXTERNAL BATT CABINET) DOLLARS and CENTS	EA	3.000	284
	6062	6026		ITS RADIO (DUAL)(2.4 GHZ/5 GHZ)-I-U DOLLARS and CENTS	EA	1.000	285
	6064	6010		ITS POLE (30 FT)(90 MPH) DOLLARS and CENTS	EA	3.000	286
	6064	6046		ITS POLE (55 FT)(90 MPH) DOLLARS and CENTS	EA	4.000	287
	6064	6076		ITS POLE MNT CAB (TY 1)(CONF 2) DOLLARS and CENTS	EA	3.000	288

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	6064	6084		ITS POLE MNT CAB (TY 2)(CONF 2) DOLLARS and CENTS	EA	4.000	289
	6071	6002		FIB OPT CBL (SM) 12 STRAND DOLLARS and CENTS	LF	16,335.000	290
	6071	6011		FIB OPT CBL (SM) 96 STRAND DOLLARS and CENTS	LF	22,265.000	291
	6096	6002		INS LED WW SGN W/BASIC SOL PWR KIT DOLLARS and CENTS	EA	12.000	292
	7027	6002		NGP(MAIN)(PLASTIC W/TRACER WIRE)(6 IN) DOLLARS and CENTS	LF	333.000	293
	7027	6003		NGP (MAIN) (12" STEEL) (OPEN CUT) DOLLARS and CENTS	LF	3,454.000	294
	7027	6004		NGP JT TRENCH(6" PLASTIC W/TW)12" STL DOLLARS and CENTS	LF	2,808.000	295
	7027	6005		NGP BORING (8" STEEL BORE FOR CASING) DOLLARS and CENTS	LF	153.000	296
	7027	6006		NGP BORING (12" STEEL BORE) DOLLARS and CENTS	LF	443.000	297
	7027	6007		NGP MAIN (6" PLASTIC W/TW) (8" CASING) DOLLARS and CENTS	LF	153.000	298
	7027	6008		NGP STOPPLE (12" THREE-WAY TEE) DOLLARS and CENTS	EA	10.000	299
	7076	6001		GROUT ABANDONMENT WATER MAIN (12 IN) DOLLARS and CENTS	LF	1,863.000	300

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	7076	6002		GROUT ABANDONMENT WATER MAIN (16 IN) DOLLARS and CENTS	LF	1,104.000	301
	7076	6003		GROUT ABANDONMENT WATER MAIN (20 IN) DOLLARS and CENTS	LF	150.000	302
	7076	6004		GROUT ABANDONMENT WATER MAIN (24 IN) DOLLARS and CENTS	LF	3,340.000	303
	7077	6001		6" C900 PVC DR18(CL 150), WTR LN(OP CT) DOLLARS and CENTS	LF	30.000	304
	7077	6002		8" C900 PVC DR18(CL 150), WTR LN(OP CT) DOLLARS and CENTS	LF	76.000	305
	7077	6003		10"C900 PVC DR18(CL 150), WTR LN(OP CT) DOLLARS and CENTS	LF	30.000	306
	7077	6004		12"C900 PVC DR18(CL 150), WTR LN(OP CT) DOLLARS and CENTS	LF	2,167.000	307
	7077	6005		16"C905 PVC DR18(CL 150), WTR LN(OP CT) DOLLARS and CENTS	LF	1,866.000	308
	7077	6006		20" DUCTILE IRON PIPE DOLLARS and CENTS	LF	27.000	309
	7077	6007		24" DUCTILE IRON PIPE DOLLARS and CENTS	LF	4,570.000	310
	7077	6008		WTR (JACK, BORE OR TUNNEL) (42 IN) DOLLARS and CENTS	LF	211.000	311

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	7077	6009		CARRIER PIPE (IN CASING) (PVC) (16 IN) DOLLARS and CENTS	LF	115.000	312
	7077	6010		CARRIER PIPE (IN CASING) (DI) (24 IN) DOLLARS and CENTS	LF	383.000	313
	7077	6011		STEEL CASING (24 IN) (OPEN CUT) DOLLARS and CENTS	LF	115.000	314
	7077	6012		STEEL CASING (42 IN) (OPEN CUT) DOLLARS and CENTS	LF	172.000	315
	7077	6013		STEEL CASING (42 IN) (BORE) DOLLARS and CENTS	LF	211.000	316
	7077	6014		CONCRETE ENCASEMENT FOR WATERLINE DOLLARS and CENTS	CY	33.500	317
	7077	6015		CONCRETE SADDLE FOR WATERLINE DOLLARS and CENTS	CY	4.700	318
	7077	6016		TIE-IN (COMPLETE)(8 IN) DOLLARS and CENTS	EA	2.000	319
	7077	6017		TIE-IN (COMPLETE)(10 IN) DOLLARS and CENTS	EA	1.000	320
	7077	6018		TIE-IN (COMPLETE)(12 IN) DOLLARS and CENTS	EA	6.000	321
	7077	6019		TIE-IN (COMPLETE)(16 IN) DOLLARS and CENTS	EA	2.000	322
	7077	6020		TIE-IN (COMPLETE)(20 IN) DOLLARS and CENTS	EA	1.000	323

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	7077	6021		TIE-IN (COMPLETE)(24 IN) DOLLARS and CENTS	EA	4.000	324
	7077	6022		GATE VALVE & BOX (COMPLETE)(8 IN) DOLLARS and CENTS	EA	1.000	325
	7077	6023		GATE VALVE & BOX (COMPLETE)(10 IN) DOLLARS and CENTS	EA	1.000	326
	7077	6024		GATE VALVE & BOX (COMPLETE)(12 IN) DOLLARS and CENTS	EA	6.000	327
	7077	6025		GATE VALVE & BOX (COMPLETE)(16 IN) DOLLARS and CENTS	EA	4.000	328
	7077	6026		GATE VALVE & BOX (COMPLETE)(20 IN) DOLLARS and CENTS	EA	1.000	329
	7077	6027		ADJUST VALVE BOX TO GRADE DOLLARS and CENTS	EA	13.000	330
	7077	6028		BUTTERFLY VALVE AND BOX (COMPL) (24 IN) DOLLARS and CENTS	EA	9.000	331
	7077	6029		DUCTILE IRON FITTINGS DOLLARS and CENTS	TON	28.900	332
	7077	6030		TEMPORARY BLOW-OFF (COMPLETE)(2 IN) DOLLARS and CENTS	EA	8.000	333
	7077	6031		TEMPORARY BLOW-OFF (COMPLETE)(4 IN) DOLLARS and CENTS	EA	4.000	334
	7077	6032		AIR RELEASE VALVE (COMPLETE) (2 IN) DOLLARS and CENTS	EA	2.000	335

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	7077	6033		ADJUST AND/OR RELOCATE WATER METER BOX DOLLARS and CENTS	EA	3.000	336
	7077	6034		FIRE HYDRANT ASSEMBLY DOLLARS and CENTS	EA	17.000	337
	7077	6035		RECONNECT SHORT WATER SERVICE (3/4 IN) DOLLARS and CENTS	EA	2.000	338
	7077	6036		RECONNECT SHORT WATER SERVICE (2 IN) DOLLARS and CENTS	EA	1.000	339
	7077	6037		FLOWABLE FILL DOLLARS and CENTS	CY	1,391.000	340
	7077	6038		WTR TRENCH EXCAVATION PROTECTION DOLLARS and CENTS	LF	9,098.000	341
	7077	6039		CUT AND REPLACE ASPHALT PAVEMENT DOLLARS and CENTS	SY	13.000	342
	7077	6040		REM EXIST DRIVEWAY AND REPL W/ ASPHALT DOLLARS and CENTS	SY	87.000	343
	7077	6041		HYDROSTATIC TEST DOLLARS and CENTS	EA	8.000	344
	7077	6043		24 IN X 6 IN TAPPING SLEEVE AND VALVE DOLLARS and CENTS	EA	1.000	345
	7077	6044		WATER SERVICE LINE BREAKS LEAK REPAIR DOLLARS and CENTS	EA	2.000	346

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	7077	6045		WATER MAIN BREAKS LEAK REPAIR DOLLARS and CENTS	EA	2.000	347
	7078	6001		SAN SWR (24 IN)(PVC)(F679)(10'-14') DOLLARS and CENTS	LF	154.000	348
	7078	6002		SAN SWR (24 IN)(PVC)(F679)(14'-18') DOLLARS and CENTS	LF	184.000	349
	7078	6003		SAN SWR (JACK,BORE OR TUNNEL)(42 IN) DOLLARS and CENTS	LF	125.000	350
	7078	6004		SAN SWR MANHOLES (TY 1) DOLLARS and CENTS	EA	4.000	351
	7078	6006		SAN SWR CARRIER PIPE IN CASE(PVC)(24") DOLLARS and CENTS	LF	493.000	352
	7078	6007		SAN SWR JK BOR TUN PIPE (42IN)(STEEL) DOLLARS and CENTS	LF	125.000	353
	7078	6008		SAN SWR TRENCH EXCAVATION PROTEC- TION DOLLARS and CENTS	LF	856.000	354
	7078	6009		SAN SWR ABANDON SEWER LINES DOLLARS and CENTS	LF	575.000	355
	7078	6010		SAN SWR POST TELEVISION INSP (18"-24") DOLLARS and CENTS	LF	830.000	356
	7078	6011		SAN SWR CASING OP CUT (STEEL)(42") DOLLARS and CENTS	LF	368.000	357
	7078	6012		SAN SWR SPLT CAS OPEN CUT (STEEL)(24") DOLLARS and CENTS	LF	150.000	358

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	7078	6013		SAN SWR FLOWABLE FILL DOLLARS and CENTS	CY	1,339.000	359
	7078	6014		SAN SWR RECONSTRUCT EXISTING MAN- HOLE DOLLARS and CENTS	EA	2.000	360
	7078	6015		SAN SWR PT REPAIRS AND OBSTRUCT REMOV DOLLARS and CENTS	EA	2.000	361
	7078	6016		SAN SWR BYPASS PUMPING DOLLARS and CENTS	LS	1.000	362
	7078	6017		SAN SWWR PRE-CAST MANHOLE (EXTRA DEPTH) DOLLARS and CENTS	LF	52.000	363
	7079	6001		12 IN TEMP LINE STOP VALVE (COMP)(PERM) DOLLARS and CENTS	EA	1.000	364
	7092	6001		GROUT ABANDONMENT GAS MAIN (4" PLASTIC) DOLLARS and CENTS	LF	2,696.000	365
	7092	6002		GROUT ABANDONMENT GAS MAIN (12" STEEL) DOLLARS and CENTS	LF	3,104.000	366

County: Bexar

Highway: Lp 1604

*****GENERAL NOTES*****
2014 Specification Book (Revised March 3, 2016)

===== **Basis of Estimate** =====

Item	Description	Rate/Area	Quant-Unit
168	Vegetative Watering	15.6 Gal / 349,204 SY	5449 MG

===== **Asphalt Concrete Pavement** =====

Location/Type	Depth	Rate/Area	Quant-Unit
Location: LP 1604 SBFR			
C(PG70-22)	2 inches	220 lbs/ 161,965 SY	17,842 Tons
D(PG70-22)(SAC A)	2 inches	220 lbs/ 86,831 SY	9,559 Tons
Location: LP 1604 SBML			
C(PG70-22)	2 inches	220 lbs/ 156,628 SY	17,247 Tons
D(PG70-22)(SAC A)	2 inches	220 lbs/ 79,362 SY	8,739 Tons
Location: LP 1604 NBML			
C(PG70-22)	2 inches	220 lbs/ 126,882 SY	13,980 Tons
D(PG70-22)(SAC A)	2 inches	220 lbs/ 88,098 SY	9,706 Tons
Location: LP 1604 NBFR			
B(PG70-22)	10 inches	1100 lbs/ 13,843	7,625 Tons
C(PG70-22)	2 inches	220 lbs/ 28,056 SY	3,098 Tons
D(PG70-22)(SAC A)	2 inches	220 lbs/ 96,053 SY	10,582 Tons
Location: LP 1604 Ramps			
C(PG70-22)	2 inches	220 lbs/ 24,374 SY	2,697 Tons
D(PG70-22)(SAC A)	2 inches	220 lbs/ 11,427 SY	1,266 Tons
Location: LP 1604 Turnarounds			
C(PG70-22)	2 inches	220 lbs/ 12,813 SY	1,417 Tons
Location: Potranco Intersection			
B(PG70-22)	10 inches	1100 lbs/ 267	120 Tons
D(PG70-22)(SAC A)	2 inches	220 lbs/ 9,034 SY	996 Tons
Location: Military Intersection			
B(PG70-22)	10 inches	1100 lbs/ 4,095	1,803 Tons
D(PG70-22)(SAC A)	2 inches	220 lbs/ 6,356 SY	704 Tons

County: Bexar

Highway: Lp 1604

Location: Wiseman Intersection

B(PG70-22)	10 inches	1100 lbs/ 1,680	741 Tons
D(PG70-22)(SAC A)	2 inches	220 lbs/ 8,785 SY	970 Tons

PROJECT TOTALS

Type	Quant-Tons
D(PG70-22)(SAC A)	42,522 Tons
C(PG70-22)	56,281 Tons
B(PG70-22)	10,289 Tons

===== **Surface Treatment Data** =====

<u>Description</u>	<u>RC250</u>
LP1604	385,946 SY
Asphalt--Rate(Gal/SY)	0.3/1 = 115,847 Gal
Aggregate--Type/Grade	GR-5 TY D
Aggregate--Rate(CY/SY)	1/100 = 3,928 CY

<u>Description</u>	<u>Prime Coat (MC-30)</u>
LP1604	250,925 SY
Asphalt--Rate(Gal/SY)	.3/1 = 75,323 Gal

*Rates are for estimating purposes only.

The following State, District, Local and/or Utility Standards have been modified: RW (TEW) MOD, PMBD (MOD), RAC-R(MOD), IGMS (MOD), IGTS (MOD), PCP (MOD), BL-STR (MOD), OSBC-SC-Z2 (MOD), BAS-A(MOD)

Steel Wrapped or Asbestos Utility Lines:

Existing steel wrapped natural gas and/or asbestos cement (AC) water lines that will no longer be in service are usually abandoned in place (AIP). However, if any of these lines have to be removed for whatever reason (in the way of other construction, to make tie-ins, etc.) comply with all federal, state and local laws, ordinances and regulations regarding the management of these materials. At a minimum:

1. Contact the Engineer.
2. Remove the minimum amount of pipe needed to perform the proposed work.
3. Cover and secure the ends of the pipe with a double layer of 6 mil plastic. If the pipe is damaged, cover the entire pipe.

County: Bexar

Highway: Lp 1604

4. Move the pipe to an approved temporary site within the project.
5. The Engineer will determine the owner (utility company) of the pipe and will coordinate removal from the project. The contractor will load the pipe onto the removal vehicles but will NOT be responsible for removing the pipe from the project.
6. Removal of the pipe from the trench is subsidiary to the work that created the need for the removal (excavation for structures, roadway, a new line, tie-ins, etc.). The work performed in handling the pipe after it has been removed from the trench (covering with plastic, hauling to the temporary site and later loading on to the disposal vehicles will be paid for through the Force Account procedure.

Contact the Engineer or the City when construction operations are within 400 feet of a signalized intersection to determine/verify the location of loop detectors, conduit, ground-boxes, etc. Repair or replace any signal equipment damaged by construction operations. The method of repair or replacement shall be pre-approved and inspected. Depending on the type and extent of the damage, the Engineer reserves the right to perform the repair or replacement work and the Contractor will be billed for this work.

Remove existing raised pavement markings as the work progresses or as approved. This work is subsidiary to the various bid items. Properly dispose materials removed.

To better fit field conditions, the cross sections may be varied when approved.

If there are waste areas or material source areas, follow the Texas Aggregate Quarry and Pit Safety Act requirements.

Any materials removed and not reused and determined to be salvageable shall be stored within the project limits at an approved location or delivered undamaged to the storage yard as directed. Properly dispose unsalvageable materials in accordance with local, state, and federal regulations. Deface traffic signs so that they will not reappear in public as signs.

Any sign panels that are adjusted or removed and replaced, shall be done the same workday unless otherwise approved. This work shall be considered subsidiary to Item 502.

Notify the Engineer at least two weeks prior to a proposed traffic pattern change(s) that will require a revision to traffic signals.

Locate and reference all manholes and valves within the construction area with station and offset. Each manhole and valve shall be identified by its owner (SAWS, CPS, etc.). No roadwork will begin until this list has been submitted. Gas valves have to be accessible at all times, therefore; temp. CTB, material stock piles, etc. cannot be placed over these valves.

County: Bexar**Highway: Lp 1604**

Construct all manholes and valves to final pavement elevations prior to the final mat of ACP. If, between the final elevation adjustment and the final mat of ACP, the manholes and valves are going to be exposed to traffic, place temporary asphalt around the manhole and valve to provide a +/- 50:1 taper. The cost of elevation adjustment will be part of the manhole and valve work, and asphalt tapers are part of the ACP work.

Hurricane Evacuation

Hurricane Season is from June 1 thru November 30. As the closest metropolitan city inland from the Texas Coast, the City of San Antonio is a major shelter destination during mandatory hurricane evacuations. As such, planned work zone lane or road closures may be restricted and/or suspended during mandatory hurricane evacuation operations. The District will coordinate these restrictions at a minimum H-120 from any projected impact to the Texas Coast.

No time charges will be made if the Engineer determines that work on the project was impacted by the hurricane.

The Engineer may order changes in the Traffic Control Plan to accommodate evacuation traffic, and may suspend the work, all or in part, to ensure timely completion of this work. All work to implement changes in the Traffic Control Plan will be paid through existing bid prices or through Item 9.5, Force Account. However, the Department will not entertain any request for delay damages, loss of efficiency that may be attributed to the restriction or suspension of road or lane closures, or to changes in the Traffic Control Plan.

The Contractor should be aware that the "City Public Service" (CPS) will be consulted by the Engineer in matters concerning the execution of the work, materials and testing related to the CPS work. As such; a CPS employee may be observing the construction and related operations as they progress.

If a sanitary sewer overflow (SSO) occurs:

1. Attempt to eliminate the source of the SSO.
2. Contain sewage from the SSO to the extent possible to prevent contamination of waterways.
3. Call SAWS at (210) 233-2015.

The Contractor should be aware that the "San Antonio Water System" (SAWS) will be consulted by the Engineer in matters concerning the execution of the joint bid Water and/or Sanitary work. This may include reviewing material submittals and testing related to this work, as well as inspection and observation of the actual work. As such, a SAWS employee may be reviewing submittals and test results as well as observing the construction and related operations as they progress.

County: Bexar

Highway: Lp 1604

--Item 5--

Reference all existing striping and other pavement markings to allow these markings to be re-established. Ensure the markings (lane lines, edge lines, ramp gores, etc.) are in line with signs, TMS arrows, etc. located on overhead sign supports.

Taper ACP placed at curb inlets, traffic inlets and slotted drains.

When a bridge deck is milled, seal coated and overlaid, remove excess material. Do not just broom to the sides of the bridge, under guardrail, etc. Cover or protect all sealed expansion joints and rails on bridges and all railroad tracks encountered as approved. Clean all of these features if they weren't properly protected. This work is subsidiary work to applicable bid items.

Prior to letting, bidders may obtain a free computer diskette or a computerized transfer of files (from the Engineer's office) that contains the earthwork information. If copies of the cross-sections in addition to, or instead of, the CD are requested, they will be available at the Engineer's office for borrowing by copying companies at the bidder's expense.

When working near aerial electrical lines or utility poles, comply with Federal, State and local regulations. For electrical lines and poles shown in the plans, if the lines need to be de-energized or if poles need to be braced, contact the electrical company. Work pertaining to de-energizing lines, bracing poles and other protective measures will not be paid by TxDOT.

Prevention of Migratory Bird Nesting

It is anticipated that migratory birds, a protected group of species, may try to nest on bridges, culverts, vegetation, or gravel substrate, at any time of the year. The preferred nesting season for migratory birds is from February 15 through October 1. When practicable, schedule construction operations outside of the preferred nesting season. Otherwise, nests containing migratory birds must be avoided and no work will be performed in the nesting areas until the young birds have fledged.

Structures

Bridge and culvert construction operations can not begin until swallow nesting prevention is implemented, until after October 1 if it's determined that swallow nesting is actively occurring, or until it's determined swallow nests have been abandoned. If the State installed nesting deterrent on the bridges and culverts, maintain the existing nesting deterrent to prevent swallow nesting until October 1 or completion of the bridge and culvert work, whichever occurs earlier. If new nests are built and occupied after the beginning of the work, do not perform work that can interfere with or discourage swallows from returning to their nests. Prevention of swallow nesting can be performed by one of the following methods:

County: Bexar

Highway: Lp 1604

1. By February 15 begin the removal of any existing mud nests and all other mud placed by swallows for the construction of nests on any portion of the bridge and culverts. The Engineer will inspect the bridges and culverts for nest building activity. If swallows begin nest building, scrape or wash down all nest sites. Perform these activities daily unless the Engineer determines the need to do this work more frequently. Remove nests and mud through October 1 or until bridge and culvert construction operations are completed.
2. By February 15 place a nesting deterrent (which prevents access to the bridge and culvert by swallows) on the entire bridge (except deck and railing) and culverts.

No extension of time or compensation payment will be granted for a delay or suspension of work caused by nesting swallows. This work is subsidiary to the various bid items.

Do not store equipment or work in the designated Critical Habitat Unit 16 (CHU). Place construction fencing as shown in the plans to designate this location to assist with avoiding the area.

No extension of time or compensation payment will be granted for a delay or suspension of work caused by encountering karst features. This work is subsidiary to the various bid items.

Provide a non-intrusive back-up alarm system on all heavy equipment used in close proximity to residential areas. This item is subsidiary to various bid items.

--Item 6--

Show the stockpile lot and/or sub lot numbers on all tickets for all materials.

--Item 7--

The project's total disturbed area is **175 acres**. The disturbed area in all project locations and Contractor project specific locations (PSL's), within 1/4 mile of the project limits, will further establish the authorization requirements for storm water discharges. The department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. Obtain any required authorization from the TCEQ for any PSL's on or off the ROW. When the total area disturbed on the project and PSL's within 1/4 mile of the project exceeds 5 acres, provide a copy of the Contractor NOI for PSL's to the Engineer (to the appropriate MS4 operator when the project is on an off-state system route).

Notify the Engineer of the disturbed acreage within one (1) mile of the project limits. Obtain authorization from the TCEQ for Contractor PSL's for construction support activities on or off ROW.

County: Bexar

Highway: Lp 1604

--Item 8--

Working days will be computed and charged in accordance with Article **8.3.1.2, Six-Day Workweek** .

Milestone 1 (Reconstruction Work at Westbound Military Drive)

Milestone 1 begins in Phase 1 at the intersection of the LP 1604 existing Southbound Mainlanes and Military Drive. Time charges for Milestone 1 shall begin when traffic is routed to the outside lanes in both the Eastbound and Westbound directions while Military Drive through lanes are closed and reconstructed.

The time charges for Milestone 1 will end when the Military Drive reconstruction is complete and all lanes of traffic on Military Drive are opened to traffic.

The daily road user cost for Milestone 1 shall be \$2,425.84.

The contractor shall have 10 working days to complete this milestone.

The maximum number of working days for computing the incentive credit for Milestone 1 shall be 10 days.

The Road User Cost liquidated damages for Milestone 1 shall be \$2,425.84 per day.

Working day time charges for Milestone 1 will be computed and charged in accordance with Article 8.3.1.2, Six-Day workweek.

Culvert No. 3, Station 785+50 (Existing LP 1604 Northbound Mainlanes)
Structure E7-MHE2, Station 782+50 (Existing LP 1604 Northbound Mainlanes)
Culvert No. 5, Station 810+40 (Existing LP 1604 Northbound Mainlanes)

The above noted structures must be installed in sections as shown in the plans during weekend operations beginning at 9 pm on Friday and completed by 5 am the following Monday morning. Lane Closure assessment fees will apply if the roadway is not opened by the designated time, as shown in the Lane Closure Assessment Table and as per SP 008-017.

Create and maintain a Critical Path Method schedule.

The CPM schedule shall be created and maintained using software fully compatible with version 6.1 of Primavera Project Planner or SureTrak Project Scheduler.

Provide a Project Schedule Summary Report.

County: Bexar

Highway: Lp 1604

A lane closure assessment fee will be assessed as per the “Lane Closure Assessment Table” in the plans.

--Item 9--

When approved, provide uniformed, off-duty law enforcement officers with marked vehicles during work that requires a lane closure. The officer in marked vehicles shall be located as approved to monitor or direct traffic during the closure. The method used to direct traffic at signalized intersections shall be as approved. Additional officers and vehicles may be provided when approved or directed.

Complete the daily tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided.

Show proof of certification by the Texas Commission on Law Enforcement Standards.

All law enforcement personnel used in Work Zone Traffic Control shall be trained for performing duties in work zones and are required to take “Safe and Effective Use of Law Enforcement Personnel in Work Zones” (Course #133119) which can be found online at the following site: www.nhi.fhwa.dot.gov

Certificates of completion should be available to all who finish the course. These should be kept by the officers in order to substantiate completion when reporting to the work site.

Minimums, scheduling fees, etc. will not be paid; TxDOT will consider paying cancellation fees on a case by case basis.

--Item 100--

Begin clearing operations after trees and other areas of vegetation to be protected have been identified and approved. Install fencing around features to be protected as shown in the plans or directed. Coordinate all right of way clearing operations with the SW3P.

Trim and remove brush and trees as needed for construction operations. Obtain approval for proposed method of tree and brush trimming and removal. Vertical flailing equipment is not allowed. Treat damaged or cut branches, roots and/or stumps of all oak trees with a commercial tree wound dressing. Disinfect all pruning tools with a solution of 70% alcohol before moving from one tree to another. Unless otherwise approved remove all resulting vegetative debris from the ROW within 24 hours. The Engineer can stop all construction operations if the dressing, cut and removal requirements are not followed.

Any items not specifically called out or shown in the plans to be removed for any construction operations within the right of way / and or designated easements are included under Item 100, Preparing Right of Way. Items designated on the plans as removal items are for the Contractor’s information only and are not intended to be the sole basis for the bid for Item 100 on this project.

County: Bexar

Highway: Lp 1604

Due to the nature of this project on new location, the contractor shall anticipate encountering abandoned items and dumped trash, including but not limited to mattresses, wood, buckets, trash, brush, gardens, batting cage, etc. Any items and / or debris encountered within the ROW during construction shall be the responsibility of the contractor to properly dispose of in accordance with Item 100 and applicable laws and regulations.

--Item 110--

Where excavation extends beyond a right of way fence, remove and replace the fence to a comparable condition. This work shall be considered subsidiary to the bid item.

--Item 132--

At no time shall the retaining wall backfill material exceed the adjacent embankment operation by more than one embankment lift. At no time will the embankment adjacent to the retaining wall backfill exceed the wall backfill by any elevation.

--Item 164--

Drill seeding of permanent grasses requires the use of approved grass seeding equipment capable of properly storing and metering the release of small seeds (such as Bermuda grass) separately from fluffy type seeds (such as bluestems). Equipment manufactured for planting grain crops is acceptable for planting temporary cool season seeds, but not for planting the permanent seed mix.

When drill seeding is required, cultivate the area to a depth of 4 in. after the fertilizer has been applied and before placing the seed.

If performing a permanent seeding in an area with established temporary grass cover and mowing is performed instead of tilling, seed and fertilizer may be distributed simultaneously during "Broadcast Seeding" operations, provided each component is applied at the specified rate.

--Item 168--

Apply vegetative watering as needed to supplement natural rainfall during the vegetation establishment period. Plan quantity of irrigation water is based on the application of a total of 1.3 gal of water each week for each sq. yd. of area that is sodded or seeded. Establishment time is estimated to be 12 weeks for both sod and permanent seed mixes. Temporary seeding will require less time for establishment. Provide a schedule and coordinate watering cycles and rates per cycle with the Engineer. Obtain approval if the quantity of water to be applied is expected to exceed the plan quantity. Adjust the amount of water applied with each cycle and the number of cycles each wk. according to actual site conditions. Drought or other conditions, as determined by the Engineer, may require the application of supplemental irrigation during hours other than normal working hours.

--Item 247--

There is no minimum PI requirement for this project.

County: Bexar

Highway: Lp 1604

--Item 302--

Previously tested aggregates found to contain excessive quantities of dust (more than 0.5 percent passing the No. 40 sieve) during precoating, stockpiling or hauling operations, may be rejected. Use Test Method Tex-200-F, Part I for testing.

Precoated Aggregate Type PE shall consist of crushed slag, crushed stone or natural limestone rock asphalt.

The Engineer will utilize the Ignition Oven Method (Tex 236-F) for aggregate gradation, with the option of utilizing belt or vacuum extraction gradation in the event the ignition oven malfunctions.

--Item 316--

When using latex asphalt, avoid drifting of asphalt onto traffic and adjacent properties.

Asphalt season will be year around, but meet sections 316.4.4.1 through 4.4.3.

Ensure that the asphalt for precoating the aggregate and the asphalt used for the surface treatment will not result in a reaction that may adversely affect the bonding of the aggregate and asphalt during the surface treatment operation.

Do not add bag house fines in the production of precoated material.

Clean all concrete curbs, islands, medians, etc. that get coated with asphalt.

--Item 320--

Construct all longitudinal ACP joints adjacent to a travel lane with a joint maker device that will create a 3:1 to 6:1 taper. For placement of 2 inches or more, the device shall provide a maximum 1/2 inch vertical edge. Taper outside edges (next to the grass) or backfill (shoulder-up) the same day.

Provide a material transfer device capable of providing a continuous flow of material to the paver. The material transfer device will consist of a windrow elevator or better.

When placing Item 346 mixtures, provide a material transfer vehicle that is capable of providing a remixing, and continuous flow of material from the haul truck to the paver, such as a Roadtec SM-2500e/ex.

--Item 341--

1. Table 10 in Item 341, Hamburg Wheel Test Requirements tested in accordance with Tex-242-F are changed for PG 64-22 or lower and PG 70-22. Minimum number of passes at 1/2" Rut Depth, Tested at 122 degrees F will be 5,000 and 10,000 respectively.

County: Bexar**Highway: Lp 1604**

2. Design all mixture types using a target laboratory-molded density of 96.5%, when the Texas
3. Gyrator Compactor is utilized. Increase the target laboratory-molded density to 97.0% or 97.5% at the Contractor's discretion. When utilizing SGC, design all mixture types at 50 gyrations (N-Design) and a target laboratory-molded density of 96.0%, but may be reduced to no less than 35 gyrations at the Contractor's discretion.
4. The asphalt plant shall have truck scales as defined in Item 520. Give three weight tickets bearing the date, the truck number, the gross, net & tare weights to the truck driver for the State inspector at the spreading and finishing operation. Trucks may be required to weigh on public scales or portable platform scales to verify the weight of the ticket.
5. Submit a copy of the Tex 233-F production charts on a weekly basis. At the end of the ACP work, provide all originals.
6. Crushing of aggregate for hot mix and immediate use for production of the mix is not allowed. Stockpile the aggregate until enough material is available for five days of production unless prior approval is provided. Hold a pre-placement meeting one month prior to the placement of the hot mix.
7. The main purpose of hot mix cores taken by the State are for payment calculations. If (for quality control purposes) the core information is needed sooner, take additional cores.
8. Do not use diesel or solvents as asphalt release agents in production, transportation, or construction. A list of approved asphalt release agents is available from the District Laboratory.
9. No more than one hot mix lot will be open for any specific type of hot mix, unless authorized. After a lot is open and the Contractor gets approval to change plants, the previous lot will be closed and a new lot will be opened. The numbering for the lots produced at the new plant will start with No. 1. If allowed to switch back to the original or previous plant, the next lot from that plant will resume numbering sequentially from the last lot produced by that plant.
10. Schedule lay-down placement where uneven travel lanes are minimized and eliminated weekly.
11. If asphalt material is obtained from other than a commercial source presently inspected by TxDOT, furnish a Type D structure for the asphalt mix control laboratory for the Engineer's use. Provide a minimum height of 8 feet and a minimum of 400 square feet of gross floor area for permanently located asphalt plants or 200 square feet for a temporary plant. The floor area will be partitioned into a minimum of two rooms, with a minimum of two windows

County: Bexar

Highway: Lp 1604

per room. The floor shall have an impervious cover and sufficient strength to support the testing equipment. Portable structures shall be support blocked for stability and shall be tied down.

12. The use of Recycled Asphalt Shingles (RAS) will not be allowed on the final riding surface.

Minimum Roadway Placement Temperature

--Item 341--

1. Place mixture when the roadway surface temperature is equal to or higher than listed in Table 1 unless otherwise approved or shown on the plans. Measure the roadway surface temperature with a hand-held thermal camera or infrared thermometer. Placement may be allowed to begin prior to the roadway surface reaching the required temperature if conditions are such that the roadway surface will reach the required temperature within 2 hrs. of beginning placement operations. Place mixtures only when weather and moisture conditions of the roadway surface are suitable in the opinion of the Engineer. The Engineer may restrict the Contractor from paving if the ambient temperature is likely to drop below 32°F within 12 hr. of paving.

Table 1
Minimum Pavement Surface Temperatures

Specification Item Number	High Temperature Binder Grade	Minimum Pavement Surface Temperatures in Degrees Fahrenheit *	
		Subsurface Layers or Night Paving Operations	Surface Layers Placed in Daylight Operations
341	PG 64	45	50
	PG 70	55	60
	PG 76	60	60

* Except for PG 64, may pave at temperatures 10° F lower than the values shown in Table 1 when utilizing a Material Transfer Vehicle that is capable of providing a remixing, and continuous flow of material from the haul truck to the paver, such as a Roadtec SM-2500e/ex, that eliminates thermal segregation. In these cases, use either an infrared bar attached to the paver, or a hand held thermal camera or infrared thermometer, or a hand held infrared thermometer operated in accordance with Text Method 244-F to demonstrate that the uncompacted mat has no more than 10° F of thermal segregation.

County: Bexar

Highway: Lp 1604

**Substitute Binder
--Item 341--**

The Contractor may use a substitute PG binder listed below in Table 1 instead of the PG binder originally specified in Table 5 of the Standard Specification, if the substitute PG binder and mixture made with the substitute PG binder meet the following:

- ◆ The substitute binder meets the specification requirements for the substitute binder grade in accordance with Section 300.2.10., “Performance-Graded Binders;” and
- ◆ The mixture has less than 10.0 mm of rutting on the Hamburg Wheel test (Tex-242-F) after the number of passes required for the originally specified binder. Use of substitute PG binders may only be allowed at the discretion of the Engineer if the Hamburg Wheel test results are between 10.0 mm and 12.5 mm.

Table 1
Allowable Substitute PG Binders and Maximum Recycled Binder Ratios

Originally Specified PG Binder	Allowable Substitute PG Binder	Maximum Ratio of Recycled Binder ¹ to Total Binder (%)		
		Surface	Intermediate	Base
HMA				
76-22 ^{2,5}	70-22	20.0	20.0	20.0
	70-28	20.0	35.0	40.0
70-22 ²	64-22	20.0	20.0	20.0
	64-28 or 58-28	20.0	35.0	40.0
64-22 ²	58-28	20.0	35.0	40.0
76-28 ^{2,5}	70-28	20.0	20.0	20.0
70-28 ²	64-28 or 58-28	20.0	20.0	20.0
	64-34 or 58-34	20.0	35.0	40.0
64-28 ²	58-28	20.0	20.0	20.0
	58-34	20.0	35.0	40.0
WMA³				
76-22 ^{2,5}	70-22	20.0	35.0	40.0
70-22 ²	64-22 or 58-28	20.0	35.0	40.0
64-22 ⁴	58-28	20.0	35.0	40.0
76-28 ^{2,5}	70-28	20.0	35.0	40.0
70-28 ²	64-28 or 58-28	20.0	35.0	40.0
64-28 ⁴	58-28	20.0	35.0	40.0

1. Combined recycled binder from RAP and RAS.
2. Use no more than 20.0% recycled binder when using this originally specified PG binder.
3. WMA as defined in Section 341.2.6.2., “Warm Mix Asphalt (WMA).”
4. When used with WMA, this originally specified PG binder is allowed for use at the maximum recycled binder ratios shown in this table.
5. No more than 1-PG grade lower than what is show on the plans will be permitted for Surface mixtures

County: Bexar

Highway: Lp 1604

--Item 354--

Retain planed material.

Take precaution to avoid damage to existing bridge decks and armor joints. Repair any damage to the bridge decks and/or armor joints as approved. This work will not be paid directly, but will be performed at the Contractor's expense.

--Item 401--

A shrinkage compensator is not required for when used for backfilling pipes. Strength of the Flowable Backfill will be verified by the District Laboratory. Field testing is not required, unless deemed necessary.

Rapid Set flash fill may be used for any pipe or box crossings in limits of cut and restore pavement, as approved by Engineer. This will be considered subsidiary to the flowable backfill item.

--Item 420--

Mass concrete will be measured in place.

Restrict large aggregate size to $\frac{3}{4}$ " maximum for class "C" concrete used in aesthetic details requiring form liners.

--Item 421--

Use an automated ticket that contains the same information as TxDOT's ticket. Submit the ticket for approval prior to use. The concrete producer will contact the District Laboratory or the Engineer's Office (outside the San Antonio area) to inform TxDOT of scheduled structural concrete batching. Structural concrete includes bridge drill shafts, columns, caps, abutments, deck or top slabs of direct traffic culverts.

Entrained air is allowed for Class P and Class HES concrete only. Air content testing is waived for all classes of concrete.

Poly-fiber reinforced concrete may be used as an option, with the approval by the Engineer, for riprap, sidewalk, curb/gutter, and mow strip. Use a TxDOT approved manufacturer or producer for the poly-fiber. The poly-fibers shall be combined with the concrete in proportions as recommended by the manufacturer. A concrete mix design must be approved by the Engineer.

--Item 422--

For construction of approach slabs, longitudinal joints shall be placed on lane lines. Joints may be either a saw-cut crack control joint or a construction joint. Saw cut joints shall terminate 1'-0" before reaching the edge of the slab, must be saw cut as soon as possible after placement of concrete, and will be cut within 12 hours of concrete placement. Once sawing begins, it should

County: Bexar

Highway: Lp 1604

be a continuous operation and should only be stopped if raveling occurs. Saw cut will be to a depth of 1.5" and filled with approved joint sealant.

--Item 423--

The backfill material for pre cast retaining walls shall be approved before placement. Build stockpile(s) in lifts not to exceed 2 feet and a minimum working face of not less than 10 feet, but not more than 20 feet.

Use the approved Concrete Block Retaining wall systems listed at:

http://www.dot.state.tx.us/business/contractors_consultants/bridge/retaining_wall.htm

Use the approved Mechanically Stabilized Earth (MSE) wall systems listed at:

http://www.dot.state.tx.us/business/contractors_consultants/bridge/retaining_wall.htm

TxDOT does not allow the use of experimental systems on projects with over 50,000 square feet walls over 25 ft. tall, or walls supporting or immediately adjacent to interstate highways.

When proprietary wall systems are used, a qualified representative of the retaining wall manufacturer must be available upon request during wall construction. As requested or required the manufacturer's representative must be on site to assist with the initial stages of wall construction, provide training to the Contractor wall crew and ensure proper interpretation of MSE wall shop drawings and details. Specific attention must be given to nonstandard wall installation details. The Contractor's wall crew foreman must be on site for the duration of wall construction. Any change to the wall crew foreman may require additional training by the wall supplier. The Contractor will ensure that the retaining walls are installed per the details presented in the construction drawings and as per the proprietary wall system requirements. The Engineer reserves the right to suspend wall construction activities due to any construction issue encountered.

Horizontal and vertical nail spacing on temp or permanent soil nail walls shall not exceed 4 ft.

Type DS material will be required on MSE walls in the area of the reinforcement mats.

Retaining wall foundation soil (Ty C Embankment): $8 < PI < 28$, $LL < 40$

--Item 432--

In all riprap slopes, provide 3 inch diameter weep holes at 10 foot maximum spacing and backed with loose graded gravel or crushed stone and galvanized hardware cloth.

County: Bexar

Highway: Lp 1604

In areas where guard fence posts are to be placed in riprap, the riprap shall have an 18 inch +/- blocked out area (round or square). Blocked out areas shall be backfilled with 2 sack flowable backfill and considered subsidiary to the various bid items.

Match the slope of the Riprap (Mow Strip) to the slope of the adjacent roadway.

--Item 454--

The list of approved Header Type Expansion Joints can be found at: http://www.txdot.gov/txdot_library/publications/producer_list.htm title is "Elastomeric Concrete".

--Item 462--

Use lean concrete or 2 sack flowable backfill for fill between pre-cast boxes. Lean concrete and 2 sack flowable backfill shall be considered subsidiary to this bid item.

The following structures shall be cast-in-place:

UNNAMED TRIBURARY 5 TO CARACOL CREEK MBC NO.2 and
CULVERT NO. 2

The following structures shall be pre-cast:

CULVERT NO. 1, CULVERT NO. 3, CULVERT NO. 4, AND
CULVERT NO. 5.

--Item 465--

Concrete Class B invert shaping is required at all inlets, manholes and junction boxes in order to insure positive flow. The material and work performed for the placement of the inverts shall be considered subsidiary to this item.

--Item 496--

The Contractor will submit a demolition plan for all structures to be replaced and/or removed in accordance with Item 496.

Provide for the safety and health of employees and abide by all OSHA Standards and Regulations. All costs incurred for proper management, shall be subsidiary to this Item.

--Item 500--

"Materials on Hand" payments will not be considered in determining percentages for mobilization payments.

County: Bexar

Highway: Lp 1604

--Item 502--

The Contractor Force Account "Safety Contingency" that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor's Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

Place standard markings no later than 14 days after surface treatment operations are completed.

When advanced warning flashing arrow panels and/or changeable message sign is specified, have one standby unit in good condition at the job site. Standby time shall be considered subsidiary to the bid item.

Treat the pavement drop-offs as shown in the TCP.

After written notification, the time frame to provide properly maintained signs and barricades before considered in non-compliance is 48 hours from receipt of the notification. Failure to make corrections as noted may result in payment for this item being withheld.

There are traffic signals at the intersection of Potranco Rd. and Loop 1604, Military Rd. and Loop 1604, and Wiseman Blvd and Loop 1604. Keep the signals in operation except when necessary for specific installation operations.

Moving an existing sign to a temporary location is subsidiary to this Item. Installations with permanent supports at permanent locations will be paid for under the applicable bid item (s).

Mount temporary mailboxes on plastic drum in accordance with Compliant Work Zone Traffic Control Devices, Section K. Mounting and moving the mailbox as needed for the various construction phases is subsidiary to this Item.

Notify the Engineer in writing 10 business days in advance of any temporary or permanent lane, ramp, connector, etc. closures/detours, restrictions to lane widths, alterations to vertical clearances, or modifications to radii. Any other modifications to the roadway that may adversely affect the mobility of oversized/overweight trucks also require 10 business days advance written notice to the Engineer. Unless shown in the TCP, no lane, ramp, connector, etc. closures are allowed during special events. At least one lane has to remain open at all times. Lane closures will not be allowed if this reporting requirement is not met.

Avoid placing stockpiles within the roadway's horizontal clear zone. If a stockpile is placed within the clear zone, address in accordance with the TMUTCD.

County: Bexar

Highway: Lp 1604

Do not place barricades, signs, or any other traffic control devices where they interfere with sight distance at driveways or side streets.

In addition to providing a Contractor's Responsible Person and a phone number for emergency contact, have an employee available to respond on the project for emergencies and for taking corrective measures within 2 hours or within a reasonable time frame as specified by the Engineer.

Temporary Rumble Strips are to be used according to WZ (RS)-14.

Use 2_number of rumble strip arrays.

If Nighttime work is required and work is not behind positive barrier then full TY 3 reflective gear is required to be worn by all workers, hard hat halos are required to be worn by the flaggers at flagging stations, TY III barricades are required to be spaced at 500 ft, and a mandatory night work meeting is required.

--Item 504--

Furnish one field office Type B with a working alarm system.

Enclose the field office and the parking area as shown in 504.2.1.1 and provide security lighting.

Provide wi-fi internet connectivity (minimum of 30 GB), a color printer/fax/scanner/copier, and telephone(s) as directed.

Provide laboratory equipment necessary for testing (moist cabinet, moist room or water storage tank in accordance with Tex-498-A, Table 32 and Concrete Testing Machine in accordance with Tex-498-A, Table 18)

--Item 506--

An Inspector will perform a regularly scheduled SWP3 inspection every 7 calendar days.

Failure to address items noted on the SW3P inspection report within two report cycles may result in the Department stopping all construction operations, exclusive of time charges, or withholding that month's estimate until the SW3P deficiencies are corrected unless the Engineer determines that the area is too wet to correct SW3P deficiencies.

New Single Slope or F-Shape CTB (cast in accordance with the Standard Sheets in the plans) may be furnished or the same pre-used shapes (that meet the requirements of this Item) may be furnished. New Safety Shape (New-Jersey) CTB is not allowed, but pre-used New-Jersey (that meets the requirements of this Item) may be furnished. More than one type may be furnished but do not mix the types when placed along the roadway.

County: Bexar

Highway: Lp 1604

--Item 514--

The Type 3 CTB taper from the Type 2 at obstructions (OSB's, bridge, columns, etc.) shall be 40:1. If gravel is used between the barriers as shown by the Standard Sheet, the top six inches shall be CL A concrete.

--Item 529--

Class "C" concrete is required for machine extruded curb.

Curb inlets and extensions are based on an exposed curb height of 7 inches. The roadway curb height and shape will be transitioned to the inlet's curb with a 40: 1 taper.

--Item 531--

The curb ramp locations shown in the plans have taken into account the geometric features of the intersection, traffic signals, and the pavement markings. If anything changes during construction, the location of curb ramps must be adjusted to ensure they meet TAS requirements.

--Item 540--

MBGF posts shall be round with domed tops, and not painted. If 10 or less timber posts are needed, they may be purchased locally and will be accepted by visual inspection.

Guard fence posts placed in proposed and/or existing areas of riprap, sidewalks or other concrete shall have an 18 inch +/- (square or round) block out in the concrete. After the posts are installed, the blocked out area shall be topped off with 4 inches of low strength grout/mortar consisting of about 1 sack of cement per cubic yard of mix.

When connecting a Thrie-Beam to a concrete wingwall, bridge rail, CTB, etc., drill the holes for bolt placement using rotary or core type equipment. Use a core type drill when reinforcing steel is encountered. Do not use percussion or impact drilling. Repair damage to the concrete and spalls exceeding 1/2" from the edge of the hole.

--Item 542--

Salvage all undamaged/acceptable radius guardrail and deliver to the TxDOT maintenance section yard.

--Item 545--

See the Crash Cushion Summary Sheet.

--Item 585--

Use Surface Test Type B, pay adjustment schedule 1 to evaluate ride quality of travel lanes.

County: Bexar

Highway: Lp 1604

--Item 610--

Fabricate steel roadway illumination poles in accordance with the RIP standards. Poles fabricated according to RIP require no shop drawings. Alternate designs or the use of aluminum to fabricate poles will require the submission of shop drawings electronically.

For instructions on submitting shop drawings electronically go to:

<http://www.dot.state.tx.us/publications/bridge.htm>. File is titled: Guide to Electronic Shop Drawing Submittal.

Provide lamps from the pre-qualified Materials Producers List, Category is "Roadway Illumination and Electrical Supplies" located on the Construction Divisions (CST) web site.

Ballast/capacitors removed from the light assembly, will remain the property of the State. Assume all ballast/capacitors contain Polychlorinated Biphenyl (PCB), unless a notation appears on the outside of the unit that specifies it does not contain PCB's. All ballast/capacitors with PCB's shall be placed in 55 gallon open top drum in accordance with Department of Transportation (DOT) specifications. Place six (6) inches of sawdust or other absorbent material in the bottom of the drum. Furnish and place a DOT approved PCB warning label on the outside of the drum. Do not fill a drum more than $\frac{3}{4}$ of capacity. Avoid rupturing the ballast/capacitor(s). If a ballast/capacitor is ruptured, use proper procedures, specialist trained staff and personal protective equipment for the clean-up operations.

The lamps in light fixtures may contain hazardous levels of mercury, halide, and sodium vapors. Observe and comply with all federal, state and local laws, ordinances and regulations regarding the management of these lamps. Prevent the breakage of the lamps. At a minimum, package all lamps removed from the light fixture(s) in a container that minimizes the breakage of the lamps. Broken lamps shall be collected in a sealed plastic bag (i.e. Ziploc). Broken lamps shall be stored in separate containers from unbroken lamps. Furnish a suitable container and attach a label stating "Universal Waste Lamps" on the container. Write the date the first lamp was placed in the container on the "Universal Waste Lamp" label. Within one (1) week after the first lamp is placed in a container, notify the Engineer. The lamps and PCB containing ballast/capacitors, placed in properly labeled containers, will remain the property of the State. Place the container in an area where it is protected from damage and the elements. The Engineer will make arrangements to collect, transport, and dispose/recycle the container. The ballast/capacitor and lamp's removal and storage is subsidiary to this item.

Stencil each illumination assembly with the circuit, light and relay numbers in black paint on the roadway side of the pole at a 45 degree angle. The numbers shall be in 3" tall and begin 6' from the top of the foundation. This work will be considered subsidiary to this item.

--Item 618--

It might be necessary to cut concrete for placement of conduit. Saw cut existing concrete, remove the concrete from the steel reinforcement (bars or fabric) and bend the steel to install the

County: Bexar

Highway: Lp 1604

conduit. After the conduit has been placed, bend the steel back to its original position and back-fill the trench with an approved concrete. This work is subsidiary to this Item.

The conduit depth for illumination under the City of San Antonio streets is 36 inches.

Use materials from Material Producers list as shown on the Construction Division's (CST) web site. Category is "Roadway Illumination and Electrical Supplies."

--Item 620--

For both transformer and shoe-base type illumination poles, provide double-pole breakaway fuse holder as shown on the Construction Division's (CST) materials producers list Category is "Roadway Illumination and Electrical Supplies." Fuse holder is shown on list under Items 610 & 620.

Provide 10 amp time delay fuses.

--Item 628--

Make all arrangements for electrical service, and compliance with local standards and practices for proper installations.

--Item 644--

The wedge anchor system shown on State Standard Sheet SMD (TWT) is not allowed.

--Item 658--

CTB reflectors will not be paid for directly but will be considered subsidiary to the barrier.

--Item 666--

If TY II material is used (vs. an acrylic or epoxy) as the sealer for the TY I markings, place the TY II a minimum of 14 calendar days (to provide adequate curing) before placing the TY I markings.

--Item 672--

Place all adhesive material directly from the heated dispenser to the pavement. Do not use portable or non-heated containers. Use adhesive of sufficient thickness so that when the marker is pressed into the adhesive, 1/8" or more adhesive will remain under 100% of the marker. The adhesive should extend not less than 1/2" but not more than 1 1/2" beyond the perimeter of the marker.

--Item 677--

Obtain approval before using the mechanical method for the elimination of existing thermoplastic pavement markings.

County: Bexar

Highway: Lp 1604

--Item 680--

Furnish and install all required materials and equipment necessary for the complete and operating traffic signal installation at the following intersections:

Potranco Rd. and Loop 1604, Military Rd. and Loop 1604, and Wiseman Blvd and Loop 1604.

The locations shown on the plans for signal pole foundations, controller foundations, conduit and other items may be adjusted to better fit field conditions as approved.

Demonstrate that the field wiring is properly installed, install the controller assembly, connect the wiring and turn on the controller.

All existing signal equipment with the exception of the signal controller and related equipment become the property of the Contractor. Deliver the controller and related equipment to the Signal shop, located at 4615 NW Loop 410 (corner of IH 410 and Callaghan Road) in San Antonio, Texas or to the Area Office as directed.

--Item 682--

Provide all signal heads from the same manufacturer. Pedestrian signals may be by a different manufacturer than the vehicle signal heads.

Cover all signal faces until placed in operation.

All pedestrian signal faces shall be single section LED Type. Die cast polycarbonate is acceptable in lieu of die cast aluminum. All mounting attachments shall be constructed of steel pipe and mounted as shown on the plans.

For all proposed mast arm pole assemblies, use mounting bracket assembly as shown on the State Standard Sheet(s) "Single Mast Arm Assemblies".

--Item 684--

Provide an extra 10' for each cable terminating in the controller cabinet. All cables shall be continuous without splices from terminal point to terminal point. All proposed signal cable shall be #14 AWG stranded copper.

--Item 686 & 687--

Provide all signal poles from the same manufacturer. Pedestrian poles may be from a different manufacturer.

--Item 688--

The pedestrian push button shall be raised or flush and a minimum of 2 inches in the smallest dimension. The force to activate the control shall be no greater than 5 lb/f. The button placement has to be coordinated with the concrete pad to access the button. The concrete pad (if required) shall be paid separately.

County: Bexar

Highway: Lp 1604

--Item 730--

Mow full-width and hand trim the right of way, including newly seeded or sodded areas, when vegetation reaches a height of 16" or when directed. Removal of brush sprouts growing within guardrail, concrete barriers or at other locations where mowing or hand trimming is done within the limits of construction is required and subsidiary to this item. Mowing may be required more often in newly sodded or seeded areas than in other parts of the project because of the supplemental irrigation these areas receive and the resulting weed growth. Coordinate mowing to avoid rutting or compaction of the soil when mowing where supplemental irrigation is being used. Use mowing equipment that will not adversely affect soil retention blankets or mulches that have been applied. Work performed under this item does not replace the mowing required when placing permanent seeding in an area that has established temporary seeding as described in Article 164.3, Construction.

Mowing Locations are described below.

Phase 1

Mow Area between existing Loop 1604 NB and SB mainlanes.

Mow area outside existing Loop 1604 NB mainlanes.

Total Acres = 37 ac

Phase 2

Mow area outside Proposed Loop 1604 Frontage Rd.

Mow area outside existing Loop 1604 NB mainlanes

Total Acres = 25 ac

--Item 734 & 738--

Perform Litter Removal and Cleaning and Sweeping Highways once a month or as directed.

Litter Removal

1 cycle per month. = 29 cycles

--Item 4001--

For Asphalt-Plug Expansion Joints, the following suppliers are approved:

FlexAble Bridge Joint System
Deery American Corporation.
PO Box 4099
Grand Junction, CO 81502
Attn: San Kearn
800-227-4059

County: Bexar

Highway: Lp 1604

Matrix 502 Asphalt Plug
D.S. Brown Co.
300 E. Cherry St.
North Baltimore, OH 45872
419-257-3561

Thorma-Joint
Dynamic Surface Applications, Ltd.
373 Village Road
Pennsdale, PA 17756
Attn: Mike Stachowicz
800-491-5663 Ext. 1

Wabo-Expandex
BASF
3011 Heatherpark Drive
Kingwood, TX 77345
Attn: Mark Huff
713-392-4833

--Item 4051--

Overhead electric and telecommunication lines are present and located in the vicinity of Sound Wall N. CPS Overhead Electric will require de-energizing of the neutral line during the construction of Sound Wall N. De-energizing can only occur between November and March. This will be paid for under Contractor's Force Account "De-Energize Overhead Utility Lines". Provide 4 weeks advance notice to CPS for de-energizing. Contact John Offer (210-416-4561) or Claudia Valles-Tovar (210-353-2226) for coordination details. A horizontal boom is recommended for construction to provide more vertical clearance during construction of Sound Wall N.

CPS Energy poles will require bracing during the construction of Sound Wall N. Contact CPS Energy Utility Coordination group (John Offer (jeoffer@cpsenergy.com), Anna Esquivel (apesquivel@cpsenergy.com) or Claudia Valles-Tovar (cvalles-tova@cpsenergy.com) eight (8) weeks prior to starting work on Sound Wall N to request pole bracing. This will be paid for under Contractor's Force Account "Utility Pole Bracing".

--Item 6001-- PORTABLE CHANGEABLE MESSAGE SIGN

Estimated Quantity For Message Sign

Phase 1

Total Number of Signs = 1

Southbound : 14 day advance notice for PCTB installation

5 day for PCTB installation

= 19 days

County: Bexar

Highway: Lp 1604

Phase 1A

Total Number of Signs = 1

Southbound: 14 day advance notice for PCTB installation.
5 day for PCTB installation
=19 days

Phase 2

Total Number of Signs = 1

Northbound: 14 day advance notice for PCTB installation.
5 day for PCTB installation
=19 days

Phase 3

Total Number of Signs = 1

Northbound: 14 day advance notice for PCTB installation.
5 day for PCTB installation
=19 days

Phase 3 (Overlay)

Total Number of Signs = 1

Southbound: 7 day advance notice for nighttime closure.
10 day for nighttime work
Northbound: 7 day advance notice for nighttime closure.
10 day for nighttime work.
=34 days

Intersection Work

Total Number of Signs = 4

7 day advance notice for nighttime closure.
10 day for nighttime work
(17 days @ 6 intesections x 4 signs = 408 days)

TOTAL DAYS = 518 days.

--Item 7078--

The LF unit bid measure for Extra Deep Manholes will be understood to be the vertical depth in feet of the manhole greater than six feet in vertical depth.

--Item 7077--

There is approximately 639 LF of Asbestos-Cement (AC) pipe to be removed as shown in the plans. Notify the Engineer 2 weeks in advance of performing work in this location so that arrangements can be made to contact the Specialty Contractor who will remove and dispose of this material.

County: Bexar

Highway: Lp 1604

TMS GENERAL NOTES

“TMS” is abbreviation for Traffic Management System.

Install proposed TMS equipment including TMS conduit, manholes, ground boxes, 96 and 12 strand Fiber Optic cables, and devices (DMS, CCTV, RVSD) within the project limits on Loop 1604. Establish wireless Ethernet radio connection to equipment on adjacent (to the north) segment of Loop 1604 bypassing the future SH-151 interchange. Establish a communication path (back to TransGuide) for all the TMS equipment. Install solar flashing wrong way signs at exit ramps.

Coordinate the installation of permanent TMS equipment, conduit, manholes, ground boxes, etc. with the roadway construction phasing so as to prohibit any open cuts across new construction.

Cover Dynamic Message Signs (DMS) that are not in service with a blue tarp until such time that they are fully operational with the TRANSGUIDE system, subsidiary to the various bid items.

All references to the TRANSGUIDE mainframe are references to the TRANSGUIDE computer network.

Provide a submittal compliance matrix with all TMS submittals.

Perform all TMS Prototype approval, Design approval, and Demonstration tests within the State of Texas.

Not previously used TMS equipment: Test any TMS Equipment (including but not limited to CCTV field equipment), which has not previously been proven to be fully operational and fully compatible with the existing TRANSGUIDE software and hardware in the following manner:

Conduct tests for each type of TMS equipment, as directed by the Engineer, to determine compatibility of the equipment with the existing TRANSGUIDE software and hardware. Prior to field installation, test one complete unit with all components to ensure that it is fully compatible with the existing TRANSGUIDE system. Mount the equipment to a trailer and connect in the field to an existing Fiber Hub. Make all hardware connections and configuration (in the operations center and in the field) and provide all incidentals (cable, connectors, etc.) to make the unit operational. Test all aspects of the system to show full functionality of the equipment and to show full compatibility with the TRANSGUIDE software and hardware. Failure to perform to the requirements of any test will be considered as a defect, and the equipment will be subject to rejection by the Engineer. Rejected equipment may be offered again for retest provided all noncompliance's have been corrected and retested by the Contractor and evidence thereof submitted to the Engineer. Testing is considered subsidiary to the particular bid item, with no payment made.

County: Bexar

Highway: Lp 1604

Partial payments:

The contractor will receive partial payments for the following TMS items unless otherwise approved by the Engineer.

Radar Vehicle Sensing Device

CCTV Field Equipment

ITS Cabinet

ITS Radio (Dual)

Dynamic Message Sign System

Partial Payments Consist of The Following:

Materials On Hand: The Contractor's paid amount is based on the invoices for the material received and stored in his/her yard.

Field Installation: When the Contractor has completed the installation of the Radar Vehicle Sensing Device (RVSD), the department will pay up to 80% of the bid item.

Stand-Alone Test: When the Radar Vehicle Sensing Device (RVSD) has passed the stand-alone test, the department will pay up to 95% of the bid item.

When the Radar Vehicle Sensing Device (RVSD) has passed the test portion of the Final Acceptance Test, the Department will pay the final 5% of the bid item.

Field Installation for CCTV Field Equipment, ITS Cabinet: When the Contractor has completed the support structure, mounted the CCTV camera, installed the ITS Cabinet(s), the Department will pay up to 80% of the bid item.

Stand-Alone Test: When the CCTV Field Equipment and ITS Cabinet has passed the stand-alone test, the Department will pay up to 95% of the bid item.

When the CCTV Field Equipment and ITS Cabinet has passed the test portion of the final acceptance test, the Department will pay the final 5% of the bid item.

Field Installation for "ITS Radio (Dual)":

When the contractor has completed installation of the ITS Radio (Dual) Link, the Department will pay up to 50% of the bid item.

Integration for "Install ITS Radio (Dual)":

When the ITS Radio Link has been installed, configured, and made operational with the TransGuide system, the Department will pay the final 50% of the bid item.

County: Bexar

Highway: Lp 1604

Field Installation: When the Contractor has completed the installation of the Dynamic Message Sign (DMS), the department will pay up to 80% of the bid item.

Stand-Alone Test: When the Dynamic Message Sign (DMS) has passed the stand-alone test, the department will pay up to 95% of the bid item.

When the Dynamic Message Sign (DMS) has passed the test portion of the final acceptance test, the Department will pay the final 5% of the bid item.

The above percentages do not include the deduction of standard Retainage.

TMS Submittals:

Include in all TMS submittals the respective bid item (specification number and descriptive code). Indicate compliance on a paragraph-by-paragraph basis. Ensure that the statements claiming compliance reference the appropriate documentation and the referenced documentation supporting this claim is included with the submittal. Provide referenced documentation that contains the same numbering system as referenced in the submittal. For example, submittal item XXXX-XXXX, Section 2.3, Paragraph 3, Meets Requirements (See Attachment “B”). The supporting documentation for Item XXXX-XXXX, Section 2.3, Paragraph 3, would be titled as Attachment “B”. Provide submittals with the same numbering system as stated in the specification. Failure to submit accordingly will result in rejection by the Engineer.

A TMS submittal will be considered as incomplete and therefore rejected, if it contains items listed as “being furnished by others”. It is the responsibility of the Contractor to make sure the submittal addresses all items of the specification.

Provide the following TMS submittals (to be received by TxDOT San Antonio Traffic Management office) within the designated time. The time frame is in calendar days.

Item Description	Submitted By Contractor W/I Days After Authorization To Begin Work	Returned By State W/I Days
Equipment & Interconnect Wiring Schematic	30	30
Fiber Optic Cable (Single Mode)	30	30
CCTV Field Equipment	30	30
ITS Pole (55 ft)(90 mph)	30	30
ITS Pole (30 ft)(90 mph)	30	30
ITS Pole Mnt. Cab. (TY 1)	30	30
ITS Pole Mnt. Cab. (TY 2)	30	30
Radar Vehicle Sensing Device (RVSD)	30	30
Communication Cable	90	15
Final Acceptance Plan	90	30

County: Bexar

Highway: Lp 1604

Submit those items designated with the (*), if any, together as a Package.

Submit the Final Acceptance Plan in electronic form.

The Contractor may submit items sooner if needed for construction, but no later than the dates stated above.

Provide, to the Engineer, as-built plans in MicroStation format (.dgn files) of the TMS portion of this project when the project is complete. TxDOT will provide the .dgn files of the TMS plan sheets. Update these files with all TMS items as ACTUALLY CONSTRUCTED in the field. Cost to provide as-built plans as described above is subsidiary to the various bid items with no direct payment.

Customize all training specifically for the TRANSGUIDE system; generic training will not be accepted on this project. Training materials and labor are subsidiary to the various Bid Items with no direct payment.

TMS equipment and conduit locations are approximate; the precise location is to be determined in the field, therefore the Contractor should not scale equipment off plan sheets. Plan sheets are to be used for visual location (vicinity). Equipment locations may have to be adjusted due to conflicts with utilities or other structures, as approved by the Engineer. Do not obstruct the natural flow of water with Traffic Management equipment. In low water areas, place Traffic Management equipment on high side of ditch.

Replace or repair any existing to remain Traffic Management Equipment, conduit, cables, etc. damaged during construction, subsidiary to the various bid items with no direct payment. Replace all pavement, sidewalk, curb, rip-rap or any item damaged during construction, subsidiary to the various bid items with no direct payment.

Stencil structure numbers on all new TMS structures for permanent identification as directed by the Engineer.

Ensure that all TMS equipment furnished and installed is completely compatible with the existing hardware and software located within the TRANSGUIDE operations center (i.e. TRANSGUIDE central software). TRANSGUIDE is unique and complicated. The Contractor should contact the Traffic Management Engineer for details on the system network architecture.

All new TMS equipment will be incorporated into the existing Network Management System, subsidiary to the various bid items.

Security against theft and vandalism of all Traffic Management equipment is the full responsibility of the Contractor until the date of final acceptance of the project by the Engineer.

County: Bexar

Highway: Lp 1604

Maintenance of all Traffic Management equipment furnished and installed on this project is the full responsibility of the Contractor until date of final acceptance of the project by the Engineer. All required documentation must be turned in before TxDOT will accept project for maintenance.

Submit a layout of equipment and interconnect wiring schematic for the TRANSGUIDE Control Center and Fiber Hubs for approval by the Engineer prior to ordering materials. Consider all interconnect wiring within the TRANSGUIDE Control Center and all interconnect wiring for all equipment in the plans and described within the specifications as subsidiary to the various Bid Items with no direct payment.

Perform all TMS electrical work and provide all TMS electrical materials in accordance with the National Electrical Code.

The location of utilities (including TMS), either underground or overhead, if shown within the right of way are approximate and must be verified by the Contractor before beginning construction operations. TRANSGUIDE will provide the approximate location of TMS equipment; however, it is the responsibility of the Contractor to determine the depth of the Traffic Management conduit.

In accordance with the Underground Facility Damage Prevention Act (One Call Bill) the phone number for a utility locator is 1-800-545-6005. It is the Contractor's responsibility to make arrangements for utility locators as needed.

TxDOT (Traffic Management)	(210)731-5109
TxDOT (Sign Lighting)	(210)615-6995
TxDOT (Traffic Signal)	(210)615-5975

In preparing holes for TMS posts and/or foundations, use care so as not to rupture existing drainage structures, sprinkler systems, electrical conduits and public utilities.

Place small signs on ramps and frontage roads at a lateral clearance of 8 feet to 12 feet from the edge of pavement or as directed by the Engineer.

When installing TMS foundations where rip-rap presently exists, use care in breaking out existing rip-rap. Do not break out area greater than is required for placement of the foundations. Replace broken out rip-rap with class "B" concrete to the exact slope, pattern and thickness of the existing rip-rap in accordance with item 432, subsidiary to the various bid items with no direct payment.

County: Bexar

Highway: Lp 1604

Work on TMS equipment that integrates into the operational system only between the hours of 12:00 am (midnight) and 4:00 am when the work requires an interface with the TRANSGUIDE operational system. Notify the TransGuide maintenance manager (210-731-5109) 48 hrs prior to this work.

The contractor is fully responsible for all necessary cross connects, provisioning and cabling in the TRANSGUIDE computer room and Fiber Hubs, subsidiary to the various bid items.

--Item 421 & 427--

Finish all TMS concrete structures with a Grade I Class B, Type I finish or as approved by the Engineer.

--Item 465—

Install 50 feet of trunkline fiber optic cable (single mode) inside all manholes or as shown on plans, racked to the side of manhole. Provide rack and hooks to support the cable, subsidiary to the various bid items with no direct payment. Partial construction of manholes will not be permitted unless the contractor provides adequate protection.

Protect all TMS equipment with metal beam guard fence, terminal anchor sections and single guard rail terminals. Install metal beam guard fence with terminal anchor sections and single guardrail terminal immediately after the creation of the TMS obstruction. Failure to do so will result in stoppage of all other work on the project until the installation of guard fence is complete.

Do not install metal beam guard fence for TMS equipment until the exact location of the TMS equipment to be protected has been determined. Obtain prior approval from the engineer before the metal beam guard fence is installed and prior to ordering materials. Due to field conditions the quantity may be reduced. The engineer's approval does not relieve the contractor of his/her responsibility for correctness. Any adjustments to TMS equipment or metal beam guard fence with TAS and SGT's will be at no cost to the department.

---Item 618---

Make all TMS underground conduit bends of 45 degrees or more in PVC systems, including bends into ground boxes, with rigid metal conduit, subsidiary to the various bid items with no direct payment. Ensure that grounding is in accordance with ED sheets.

Steel case all TMS PVC bores, subsidiary to the item "conduit" with no direct payment for labor or materials.

Install a permanent pull cord all new TMS conduit and innderducts which do not contain cables. Provide pull cords that have a minimum tensile strength of 1250 lbs. and are flat with footage markings for determining length installed. Provide pull cords that are water-resistant and resistant to environmental conditions within conduit. Pull cords installed will be considered incidental to the various bid items with no direct payment made for labor and materials.

County: Bexar

Highway: Lp 1604

Install a single 1/C #14 AWG insulated wire (tracer wire) in TMS conduit that does not contain copper cables or contains fiber optic cable only and no copper cables, for the purpose of locating that conduit after installation, subsidiary to the item "conduit".

When installing TMS conduit in areas where riprap presently exists, use care and do not break out more riprap than is necessary for placement of conduit. Replace riprap with concrete to the exact slope, pattern and thickness of existing riprap, subsidiary to the various bid items with no direct payment.

Where shown in plans, install TMS concrete encased conduit with a minimum of 2 inches of encasement. Provide a template at 10 foot intervals to ensure that the conduit remains in its original position as approved by the engineer. Templates are considered subsidiary to the item "conduit" with no direct payment.

TMS bore lengths shown on plan sheets are approximate. Length of bore is measured starting 3 feet from each edge of pavement, curb and gutter, or any unforeseen existing utility, and balance of conduit run is measured as trenched conduit.

--Item 620--

Wire nuts for TMS installation are not permitted.

In locations where TMS service conductors are routed through ground boxes with other cables, install a section of flexible PVC conduit in the ground box. Route the service conductors through this conduit to keep it separated from other cables. Isolate all other cables in the ground box in the same manner. Furnishing and installing the flexible PVC conduit is subsidiary to the various bid items with no direct payment.

To ensure immediate identification, consistently color code and permanently identify all TMS power conductors, twisted wire pair cables, shielded cables, control cables, and fiber optic cables in all manholes, ground boxes, and at all termination points and splices. Submit a chart or list identifying all cables and conductors in a logical and sequential manner.

Install all TMS conductors and cables continuous and without splices from terminal point to terminal point unless otherwise shown on the plans.

The TMS plans show the conduits numbered and specified cables in specific conduits. The purpose of these notes is to instruct the contractor on how to group the cables in the conduits and not to specify the exact conduit to carry the cables. The numbering system is arbitrary and may be set by the contractor.

Provide an electrical conductor insulated ground in accordance with the National Electrical Code for any TMS conduit containing electrical conductors (insulated).

County: Bexar

Highway: Lp 1604

Test all TMS circuits to be clear of faults, grounds or open circuits.

--Item 624—

Place concrete aprons around all TMS ground boxes installed in sodded areas or as directed/approved by the Engineer.

Complete construction of TMS ground boxes within 48 hours after beginning construction for that ground box.

Provide TMS ground boxes as shown as state standard sheet ED (3)-03. Construct the cover of polymer concrete. Legibly imprint the cover with the letters “TMS” – “Danger High Voltage” in minimum 1 inch letters.

--Item 628—

Construct the TMS electrical services as shown on the TMS Electrical Service Data sheets.

--Item 6003 -- ITS SYSTEM SUPPORT EQUIPMENT

Furnish the following TMS equipment to TRANSGUIDE maintenance (210-731-5109), meeting the specifications in this contract:

- 2 ea Radar Vehicle Sensing Devices with all mounting hardware
- 4 ea Radar Vehicle Sensing Device lighting surge protectors
- 2 ea CCTV Field Equipment

--Item 6010 -- CCTV FIELD EQUIPMENT

CCTV Field Equipment standard manufacturers' warranty will not begin until the Final Acceptance Test begins. Any CCTV Field Equipment not having 100% of the standard manufacturer's warranty remaining when Final Acceptance testing begins will be rejected by TxDOT.

Ensure that all underground coaxial cable is RG-11 (double shielded) or as recommended by the manufacturer of the CCTV Field Equipment.

Furnish and install CCTV communication/power cables recommended or supplied by the manufacturer of CCTV Field Equipment.

If no recommendation for communication/power cables is made by manufacturer of CCTV Field Equipment, the following cable to conduit assignment will be followed:

Conduit #1: Install coaxial drop cable and CCTV control cable.

Conduit #2: Install CCTV power cable.

County: Bexar

Highway: Lp 1604

If the CCTV Field Equipment power cable carries 24 VDC, then the power cable may be installed in the same conduit with the coaxial drop cable. If the CCTV control cables carry 115 VAC, then the control cables must be installed with the 115 VAC power cable in conduit #2.

In cases where the CCTV Field Equipment and conduit are to be mounted on an existing or proposed structure, review the structure and submit the mounting details to the engineer for approval.

--Item 6005-- FINAL ACCEPTANCE PLAN

The 60 day test will begin only when all TMS equipment installation, cabling, wiring, testing, field work, TRANSGUIDE operations center work, etc. for the entire project is completed and acceptable to TxDOT. Partial testing is not allowed.

--Item 6064—ITS POLE

The camera pole may be twelve (12) sided.

--Item 6071—FIBER OPTIC CABLE (SINGLE MODE)

This project requires the placement of fiber optic cable. Splicing fiber optic cable of different manufacturers may result in signal degradation as measured through splice loss and DB loss per mile. The contractor must supply documentation of the compatibility of the fiber types with the fiber optic cable submittals. If testing of the new fiber optic cable after installation shows evidence of signal degradation outside of tolerable specifications due to the use of different fiber types, the contractor is responsible for replacing the newly installed fiber optic cable with material that results in signal quality with specifications. A TxDOT representative will be present while the contractor is splicing fibers from two different manufacturers.

If any TMS fiber optic cable is damaged during construction, it will be repaired within 48 hours after detection of damage. The Contractor will be required to test the fiber and provide such tests to the Engineer for determining suitability for splicing. If no splice is permitted, the Contractor will replace the entire run (approx. 15,000 ft or actual length) at no direct cost to the Department. All fiber provided, tested and spliced will be in accordance with special specification "Fiber Optic Cable (Single Mode)".

Install 50 feet of slack of "trunkline" fiber optic cable in each manhole that fiber passes through, racked to side of manholes using support hooks. Rack and hooks are subsidiary to the item manhole with no direct payment.

Use ST connectors where fiber optic cables terminate in TMS equipment.

All fiber optic cable splices and connectors are subsidiary to the item "Fiber Optic Cable (Single Mode)", with no direct payment.

CONTROL : 2452-01-056, ETC
PROJECT : C 2452-1-56, ETC
HIGHWAY : SL 1604
COUNTY : BEXAR

TEXAS DEPARTMENT OF TRANSPORTATION

GOVERNING SPECIFICATIONS AND SPECIAL PROVISIONS

ALL SPECIFICATIONS AND SPECIAL PROVISIONS APPLICABLE TO THIS PROJECT ARE IDENTIFIED AS FOLLOWS:

STANDARD SPECIFICATIONS: ADOPTED BY THE TEXAS DEPARTMENT OF
----- TRANSPORTATION NOVEMBER 1, 2014.
STANDARD SPECIFICATIONS ARE INCORPORATED
INTO THE CONTRACT BY REFERENCE.

ITEMS 1 TO 9 INCL., GENERAL REQUIREMENTS AND COVENANTS
ITEM 100 PREPARING RIGHT OF WAY (100)
ITEM 104 REMOVING CONCRETE
ITEM 110 EXCAVATION (132)
ITEM 132 EMBANKMENT (100) (160) (204) (210) (216) (260) (400)
ITEM 161 COMPOST (160)
ITEM 164 SEEDING FOR EROSION CONTROL (162) (166) (168)
ITEM 168 VEGETATIVE WATERING
ITEM 247 FLEXIBLE BASE (105) (204) (210) (216) (520)
ITEM 260 LIME TREATMENT (ROAD-MIXED) (105) (132) (204) (210) (216)
(247) (300) (310) (520)
ITEM 310 PRIME COAT (300) (316)
ITEM 316 SEAL COAT (210) (300) (302) (340) (520)
ITEM 341 DENSE-GRADED HOT-MIX ASPHALT (300) (301) (320) (520) (585)
ITEM 354 PLANING AND TEXTURING PAVEMENT
ITEM 400 EXCAVATION AND BACKFILL FOR STRUCTURES (110) (132) (401)
(402) (403) (416) (420) (421) (423)
ITEM 401 FLOWABLE BACKFILL (421)
ITEM 402 TRENCH EXCAVATION PROTECTION
ITEM 403 TEMPORARY SPECIAL SHORING (410) (411) (423)
ITEM 416 DRILLED SHAFT FOUNDATIONS (405) (420) (421) (423) (440) (448)
ITEM 420 CONCRETE SUBSTRUCTURES (400) (404) (421) (422) (426) (427)
(440) (441) (448)
ITEM 422 CONCRETE SUPERSTRUCTURES (420) (421) (424) (438) (440) (448)
(454) (780)
ITEM 423 RETAINING WALLS (110) (132) (216) (400) (416) (420) (421) (424)
(440) (445)
ITEM 425 PRECAST PRESTRESSED CONCRETE STRUCTURAL MEMBERS (409)
(420) (421) (424) (426) (427) (434) (440) (442) (445)
ITEM 427 SURFACE FINISHES FOR CONCRETE (420)

ITEM 432 RIPRAP (247) (420) (421) (431) (440)
 ITEM 442 METAL FOR STRUCTURES (441) (445) (446) (447) (448)
 ITEM 450 RAILING (420) (421) (422) (424) (440) (441) (442) (445) (446)
 (448)
 ITEM 454 BRIDGE EXPANSION JOINTS (429) (442) (785)
 ITEM 459 GABIONS AND GABION MATTRESSES
 ITEM 460 CORRUGATED METAL PIPE (400) (402) (403) (445) (467) (476)
 ITEM 462 CONCRETE BOX CULVERTS AND DRAINS (400) (402) (403) (420)
 (421) (422) (424) (440) (464) (476)
 ITEM 464 REINFORCED CONCRETE PIPE (400) (402) (403) (467) (476)
 ITEM 465 JUNCTION BOXES, MANHOLES, AND INLETS (400) (420) (421) (424)
 (440) (476)
 ITEM 466 HEADWALLS AND WINGWALLS (400) (420) (421) (432) (440) (464)
 ITEM 467 SAFETY END TREATMENT (400) (420) (421) (432) (440) (442) (445)
 (460) (464)
 ITEM 496 REMOVING STRUCTURES
 ITEM 500 MOBILIZATION
 ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING
 ITEM 504 FIELD OFFICE AND LABORATORY
 ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL
 CONTROLS (161) (432) (556)
 ITEM 508 CONSTRUCTING DETOURS
 ITEM 512 PORTABLE CONCRETE TRAFFIC BARRIER (420) (421) (424) (440)
 (442)
 ITEM 528 COLORED TEXTURED CONCRETE AND LANDSCAPE PAVERS (132) (247)
 (275) (401) (420) (421) (440)
 ITEM 529 CONCRETE CURB, GUTTER, AND COMBINED CURB AND GUTTER (360)
 (420) (421) (440)
 ITEM 530 INTERSECTIONS, DRIVEWAYS, AND TURNOUTS (247) (260) (263)
 (275) (276) (292) (316) (330) (334) (340) (360) (421) (440)
 ITEM 531 SIDEWALKS (104) (360) (420) (421) (440) (530)
 ITEM 536 CONCRETE MEDIANS AND DIRECTIONIONAL ISLANDS (420) (421)
 (427) (440) (529)
 ITEM 540 METAL BEAM GUARD FENCE (421) (441) (445) (529)
 ITEM 543 CABLE BARRIER SYSTEM (421) (658)
 ITEM 544 GUARDRAIL END TREATMENTS
 ITEM 545 CRASH CUSHION ATTENUATORS (421)
 ITEM 610 ROADWAY ILLUMINATION ASSEMBLIES (416) (421) (432) (441) (442)
 (445) (449) (614) (616) (618) (620) (622) (624) (628)
 ITEM 617 TEMPORARY ROADWAY ILLUMINATION (416) (610) (613) (614) (618)
 (620) (621) (622) (624) (627) (628)
 ITEM 618 CONDUIT (400) (476)
 ITEM 620 ELECTRICAL CONDUCTORS (610) (628)
 ITEM 624 GROUND BOXES (420) (421) (432) (440) (618) (620)
 ITEM 628 ELECTRICAL SERVICES (441) (445) (449) (618) (620) (627) (656)
 ITEM 636 SIGNS (643)
 ITEM 644 SMALL ROADSIDE SIGN ASSEMBLIES (421) (440) (441) (442) (445)
 (636) (643) (656)
 ITEM 647 LARGE ROADSIDE SIGN SUPPORTS AND ASSEMBLIES (416) (421)
 (440) (441) (442) (445) (636)
 ITEM 650 OVERHEAD SIGN SUPPORTS (416) (420) (421) (441) (442) (445)
 (449) (618) (636) (654)
 ITEM 658 DELINEATOR AND OBJECT MARKER ASSEMBLIES (445)
 ITEM 662 WORK ZONE PAVEMENT MARKINGS (666) (668) (672) (677)

ITEM 666 RETROREFLECTORIZED PAVEMENT MARKINGS (316) (502) (662) (677)
 (678) (6040)
 ITEM 672 RAISED PAVEMENT MARKERS (677) (678)
 ITEM 677 ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS (300)
 (302) (316)
 ITEM 680 HIGHWAY TRAFFIC SIGNALS (416) (610) (618) (620) (624) (625)
 (627) (628) (636) (656) (682) (684) (686) (688)
 ITEM 681 TEMPORARY TRAFFIC SIGNALS (416) (610) (618) (620) (621) (622)
 (624) (625) (627) (628) (636) (644) (656) (680) (682) (684) (686)
 (687) (688) (690)
 ITEM 682 VEHICLE AND PEDESTRIAN SIGNAL HEADS
 ITEM 684 TRAFFIC SIGNAL CABLES
 ITEM 686 TRAFFIC SIGNAL POLE ASSEMBLIES (STEEL) (416) (421) (441)
 (442) (445) (449)
 ITEM 687 PEDESTAL POLE ASSEMBLIES (445) (449) (656) (682)
 ITEM 688 PEDESTRIAN DETECTORS AND VEHICLE LOOP DETECTORS (618)
 (624) (682) (684)
 ITEM 690 MAINTENANCE OF TRAFFIC SIGNALS (416) (421) (476) (610) (618)
 (620) (622) (624) (625) (627) (628) (636) (656) (680) (682) (684)
 (685) (686) (687) (688)
 ITEM 730 ROADSIDE MOWING
 ITEM 734 LITTER REMOVAL
 ITEM 740 GRAFFITI REMOVAL AND ANTI-GRAFFITI COATING (427) (446)

SPECIAL PROVISIONS: SPECIAL PROVISIONS WILL GOVERN AND TAKE
 ----- PRECEDENCE OVER THE SPECIFICATIONS ENUMERATED
 HEREON WHEREVER IN CONFLICT THEREWITH.

SPECIAL LABOR PROVISIONS FOR STATE PROJECTS (000---008)

WAGE RATES

SPECIAL PROVISION "SCHEDULE OF LIQUIDATED DAMAGES" (000---001)

SPECIAL PROVISION "NONDISCRIMINATION" (000---002)

SPECIAL PROVISION "SMALL BUSINESS ENTERPRISE IN STATE FUNDED
 CONSTRUCTION" (000---009)

SPECIAL PROVISION "IMPORTANT NOTICE TO CONTRACTORS" (000---010)

SPECIAL PROVISION "CERTIFICATE OF INTERESTED PARTIES (FORM 1295)"
 (000---249)

SPECIAL PROVISION "IMPORTANT NOTICE TO CONTRACTORS" (000---254)

SPECIAL PROVISION TO ITEM 2 (002---004)

SPECIAL PROVISION TO ITEM 6 (006---001)

SPECIAL PROVISIONS TO ITEM 7 (007---001) (007---003) (007---004)

SPECIAL PROVISIONS TO ITEM 8 (008---002) (008---006) (008---017)

SPECIAL PROVISION TO ITEM 300 (300---009)

SPECIAL PROVISION TO ITEM 506 (506---003)

SPECIAL PROVISION TO SPECIAL SPECIFICATION ITEM 6029 (6029--002)

SPECIAL SPECIFICATIONS:

ITEM 4051 SOUND WALLS (420) (421) (424) (425) (426) (427) (429) (440) (441)
 (442) (445) (446) (447) (448) (449)

- ITEM 4052 FIBERGLASS SOUND WALLS
- ITEM 6001 PORTABLE CHANGEABLE MESSAGE SIGN
- ITEM 6003 ITS SYSTEM SUPPORT EQUIPMENT (6005)
- ITEM 6005 TESTING, TRAINING, DOCUMENTATION, FINAL ACCEPTANCE, AND WARRANTY
- ITEM 6006 ELECTRONIC COMPONENTS
- ITEM 6010 CCTV FIELD EQUIPMENT (6005) (6006)
- ITEM 6025 RADAR PRESENCE DETECTION DEVICE
- ITEM 6028 INSTALLATION OF DYNAMIC MESSAGE SIGN SYSTEM (416) (432) (441) (445) (449) (618) (620) (650) (654) (656)
- ITEM 6029 RADAR VEHICLE SENSING DEVICE (RVSD) (6005) (6006)
- ITEM 6040 MOBILE RETROREFLECTIVITY DATA COLLECTION FOR PAVEMENT MARKINGS
- ITEM 6057 RADAR ADVANCE DETECTION DEVICE (RADD)
- ITEM 6058 BATTERY BACK-UP SYSTEM FOR SIGNAL CABINETS (420) (620)
- ITEM 6062 INTELLIGENT TRANSPORTATION SYSTEM (ITS) RADIO
- ITEM 6064 INTELLIGENT TRANSPORTATION SYSTEM (ITS) POLE WITH CABINET (416) (421) (440) (441) (442) (445) (449) (496) (618) (620) (740)
- ITEM 6071 FIBER OPTIC CABLE
- ITEM 6096 WRONG WAY DRIVER SIGN(S) AND RADAR EQUIPMENT (618) (620) (644) (656)
- ITEM 7027 NATURAL GAS PIPELINE
- ITEM 7076 GROUTING OF WATER MAINS
- ITEM 7077 WATER MAINS AND SERVICE LINES
- ITEM 7078 SANITARY SEWER
- ITEM 7079 TEMPORARY LINE STOP TYPE VALVE
- ITEM 7092 GROUTING OF GAS MAINS

GENERAL: THE ABOVE-LISTED SPECIFICATION ITEMS ARE THOSE UNDER WHICH
 ----- PAYMENT IS TO BE MADE. THESE, TOGETHER WITH SUCH OTHER
 PERTINENT ITEMS, IF ANY, AS MAY BE REFERRED TO IN THE ABOVE-
 LISTED SPECIFICATION ITEMS, AND INCLUDING THE SPECIAL
 PROVISIONS LISTED ABOVE, CONSTITUTE THE COMPLETE SPECIFI-
 CATIONS FOR THIS PROJECT.

Control 2452-01-056, ETC.

Project C 2452-1-56, ETC.

Highway SL 1604

County BEXAR

SMALL BUSINESS ENTERPRISES REQUIREMENTS

The following goal for small business enterprises is established:

SBE
8.5%

Special Provision to Item 000

Special Labor Provisions for State Projects



1. GENERAL

This is a "Public Works" Project, as provided under Government Code Title 10, Chapter 2258, "Prevailing Wage Rates," and is subject to the provisions of the Statute. No provisions in the Contract are intended to be in conflict with the provisions of the Statute.

The Texas Transportation Commission has ascertained and indicated in the special provisions the regular rate of per diem wages prevailing in each locality for each craft or type of worker. Apply the wage rates contained in the specifications as minimum wage rates for the Contract.

2. MINIMUM WAGES, HOURS AND CONDITIONS OF EMPLOYMENT

All workers necessary for the satisfactory completion of the work are within the purview of the Contract.

Whenever and wherever practical, give local citizens preference in the selection of labor.

Do not require any worker to lodge, board or trade at a particular place, or with a particular person as a condition of employment.

Do not charge or accept a fee of any from any person who obtains work on the project. Do not require any person who obtains work on the project to pay any fee to any other person or agency obtaining employment for the person on the project.

Do not charge for tools or equipment used in connection with the duties performed, except for loss or damage of property. Do not charge for necessary camp water.

Do not charge for any transportation furnished to any person employed on the project.

The provisions apply where work is performed by piece work, station work, etc. The minimum wage paid will be exclusive of equipment rental on any shipment which the worker or subcontractor may furnish in connection with his work.

Take responsibility for carrying out the requirements of this specification and ensure that each subcontractor working on the project complies with its provisions.

Any form of subterfuge, coercion or deduction designed to evade, reduce or discount the established minimum wage scales will be considered a violation of the Contract.

The Fair Labor Standards Acts (FLSA) established one and one-half (1-1/2) pay for overtime in excess of 40 hours worked in 1 week. Do not consider time consumed by the worker in going to and returning from the place of work as part of the hours of work. Do not require or permit any worker to work in excess of 40 hours in 1 week, unless the worker receives compensation at a rate not less than 1-1/2 times the basic rate of pay for all hours worked in excess of 40 hours in the workweek.

The general rates of per diem wages prevailing in this locality for each class and type of workers whose services are considered necessary to fulfill the Contract are indicated in the special provisions, and these rates govern as minimum wage rates on this Contract. A penalty of \$60.00 per calendar day or portion of a calendar day for each worker that is paid less than the stipulated general rates of per diem wages for any work done under the Contract will be deducted. The Department, upon receipt of a complaint by a worker,

will determine within 30 days whether good cause exists to believe that the Contractor or a subcontractor has violated wage rate requirements and notify the parties involved of the findings. Make every effort to resolve the alleged violation within 14 days after notification. The next alternative is submittal to binding arbitration in accordance with the provisions of the Texas General Arbitration Act (Art. 224 et seq., Revised Statutes).

Notwithstanding any other provision of the Contract, covenant and agree that the Contractor and its subcontractors will pay each of their employees and contract labor engaged in any way in work under the Contract, a wage not less than what is generally known as the "federal minimum wage" as set out in 29 U.S.C. 206 as that Statute may be amended from time to time.

Pay any worker employed whose position is not listed in the Contract, a wage not less than the per diem wage rate established in the Contract for a worker whose duties are most nearly comparable.

3. RECORD AND INSPECTIONS

Keep copies of weekly payrolls for review. Require subcontractors to keep copies of weekly payrolls for review. Show the name, occupation, number of hours worked each day and per diem wage paid each worker together with a complete record of all deductions made from such wages. Keep records for a period of 3 years from the date of completion of the Contract.

Where the piece-work method is used, indicate on the payroll for each person involved:

- Quantity of piece work performed.
- Price paid per piece-work unit.
- Total hours employed.

The Engineer may require the Contractor to file an affidavit for each payroll certifying that payroll is a true and accurate report of the full wages due and paid to each person employed.

Post or make available to employees the prevailing wage rates from the Contract. Require subcontractors to post or make available to employees the prevailing wage rates from the Contract.

Special Provision to Item 000

Small Business Enterprise in State Funded Projects



1. DESCRIPTION

The purpose of this Special Provision is to carry out the Texas Department of Transportation's policy of ensuring that Small Business Enterprise (SBE) has an opportunity to participate in the performance of contracts. If the SBE goal is greater than zero, Article A of this Special Provision shall apply to this Contract; otherwise, Article B of this Special Provision applies. The percentage goal for SBE participation in the work to be performed under this contract will be shown in the proposal.

2. DEFINITIONS

Small Business Enterprise (SBE) is a firm (including affiliates) certified by the Department whose annual gross receipts do not exceed the U.S. Small Business Administration's size standards for 4 consecutive years. Firms certified as Historically Underutilized Businesses (HUBs) by the Texas Comptroller of Public Accounts and as Disadvantaged Business Enterprises (DBEs) by the Texas Uniform Certification Program automatically qualify as SBEs.

2.1. Article A - SBE Goal is Greater than Zero.

2.1.1. **Policy.** The Department is committed to providing contracting opportunities for small businesses. In this regard, it is the Department's policy to develop and maintain a program in order to facilitate contracting opportunities for small businesses. Consequently, the requirements of the Department's Small Business Enterprise Program apply to this contract as follows:

2.1.1.1. The Contractor shall make a good faith effort to meet the SBE goal for this contract.

2.1.1.2. The Contractor and any Subcontractors shall not discriminate on the basis of race, color, national origin, age, disability or sex in the award and performance of this contract. These nondiscrimination requirements shall be incorporated into any subcontract and purchase order.

2.1.1.3. After a conditional award is made to the low bidder, the Department will determine the adequacy of a Contractor's efforts to meet the contract goal, as is outlined under Section 2, "Contractor's Responsibilities." If the requirements of Section 2 are met, the contract will be forwarded to the Contractor for execution.

The Contractor's performance, during the construction period of the contract in meeting the SBE goal, will be monitored by the Department.

2.1.2. **Contractor's Responsibilities.** These requirements must be satisfied by the Contractor. A SBE Contractor may satisfy the SBE requirements by performing at least 25% of the contract work with its own organization as defined elsewhere in the contract.

2.1.2.1. The Contractor shall submit a completed SBE Commitment Agreement Form for each SBE they intend to use to satisfy the SBE goal so as to arrive in the Department's Office of Civil Rights (OCR) in Austin, Texas not later than 5:00 p.m. on the 10th business day, excluding national holidays, after the conditional award of the contract. When requested, additional time, not to exceed 7 business days, excluding national holidays, may be granted based on documentation submitted by the Contractor.

2.1.2.2. A Contractor who cannot meet the contract goal, in whole or in part, shall document the good faith efforts taken to meet the SBE goal. The Department will consider as good faith efforts all documented explanations

that are submitted and that describe a Contractor's failure to meet a SBE goal or obtain SBE participation, including:

- 2.1.2.2.1. Advertising in general circulation, trade association, and/or minority/women focus media concerning subcontracting opportunities,
- 2.1.2.2.2. Dividing the contract work into reasonable portions in accordance with standard industry practices,
- 2.1.2.2.3. Documenting reasons for rejection or meeting with the rejected SBE to discuss the rejection,
- 2.1.2.2.4. Providing qualified SBEs with adequate information about bonding, insurance, plans, specifications, scope of work, and the requirements of the contract,
- 2.1.2.2.5. Negotiating in good faith with qualified SBEs, not rejecting qualified SBEs who are also the lowest responsive bidder, and;
- 2.1.2.2.6. Using the services of available minorities and women, community organizations, contractor groups, local, state and federal business assistance offices, and other organizations that provide support services to SBEs.
- 2.1.2.3. The good faith effort documentation is due at the time and place specified in Subarticle 2.(a). of this Special Provision. The Director of the DBE & SBE Programs Section will evaluate the Contractor's documentation. If it is determined that the Contractor has failed to meet the good faith effort requirements, the Contractor will be given an opportunity for reconsideration by the Department.
- 2.1.2.4. Should the bidder to whom the contract is conditionally awarded refuse, neglect or fail to meet the SBE goal and/or demonstrate to the Department's satisfaction sufficient efforts to obtain SBE participation, the proposal guaranty filed with the bid shall become the property of the State, not as a penalty, but as liquidated damages to the Department.
- 2.1.2.5. The Contractor must not terminate a SBE subcontractor submitted on a commitment agreement for a contract with an assigned goal without the prior written consent of the Department.
- 2.1.2.6. The Contractor shall designate a SBE contact person who will administer the Contractor's SBE program and who will be responsible for submitting reports, maintaining records, and documenting good faith efforts to use SBEs.
- 2.1.2.7. The Contractor must inform the Department of the representative's name, title and telephone number within 10 days of beginning work.
- 2.1.3. **Eligibility of SBEs.**
- 2.1.3.1. The Department certifies the eligibility of SBEs.
- 2.1.3.2. The Department maintains and makes available to interested parties a directory of certified SBEs.
- 2.1.3.3. Only firms certified at the time of letting or at the time the commitments are submitted are eligible to be used in the information furnished by the Contractor required under Section 2.(a) above.
- 2.1.3.4. Certified HUBs and DBEs are eligible as SBEs.
- 2.1.3.5. Small Business Size Regulations and Eligibility is referenced on e-CFR (Code of Federal Regulations), Title 13 – Business Credit and Assistance, Chapter 1 – Small Business Administration, Part 121 – Small Business Size Regulations, Subpart A – Size Eligibility Provisions and Standards.
- 2.1.4. **Determination of SBE Participation.** SBE participation shall be counted toward meeting the SBE goal in this contract in accordance with the following:

- 2.1.4.1. A Contractor will receive credit for all payments actually made to a SBE for work performed and costs incurred in accordance with the contract, including all subcontracted work.
- 2.1.4.2. A SBE Contractor or subcontractor may not subcontract more than 75% of a contract. The SBE shall perform not less than 25% of the value of the contract work with its own organization.
- 2.1.4.3. A SBE may lease equipment consistent with standard industry practice. A SBE may lease equipment from the prime contractor if a rental agreement, separate from the subcontract specifying the terms of the lease arrangement, is approved by the Department prior to the SBE starting the work in accordance with the following:
- 2.1.4.3.1. If the equipment is of a specialized nature, the lease may include the operator. If the practice is generally acceptable with the industry, the operator may remain on the lessor's payroll. The operator of the equipment shall be subject to the full control of the SBE, for a short term, and involve a specialized piece of heavy equipment readily available at the job site.
- 2.1.4.3.2. For equipment that is not specialized, the SBE shall provide the operator and be responsible for all payroll and labor compliance requirements.
- 2.1.5. **Records and Reports.**
- 2.1.5.1. The Contractor shall submit monthly reports, after work begins, on SBE payments, (including payments to HUBs and DBEs). The monthly reports are to be sent to the Area Engineer's office. These reports will be due within 15 days after the end of a calendar month.
- These reports will be required until all SBE subcontracting or supply activity is completed. The "SBE Progress Report" is to be used for monthly reporting. Upon completion of the contract and prior to receiving the final payment, the Contractor shall submit the "SBE Final Report" to the Office of Civil Rights and a copy to the Area Engineer. These forms may be obtained from the Office of Civil Rights and reproduced as necessary. The Department may verify the amounts being reported as paid to SBEs by requesting, on a random basis, copies of invoices and cancelled checks paid to SBEs. When the SBE goal requirement is not met, documentation supporting Good Faith Efforts, as outlined in Section 2.(b) of this Special Provision, must be submitted with the Final Report.
- 2.1.5.2. SBE subcontractors and/or suppliers should be identified on the monthly report by SBE certification number, name and the amount of actual payment made to each during the monthly period. **These reports are required regardless of whether or not SBE activity has occurred in the monthly reporting period.**
- 2.1.5.3. All such records must be retained for a period of 3 years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the Department.
- 2.1.6. **Compliance of Contractor.** To ensure that SBE requirements of this contract are complied with, the Department will monitor the Contractor's efforts to involve SBEs during the performance of this contract. This will be accomplished by a review of monthly reports submitted by the Contractor indicating his progress in achieving the SBE contract goal and by compliance reviews conducted by the Department.
- A Contractor's failure to comply with the requirements of this Special Provision shall constitute a material breach of this contract. In such a case, the Department reserves the right to employ remedies as the Department deems appropriate in the terms of the contract.
- 2.2. **Article B - No SBE Goal.**
- 2.2.1. **Policy.** It is the policy of the Department that SBEs shall have an opportunity to participate in the performance of contracts. Consequently, the requirements of the Department's Small Business Enterprise Program apply to this contract as specified in Section 2-5 of this Article.

- 2.2.2. **Contractor's Responsibilities.** If there is no SBE goal, the Contractor will offer SBEs an opportunity to participate in the performance of contracts and subcontracts.
- 2.2.3. **Prohibit Discrimination.** The Contractor and any subcontractor shall not discriminate on the basis of race, color, national origin, religion, age, disability or sex in the award and performance of contracts. These nondiscrimination requirements shall be incorporated into any subcontract and purchase order.
- 2.2.4. **Records and Reports.**
- 2.2.4.1. The Contractor shall submit reports on SBE (including HUB and DBE) payments. The reports are to be sent to the Area Engineer's office. These reports will be due annually by the 31st of August or at project completion, whichever comes first.
- These reports will be required until all SBE subcontracting or supply activity is completed. The "SBE Progress Report" is to be used for reporting. Upon completion of the contract and prior to receiving the final payment, the Contractor shall submit the "SBE Final Report" to the Office of Civil Rights and a copy to the Area Engineer. These forms may be obtained from the Office of Civil Rights and reproduced as necessary. The Department may verify the amounts being reported as paid to SBEs by requesting copies of invoices and cancelled checks paid to SBEs on a random basis.
- 2.2.4.2. SBE subcontractors and/or suppliers should be identified on the report by SBE Certification Number, name and the amount of actual payment made.
- 2.2.4.3. All such records must be retained for a period of 3 years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the Department.