

NOTIFICATION OF ADDENDUM

ADDENDUM NO. 1

DATED 5/03/2016

Control	6301-12-001
Project	RMC - 630112001
Highway	FM1340
County	KERR

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: RMC - 630112001

CONTROL: 6301-12-001

COUNTY: KERR

LETTING: 05/04/2016

REFERENCE NO: 0503

PROPOSAL ADDENDUMS

PROPOSAL COVER

BID INSERTS (SH. NO.:

GENERAL NOTES (SH. NO.:

X SPEC LIST (SH. NO.: SHEET 2-2

X SPECIAL PROVISIONS:

ADDED: 002---004, 007---004

DELETED:

SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

OTHER:

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

CONTROL : 6301-12-001
PROJECT : RMC - 630112001
HIGHWAY : FM1340
COUNTY : KERR

TEXAS DEPARTMENT OF TRANSPORTATION

GOVERNING SPECIFICATIONS AND SPECIAL PROVISIONS

ALL SPECIFICATIONS AND SPECIAL PROVISIONS APPLICABLE TO THIS PROJECT ARE IDENTIFIED AS FOLLOWS:

STANDARD SPECIFICATIONS: ADOPTED BY THE TEXAS DEPARTMENT OF
----- TRANSPORTATION NOVEMBER 1, 2014.
STANDARD SPECIFICATIONS ARE INCORPORATED
INTO THE CONTRACT BY REFERENCE.

ITEMS 1 TO 9 INCL., GENERAL REQUIREMENTS AND COVENANTS
ITEM 100 PREPARING RIGHT OF WAY (100)
ITEM 104 REMOVING CONCRETE
ITEM 110 EXCAVATION (132)
ITEM 247 FLEXIBLE BASE (105) (204) (210) (216) (520)
ITEM 316 SEAL COAT (210) (300) (302) (340) (520)
ITEM 340 DENSE-GRADED HOT-MIX ASPHALT (SMALL QUANTITY) (300) (301)
(320) (520) (585)
ITEM 354 PLANING AND TEXTURING PAVEMENT
ITEM 432 RIPRAP (247) (420) (421) (431) (440)
ITEM 460 CORRUGATED METAL PIPE (400) (402) (403) (445) (467) (476)
ITEM 500 MOBILIZATION
ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING
ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL
CONTROLS (161) (432) (556)
ITEM 512 PORTABLE CONCRETE TRAFFIC BARRIER (420) (421) (424) (440)
(442)
ITEM 529 CONCRETE CURB, GUTTER, AND COMBINED CURB AND GUTTER (360)
(420) (421) (440)
ITEM 530 INTERSECTIONS, DRIVEWAYS, AND TURNOUTS (247) (260) (263)
(275) (276) (292) (316) (330) (334) (340) (360) (421) (440)
ITEM 662 WORK ZONE PAVEMENT MARKINGS (666) (668) (672) (677)
ITEM 666 RETROREFLECTORIZED PAVEMENT MARKINGS (316) (502) (662) (677)
(678) (6040)
ITEM 672 RAISED PAVEMENT MARKERS (677) (678)
ITEM 677 ELIMINATING EXISTING PAVEMENT MARKINGS AND MARKERS (300)
(302) (316)
ITEM 764 PUMP STATION AND DRAINAGE SYSTEM CLEANING

SPECIAL PROVISIONS: SPECIAL PROVISIONS WILL GOVERN AND TAKE
----- PRECEDENCE OVER THE SPECIFICATIONS ENUMERATED
HEREON WHEREVER IN CONFLICT THEREWITH.

SPECIAL PROVISION "SCHEDULE OF LIQUIDATED DAMAGES" (000---001)
SPECIAL PROVISION "NONDISCRIMINATION" (000---002)
SPECIAL PROVISION "IMPORTANT NOTICE TO CONTRACTORS" (000---010)
SPECIAL PROVISION "CERTIFICATE OF INTERESTED PARTIES (FORM 1295)"
(000---249)
SPECIAL PROVISION TO ITEM 2 (002---004)
SPECIAL PROVISION TO ITEM 6 (006---001)
SPECIAL PROVISIONS TO ITEM 7 (007---001) (007---003) (007---004)

SPECIAL SPECIFICATIONS:

ITEM 6001 PORTABLE CHANGEABLE MESSAGE SIGN
ITEM 6040 MOBILE RETROREFLECTIVITY DATA COLLECTION FOR PAVEMENT
MARKINGS

GENERAL: THE ABOVE-LISTED SPECIFICATION ITEMS ARE THOSE UNDER WHICH
----- PAYMENT IS TO BE MADE. THESE, TOGETHER WITH SUCH OTHER
PERTINENT ITEMS, IF ANY, AS MAY BE REFERRED TO IN THE ABOVE-
LISTED SPECIFICATION ITEMS, AND INCLUDING THE SPECIAL
PROVISIONS LISTED ABOVE, CONSTITUTE THE COMPLETE SPECIFI-
CATIONS FOR THIS PROJECT.

Special Provision to Item 2

Instructions to Bidders



Item 2, "Instructions to Bidders" of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Article 2.3., "Issuing Proposal Forms," is supplemented by the following:

The Department may not issue a proposal form if one or more of the following apply:

- The Contractor has been defaulted in accordance with Article 8.7., "Default of Contract" (a default for performance) on a previous Contract with the Department within the last 3 years.
- The Contractor is not in compliance with Texas Government Code Sections 2155.089 and 2262.055.

Special Provision to Item 7

Legal Relations and Responsibilities



Item 7, "Legal Relations and Responsibilities," of the Standard Specifications is amended with respect to the clauses cited below. No other clauses or requirements of this Item are waived or changed.

Section 7.7.2., "Texas Pollutant Discharge Elimination System (TPDES) Permits and Storm Water Pollution Prevention Plans (SWP3)," is voided and replaced by the following:

7.2. Texas Pollution Discharge Elimination System (TPDES) Permits and Storm Water Pollution Prevention Plans (SWP3).

7.2.1. Projects with less than one acre of soil disturbance including required associated project specific locations (PSL's) per TPDES GP TXR 150000.

No posting or filing will be required for soil disturbances within the right of way. Adhere to the requirements of the SWP3.

7.2.2. Projects with one acre but less than five acres of soil disturbance including required associated PSL's per TPDES GP TXR 150000.

The Department will be considered a primary operator for Operational Control Over Plans and Specifications as defined in TPDES GP TXR 150000 for construction activity in the right of way. The Department will post a small site notice along with other requirements as defined in TPDES GP TXR 150000 as the entity of having operational control over plans and specifications for work shown on the plans in the right of way.

The Contractor will be considered a Primary Operator for Day-to-Day Operational Control as defined in TPDES GP TXR 150000 for construction activity in the right of way. In addition to the Department's actions, the Contractor will post a small site notice along with other requirements as defined in TPDES GP TXR 150000 as the entity of having day-to-day operational control of the work shown on the plans in the right of way. This is in addition to the Contractor being responsible for TPDES GP TXR 150000 requirements for on- right of way and off- right of way PSL's. Adhere to all requirements of the SWP3 as shown on the plans. The Contractor will be responsible for Implement the SWP3 for the project site in accordance with the plans and specifications, TPDES General Permit TXR150000, and as directed.

7.2.3. Projects with 5 acres or more of soil disturbance including required associated PSL's per TPDES GP TXR 150000.

The Department will be considered a primary operator for Operational Control Over Plans and Specifications as defined in TPDES GP TXR 150000 for construction activities in the right of way. The Department will post a large site notice, file a notice of intent (NOI), notice of change (NOC), if applicable, and a notice of termination (NOT) along with other requirements per TPDES GP TXR 150000 as the entity having operational control over plans and specifications for work shown on the plans in the right of way.

The Contractor will be considered a primary operator for Day-to-Day Operational Control as defined in TPDES GP TXR 150000 for construction activities in the right of way. In addition to the Department's actions, the Contractor shall file a NOI, NOC, if applicable, and NOT and post a large site notice along with other requirements as the entity of having day-to-day operational control of the work shown on the plans in the right of way. This is in addition to the Contractor

being responsible for TPDES GP TXR 150000 requirements for on- right of way and off- right of way PSL's. Adhere to all requirements of the SWP3 as shown on the plans.

This page intentionally left blank.