

# NOTIFICATION OF ADDENDUM

## ADDENDUM NO. 1

**DATED 6/30/2005**

<b>Control</b>	<b>1895-01-020</b>
<b>Project</b>	<b>STP 2005(693)SFT</b>
<b>Highway</b>	<b>FM 726</b>
<b>County</b>	<b>UPSHUR</b>

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum by entering the date, which appears at the top of this letter on the Addendum Acknowledgement Form, contained in your bid proposal.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: STP 2005(693)SFT

CONTROL: 1895-01-020

COUNTY: UPSHUR

LETTING: 07/08/2005

REFERENCE NO: 0630

**PROPOSAL ADDENDUMS**

-----

PROPOSAL COVER

BID INSERTS (SH. NO.:

X GENERAL NOTES (SH. NO.: A

SPEC LIST (SH. NO.:

SPECIAL PROVISIONS:

ADDED:

DELETED:

SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

X OTHER: PLAN SHEET CHANGE

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

GENERAL NOTES SHEET A (PLAN SHEET 3): REVISED NOTE TO ITEM 8

**County:** UPSHUR

**Control:** 1895-01-020, etc.

**Highway:** FM 726

General Notes:

**ITEM 7:**

This project is covered by a U.S. Army Corps of Engineers Nationwide 3(i) permit with no coordination. Obtain a copy of permit and conditions at the Engineer's office.

Transmit copies of correspondence between Contractor and resource agencies as listed in Article 7.19 "Preservation of Cultural and Natural Resources and the Environment".

**ITEM 8:**

The Work Start Date and beginning of Working Day Charges for this project will be December 1, 2005.

**ITEM 132:**

Remove deleterious material, organic matter and sediment, etc., from all channels and existing roadway ditches prior to placement of embankment. This work will be subsidiary to this item.

**ITEM 162:**

Finish slopes with a tracked vehicle running vertically up and down the slope.

Repair mulch sod, damaged by causes other than the Contractor's operations, as directed using mulch sod, seeding, and fertilizer. This work will be measured and paid for in accordance with the applicable bid items of the contract.

**ITEMS 420, 430 & 464:**

When unstable foundation materials are encountered, the Engineer will have the option of directing the placement of a foundation seal of Class "A" concrete instead of an undercut.

**ITEM 421:**

TxDOT will furnish and maintain concrete compressive strength testing equipment.

Elevate beam tanks a minimum of one foot above the ground.

**ITEM 427:**

Provide a rub finish for surface area I.

**ITEM 430:**

Remove trees, bushes, and underbrush as directed. This work will be subsidiary to the pertinent bid items.

**County:** UPSHUR

**Control:** 1895-01-020, etc.

**Highway:** FM 726

**ITEM 432:**

Provide expansion joint material with an area equal to the area of contact between the two concrete surfaces. The Engineer will visually inspect the joint material for approval.

**ITEM 467:**

Provide precast safety end treatments with a toewall measuring at least 12 inches. Construct toewalls for cast-in-place safety end treatments as shown in the plans.

**ITEM 502:**

Maintain access to abutting property at all times using approved materials and methods. Work required to maintain ingress and egress within the limits of this project will not be paid for directly, but is subsidiary to the pertinent bid items.

Restrict the movement of equipment across traffic lanes to an absolute minimum.

Use strobe lights or rotating beacons on all motorized equipment, operating on or adjacent to the road surface.

**ITEM 504:**

Provide a Type C structure or an approved equivalent.

Provide a desktop computer, printer, and internet service provider in accordance with DMS-10101 "Computer Equipment".

Erect the chain link fence enclosure to maintain a minimum clearance of 10 feet.

**ITEM 540:**

Furnish round timber posts unless otherwise shown.

**ITEMS 540 & 544:**

Place sufficient dry batch concrete mix in holes to ensure minimum of 2 inch embedment of tubes and posts.

**ITEM 658:**

Use flat type flexible posts.

**County:** UPSHUR

**Control:** 1895-01-020, etc.

**Highway:** FM 726

**BASIS OF ESTIMATE  
1895-01-022**

ITEM	DESCRIPTION	RATE	UNIT	QUANTITY
162	Mulch Sod	As Directed	cy	140
*166	Fertilizer (12-12-12)	800 lb./5,000 sq. yd. of Seed	lb	134.4
168	Vegetative Watering	80 mg/5,000 sq. yd. of Seed	mg.	13.4

\*FOR CONTRACTOR'S INFORMATION ONLY.

**BASIS OF ESTIMATE  
1896-01-010**

ITEM	DESCRIPTION	RATE	UNIT	QUANTITY
162	Mulch Sod	As Directed	cy	140
*166	Fertilizer (12-12-12)	800 lb./5,000 sq. yd. of Seed	lb	134.4
168	Vegetative Watering	80 mg/5,000 sq. yd. of Seed	mg.	13.4

\*FOR CONTRACTOR'S INFORMATION ONLY.

**BASIS OF ESTIMATE  
1896-02-011**

ITEM	DESCRIPTION	RATE	UNIT	QUANTITY
162	Mulch Sod	As Directed	cy	40
*166	Fertilizer (12-12-12)	800 lb./5,000 sq. yd. of Seed	lb	38.4
168	Vegetative Watering	80 mg/5,000 sq. yd. of Seed	mg.	3.8

\*FOR CONTRACTOR'S INFORMATION ONLY.

**BASIS OF ESTIMATE  
1896-03-010**

ITEM	DESCRIPTION	RATE	UNIT	QUANTITY
162	Mulch Sod	As Directed	cy	240
*166	Fertilizer (12-12-12)	800 lb./5,000 sq. yd. of Seed	lb	230.4
168	Vegetative Watering	80 mg/5,000 sq. yd. of Seed	mg.	23.0

\*FOR CONTRACTOR'S INFORMATION ONLY.