

# **NOTIFICATION OF ADDENDUM**

## **ADDENDUM NO. 1**

**DATED 8/06/2012**

<b>Control</b>	<b>6236-89-001</b>
<b>Project</b>	<b>RMC - 623689001</b>
<b>Highway</b>	<b>FM2452</b>
<b>County</b>	<b>NAVARRO</b>

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: RMC - 623689001

CONTROL: 6236-89-001

COUNTY: NAVARRO

LETTING: 08/07/2012

REFERENCE NO: 0806

**PROPOSAL ADDENDUMS**

-----

\_ PROPOSAL COVER

\_ BID INSERTS (SH. NO.:

X GENERAL NOTES (SH. NO.: SHEETS 3A - 3C

\_ SPEC LIST (SH. NO.:

\_ SPECIAL PROVISIONS:

ADDED:

DELETED:

\_ SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

\_ OTHER:

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

REVISIONS TO GENERAL NOTES 3A-3C TO INCLUDE REVISED PLAN SHEETS.

**County:** Navarro

**Control:** 6236-89-001

**Highway:** FM2452

**GENERAL NOTES:**

**General:**

This project consists of performing "Bridge Erosion Repair" on FM2452 at .5 miles north of FM 709 as detailed on the Location Summary and Quantity Sheet in Navarro County Maintenance Section.

Coordinate work through:

George Coppock  
100 SW CR 1000  
Corsicana, Texas 75110  
903-874-5361

Attention is directed to the possible presence of underground utilities owned by the Texas Department of Transportation (irrigation, signal, illumination and surveillance, communication, and control) on the right of way. Call the Department for locates at 214-320-6682 and 214-320-6205 48 hr. in advance of excavation.

Contact the appropriate department of the local city or town a minimum of 48 hr. in advance of excavation.

**Item 2:**

This project includes plan sheets that are not part of the bid proposals.

Order plans from any Reproduction Company listed at:

[http://www.txdot.gov/business/contractors\\_consultants/repro\\_companies.htm](http://www.txdot.gov/business/contractors_consultants/repro_companies.htm)

View or download plans at:

<http://www.txdot.gov/business/plansonline/plansonline.htm>

**Item 3:**

After written notification, work will be continuously prosecuted to completion.

**Item 8:**

Working days will be charged in accordance with Section 8.3.A.4., "Standard Workweek".

**Item 100:**

The limits of preparing right of way will be measured along the centerline of creeks from north to south or east to west to the right of way line.

**Item 459:**

Submit within 14 days the following:

1. Gabion shop drawings for each section of creek embankment on 11x17 sheets.
2. Submit a work schedule and plans for controlling the water.

Failure to submit the gabion drawings, work schedule, and plans for controlling water flow within the 14 calendar days will result in liquidated damages for each day charged over the 14 calendar days.

Time charges will be suspended upon receipt by the Department of all the above submittals.

Allow 14 calendar days for the Department's review and approval.

After notification of approval of the submittals, time charges will resume.

Place gabion and gabion mattress between the bridges to match the gabion under the bridges.

Always place gabion block 3 ft. back from natural stream line.

Provide two 18 in. pipes spaced on 3 ft. centers for Sediment Trap/Pipe Outlet (ST/PO).

When working under water in any location, before placement of gabion, the area should be dried out by an approved method as directed.

**Item 502:**

**County:** Navarro

**Control:** 6236-89-001

**Highway:** FM2452

Provide traffic control in compliance with the latest editions of the “Texas Manual on Uniform Traffic Control Devices” (TMUTCD), the “Traffic Control Standards Sheets” (TCSS), and as directed.

Provide lane closure information to the Engineer by 1 P.M. on the day prior to the proposed closures. Furnish information for Monday closures or closures following a national or state holiday on the last office workday prior to the closures. Do not close lanes if the above reporting requirements have not been met.

Unless otherwise approved, perform work Monday through Saturday during daylight hours. Lane closure time will be Monday through Saturday, 7 A.M. to 5 P.M. Unless otherwise approved, close no more than 1 lane at a time.

Erect barricades and signs in locations not obstructing the traveling public’s view of the normal roadway signing or necessary sight distance.

Equipment and materials will not be left within 30 ft. of the travel lane during non-working hours.

Shadow vehicles equipped with the Department approved Truck Mounted Attenuators (TMA) will be required as shown on the Traffic Control Plan (TCP) Standard (1-series).

When moving unlicensed equipment on or across any pavement or public highways, protect the pavement from all damage using an acceptable method.

This page intentionally left blank.