

# NOTIFICATION OF ADDENDUM

## ADDENDUM NO. 1

**DATED 9/04/2009**

<b>Control</b>	<b>6196-74-001</b>
<b>Project</b>	<b>RMC - 619674001</b>
<b>Highway</b>	<b>US0059</b>
<b>County</b>	<b>VICTORIA</b>

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: RMC - 619674001

CONTROL: 6196-74-001

COUNTY: VICTORIA

LETTING: 09/16/2009

REFERENCE NO: 0904

**PROPOSAL ADDENDUMS**

-----

- X PROPOSAL COVER
- \_ BID INSERTS (SH. NO.: )
- X GENERAL NOTES (SH. NO.: Sheet B )
  
- \_ SPEC LIST (SH. NO.: )
- \_ SPECIAL PROVISIONS: )  
ADDED:
  
- DELETED:
  
- \_ SPECIAL SPECIFICATIONS:  
ADDED:
  
- DELETED:
  
- X OTHER: Plan Sheet 2

DESCRIPTION OF ABOVE CHANGES  
(INCLUDING PLANS SHEET CHANGES)

Proposal Cover: Contract working days changed from 30 to 40  
General Notes: Sheet B, Item 712, option of Class A or Class B.  
Plan Sheet 2 (General Notes, Item 712)

Control	6196-74-001
Project	RMC - 619674001
Highway	US0059
County	VICTORIA

# PROPOSAL TO THE TEXAS TRANSPORTATION COMMISSION

## 2004 SPECIFICATIONS

### WORK CONSISTING OF CLEAN & SEAL CRACKS ON VARIOUS ROADWAYS VICTORIA COUNTY, TEXAS

The quantities in the proposal are approximate. The quantities of work and materials may be increased or decreased as considered necessary to complete the work as planned and contemplated.

This project is to be completed in 40 working days and will be accepted when fully completed and finished to the satisfaction of the Executive Director or designee.

Provide a proposal guaranty in the form of a Cashier's Check, Teller's Check (including an Official Check) or Bank Money Order on a State or National Bank or Savings and Loan Association, or State or Federally chartered Credit Union made payable to the Texas Transportation Commission in the following amount:

FOUR THOUSAND (Dollars) ( \$4,000 )

A bid bond may be used as the required proposal guaranty. The bond form may be detached from the proposal for completion. The proposal may not be disassembled to remove the bond form. The bond must be in accordance with Item 2 of the specifications.

Any addenda issued amending this proposal and/or the plans that have been acknowledged by the bidder, become part of this proposal.

By signing the proposal the bidder certifies:

1. the only persons or parties interested in this proposal are those named and the bidder has not directly or indirectly participated in collusion, entered into an agreement or otherwise taken any action in restraint of free competitive bidding in connection with the above captioned project.
2. in the event of the award of a contract, the organization represented will secure bonds for the full amount of the contract.
3. the signatory represents and warrants that they are an authorized signatory for the organization for which the bid is submitted and they have full and complete authority to submit this bid on behalf of their firm.
4. that the certifications and representations contained in the proposal are true and accurate and the bidder intends the proposal to be taken as a genuine government record.

• **Signed: \*\***

(1) \_\_\_\_\_ (2) \_\_\_\_\_ (3) \_\_\_\_\_

**Print Name:**

(1) \_\_\_\_\_ (2) \_\_\_\_\_ (3) \_\_\_\_\_

**Title:**

(1) \_\_\_\_\_ (2) \_\_\_\_\_ (3) \_\_\_\_\_

**Company:**

(1) \_\_\_\_\_ (2) \_\_\_\_\_ (3) \_\_\_\_\_

- Signatures to comply with Item 2 of the specifications.

\*\*Note: Complete (1) for single venture, through (2) for joint venture and through (3) for triple venture.

\* **When the working days field contains an asterisk (\*) refer to the Special Provisions and General Notes.**

## **NOTICE TO CONTRACTORS**

**FOR THIS PROJECT THE AUDITED FINANCIAL PREQUALIFICATION REQUIREMENT IS WAIVED. ANY CONTRACTOR INTENDING TO BID ON THIS WORK MUST SUBMIT A COMPLETED “BIDDERS QUESTIONNAIRE”, WITH ANY ADDITIONAL INFORMATION REQUESTED IN THAT FORM, AT LEAST TEN DAYS PRIOR TO THE LETTING DATE.**

**CONTRACTORS THAT ARE CURRENTLY PREQUALIFIED BASED ON AN AUDITED FINANCIAL STATEMENT DO NOT NEED TO SUBMIT A “BIDDERS QUESTIONNAIRE” SINCE THE NECESSARY INFORMATION IS CONTAINED IN THE AUDITED PREQUALIFICATION DOCUMENTS.**

**UNIT PRICES MUST BE SUBMITTED IN ACCORDANCE WITH ITEM 2 OF THE STANDARD SPECIFICATIONS OR SPECIAL PROVISION TO ITEM 2 FOR EACH ITEM LISTED IN THIS PROPOSAL.**

**Project Number:** RMC 6196 74 001

**County:** Victoria, Jackson & Calhoun

**Highway:** US 59, etc.

## **GENERAL NOTES:**

### **General:**

Perform cleaning and sealing cracks as defined in Item 712 "CLEANING AND SEALING JOINTS AND CRACKS (ASPHALT CONCRETE)" of the 2004 Texas Department of Transportation Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges and these General Notes.

Provide sufficient staff and equipment to concurrently process each contract at all times in the event of multiple contract awards. Each contract stands on its own and as such, is separate from other contracts.

Notify the specific office in which work will be performed by telephone each morning by 8:15 a.m. that work is scheduled with work location and time arrival or reason for not working that day.

Do not commence work on the road before sunrise and arrange work so that no machinery will be on any traveled roadway after sunset.

Do not store materials or equipment in TxDOT yards. Do not heat sealant materials within TxDOT yards.

### **Item 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING**

Furnish and install all signs, barricades, and other incidentals necessary for proper traffic control. The traffic control plan for this project shall consist of the traffic control plan sheets and the barricade and construction standards listed on the title sheet. All warning signs shall be factory made and in satisfactory condition.

Shadow vehicles with truck mounted attenuators (TMA) will be required.

Provide suitable warning lights mounted high enough to be visible from all directions on all construction equipment, including pilot vehicles, and operate warning lights when the equipment is within the right of way. Equip other equipment such as trucks, trailers, autos, etc., with emergency flashers and use emergency flashers while within the work area.

Pilot cars are required on Yoakum District TCP-One Lane Roadway unless otherwise directed.

Not more than one lane will be blocked at any time at a specific work site, unless otherwise authorized. Limit lane closures to 2 miles in length unless otherwise directed.

**Project Number:** RMC 6196 74 001

**County:** Victoria, Jackson & Calhoun

**Highway:** US 59, etc.

The lane closure length in town sections will be determined by the engineer. Intersection traffic control and signing shall be in accordance with the BC sheets.

Provide sequential arrow boards for each lane closure. Provide a standby unit in good working condition at the jobsite ready for immediate use. Additional devices may be needed to supplement these requirements.

Traffic control is considered subsidiary to the various bid items.

**Item 712. CLEANING AND SEALING JOINTS AND CRACKS (ASPHALT CONCRETE)**

Furnish and apply **Class A or Class B** rubber asphalt crack sealer in accordance with Item 300.2.H.

Furnish equipment to clean cracks capable of delivering a minimum of 125 PSI of air pressure with an orifice at least 0.5 inch in size.

Furnish and apply fine aggregate in accordance with Item 340.2.A.3. as directed. All aggregate used and work involved shall be considered subsidiary.

Use crew(s) experienced in the work of crack sealing operations and in the necessary traffic control.

Working days are based on placing a minimum of 10 lane miles of sealing compound per day.

Keep all roadways clean of debris and open to traffic at the end of each workday.

Equip vehicles with highly visible, omni directional strobe lights.

**NOTE: Crack sealing limits and quantities are approximate and for the contractor's information only. Highways and quantities may be added or deleted to this contract. The highways will be prioritized in the order of need as submitted by the Engineer prior to start of work.**

**Project Number:** RMC 6196 74 001

**County:** Victoria, Jackson & Calhoun

**Highway:** US 59, etc.

**Estimated work limits for Victoria County. Ned Pyatt at 361/573-9251**

<b>HWY</b>	<b>Limits</b>	<b>Location</b>	<b>Quantity</b>
FM 236	BU 59 to DeWitt C/L	Lanes & Shoulders	63.0 LM
US 77	Coleto Creek to Refugio C/L	Shoulders	25.0 LM
US 59	SB Frontage Rd @ FM 444	2 Lanes	1.5 LM
US 59	NB Frontage Rd @ FM 444	2 Lanes	2.1 LM
US 59	NB Frontage Rd @ SL 463	2 lanes	2.2 LM
Us 59	NB Frontage Rd (Anthony to Juan Linn)	2 Lanes	1.1 LM
US 59	NB Frontage Rd (SH 185 to US 87)	2 Lanes	1.2 LM
SL 463	Salem Rd to end state maintenance at US 59	Lanes/Shoulders/Ramps	2.1 LM
BU 59	SL 463 to Sam Houston	Lanes & Shoulders	12.0 LM
BU 59	BU 77 (Navarro) to Guadalupe RB	4 Lanes	4.0 LM
SH 185	US 59 to BU 59	5 Lanes	18.0 LM
BU 77	FM 1315 to SL 463	5 Lanes	8.0 LM
FM 1090	Railroad crossing at US 87 to Calhoun C/L	2 Lanes	12.5 LM
		<b>Total</b>	<b>152.7 LM</b>

**Estimated work limits for Jackson County. Bobby Mozisek at 361/782-2322**

<b>HWY</b>	<b>Limits</b>	<b>Location</b>	<b>Quantity</b>
FM 1593	Lolita (Walnut St) to Calhoun C/L	Shoulders	20.0 LM
FM 234	US 59 frontage road to CR 319	Lanes & Shoulders	17.2 LM
FM 234	CR 319 to Vanderbilt	Shoulders	11.6 LM
FM 234	US 59 (at Sklar OP) to CR 107	Lanes	1.1 LM
FM 234	US 59 (at El Toro) to RM 540	Lanes	4.0 LM
FM 616	Carancahua St (Vanderbilt) to Lavaca Relief Bridge	Shoulders	2.0 LM
FM 530	US 59 to CR 274 (Spruce Farms) (-6900' base repair)	Lanes	15.6 LM
US 59	End of LP 522 on ramp to Wharton C/L	NB Lanes	14.1 LM
US 59 FR	NB/SB, all frontage roads at FM 234	Lanes & Shoulders	4.2 LM
US 59 FR	NB, FM 822 to change of pavement	Lanes & Shoulders	1.0 LM
SH 35	Carancahua Bridge to Matagorda C/L	Lanes	13.8 LM
LP 521	FM 530 overpass to CR 300 (including interchanges)	Lanes & Shoulders	34.0 LM
SH 111	Houston St (RR Xing) to end of Multi-lane (Walmart)	Lanes & Shoulders	4.0 LM
SH 111	Jct SH 172 to Matagorda C/L	Shoulders	22.0 LM
SH 111	Hot mix at Matagorda C/L	Lanes	0.5 LM
		<b>Total</b>	<b>165.1 LM</b>

**Estimated work limits for Calhoun County. Wesley Abraham at 361/552-6131**

<b>HWY</b>	<b>Limits</b>	<b>Location</b>	<b>Quantity</b>
SH 35	FM 1090 to Lavaca Bay Bridge	Lanes & Shoulders	12.0 LM
SH 238	SH 35 to US 87	Lanes	3.5 LM
SH 238	FM 1090 (Alcoa Dr) to Fishers Curve	SB Lanes, outside north & shoulders	5.3 LM
SH 35	Jackson C/L to SH 35	Shoulders	3.8 LM
FM 2143	SH 35 to Keller's Creek	Lanes	6.0 LM
FM 1679	US 87 to SH 35	Lanes	9.0 LM
FM 1090	Victoria C/L to FM 3084	Lanes	5.7 LM
FM 1593	Jackson C/L south to SH 35	Shoulders	3.8 LM
SH 185	SH 238 to FM 2235	Shoulders	6.5 LM
FM 1090	Victoria C/L to FM 3084	2 Lanes	5.8 LM
		<b>Total</b>	<b>61.4 LM</b>

This page intentionally left blank.