

NOTIFICATION OF ADDENDUM

ADDENDUM NO. 2

DATED 4/12/2013

Control	6256-01-001
Project	RMC - 625601001
Highway	US0077
County	FAYETTE

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: RMC - 625601001

CONTROL: 6256-01-001

COUNTY: FAYETTE

LETTING: 04/17/2013

REFERENCE NO: 0412

PROPOSAL ADDENDUMS

_ PROPOSAL COVER

_ BID INSERTS (SH. NO.:

X GENERAL NOTES (SH. NO.: A

_ SPEC LIST (SH. NO.:

_ SPECIAL PROVISIONS:

ADDED:

DELETED:

_ SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

_ OTHER:

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

Item 502: Barricades, Signs, and Traffic Handling

First paragraph deleted and replaced with:

Project limit traffic control devices will not be required for this project.

Plan Sheet 2 under Item 502: Barricades, Signs & Traffic Handling

Paragraph 1 is deleted and replaced with:

Project limit traffic control devices will not be required for this project.

Project Number: RMC 6256 01 001

County: Fayette, etc.

Highway: US 77, Etc.

GENERAL NOTES:

Do not work on the roadway before sunrise or after sunset.

Leave all traffic lanes open to traffic at night, weekends and holidays unless otherwise approved.

The storm water pollution prevention plan (SW3P) for this project will consist of utilizing existing vegetation.

Remove and dispose of existing raised pavement markers as directed. All work involved in the removal and disposal of these markers will not be paid for directly but shall be considered subsidiary to the various bid items involved.

ITEM 8: PROSECUTION AND PROGRESS

Provide progress schedules meeting the requirements of Section 8.2.B, "Construction Contracts."

ITEM 502: BARRICADES, SIGNS, AND TRAFFIC HANDLING

Project limit traffic control devices will not be required for this project.

Limit the lane closure lengths for texturing operations to one (1) mile for one-lane, two way traffic control.

Use TCP 2-2b for one-lane, two-way traffic control.

When using TCP 2-2b, a pilot car is required to lead traffic through the work space with or without channelizing devices on the center line unless otherwise approved.

When using TCP 2-2b, channelizing devices may be omitted during centerline texturing operations unless otherwise directed. Flaggers will be required at public intersections when channelizing devices are omitted.

When using TCP 2-2b, arrow boards shall be used to enhance the flagger stations except for operations of less than one hour. The arrow boards shall display the caution mode.

When using TCP 2-2b, the temporary 24" stop line and the CW16-2P plaques may be omitted.

When using TCP 2-2b, an additional "Road Work Ahead" and "Be Prepared To Stop" signs will be required on each end of the lane closure.

Provide trail and lead vehicles when using TCP(3-1) or TCP(3-3).

Project Number: RMC 6256 01 001

County: Fayette, etc.

Highway: US 77, Etc.

Provide suitable warning lights mounted high enough to be visible from all directions on all construction equipment, including pilot vehicles, and operate warning lights when the equipment is within the right of way. Equip other equipment such as trucks, trailers, autos, etc., with emergency flashers and use emergency flashers while within the work area.

ITEM 5369: CENTERLINE TEXTURING

The limits for centerline texturing are based on the locations of the 70 mph speed zone signs. Begin and end the texturing/ rumble strip at the 70 mph signs outside each community. The only exception is on US 77 due to an ongoing construction project within the 70 mph zone.

Utilize TCP (2-2)-12 for texturing operations.

Provide a broom to clean the roadway after the texturing operation and prior to opening the lanes to traffic.

ITEM 8251: REFLECTORIZED PAVEMENT MARKINGS

Multiple move-ins will be required for the striping crew. There are four roadway locations listed on the Location Summary. Place permanent stripe no later than one day after completing the texturing for each roadway location.

A VHS or DVD video of the retroreflectometer data will not be required.

Project Number: RMC 6256 01 001

County: Fayette, etc.

Highway: US 77, Etc.

B A S I S O F E S T I M A T E

ITEM	DESCRIPTION	RATE	BASIS	QUANTITY	UNIT
------	-------------	------	-------	----------	------

HIGHWAY: US 87
CONTROL: 0143-06 AND 0143-07
COUNTY : GONZALES
LIMITS : SOUTH OF NIXON TO NORTH OF SMILEY
AND
SOUTH OF SMILEY TO DEWITT COUNTY LINE
LENGTH : 6.0 MILES AND 9.5 MILES

672	REFL PAV MRKR TY II-A-A				
	PASS	1 EA/80 LF	20407 LF	255	EA
	SINGLE NO PASS	1 EA/40 LF	40862 LF	1022	EA
	DOUBLE NO PASS	1 EA/40 LF	20091 LF	502	EA
				=====	
			TOTAL	1779	EA

5369	CENTERLINE TEXTURING				
	81360 LF / 100 LF PER STA			814	STA

8251	RE PM W/ RET REQ TY I(Y)(4")(BRK)(100 MIL)				
	PASS	10 LF/40 LF	20407 LF	5100	LF
	SINGLE NO PASS	10 LF/40 LF	40862 LF	10220	LF
				=====	
			TOTAL	15320	LF

8251	RE PM W/ RET REQ TY I(Y)(4")(SLD)(100 MIL)				
	SINGLE NO PASS		40862 LF	40862	LF
	DOUBLE NO PASS		20091 LF X 2	40182	LF
				=====	
			TOTAL	81044	LF

Project Number: RMC 6256 01 001

County: Fayette, etc.

Highway: US 77, Etc.

B A S I S O F E S T I M A T E

ITEM	DESCRIPTION	RATE	BASIS	QUANTITY	UNIT
------	-------------	------	-------	----------	------

HIGHWAY: US 87
CONTROL: 0143-08
COUNTY : DEWITT
LIMITS : GONZALES COUNTY LINE TO NORTH OF WESTHOFF
AND
SOUTH OF WESTHOFF TO US 183
LENGTH : 0.7 MILE AND 12.5 MILES

672	REFL PAV MRKR TY II-A-A				
	PASS	1 EA/80 LF	24029 LF	301	EA
	SINGLE NO PASS	1 EA/40 LF	27530 LF	689	EA
	DOUBLE NO PASS	1 EA/40 LF	16865 LF	422	EA
				=====	
			TOTAL	1412	EA

5369	CENTERLINE TEXTURING				
	68424 LF / 100 LF PER STA			684	STA

8251	RE PM W/ RET REQ TY I(Y)(4")(BRK)(100 MIL)				
	PASS	10 LF/40 LF	24049 LF	6010	LF
	SINGLE NO PASS	10 LF/40 LF	27530 LF	6890	LF
				=====	
			TOTAL	12900	LF

8251	RE PM W/ RET REQ TY I(Y)(4")(SLD)(100 MIL)				
	SINGLE NO PASS		27530 LF	27530	LF
	DOUBLE NO PASS		16865 LF X 2	33730	LF
				=====	
			TOTAL	61260	LF

Project Number: RMC 6256 01 001

County: Fayette, etc.

Highway: US 77, Etc.

B A S I S O F E S T I M A T E

ITEM	DESCRIPTION	RATE	BASIS	QUANTITY	UNIT
------	-------------	------	-------	----------	------

HIGHWAY: SH 111
CONTROL: 0325-01
COUNTY : DEWITT
LIMITS : US 183 TO WEST OF PETERSVILLE
AND
EAST OF PETERSVILLE TO WEST OF YOAKUM
LENGTH : 4.9 MILES AND 2.5 MILES

672	REFL PAV MRKR TY II-A-A				
	PASS	1 EA/80 LF	5004 LF	63	EA
	SINGLE NO PASS	1 EA/40 LF	21095 LF	528	EA
	DOUBLE NO PASS	1 EA/40 LF	12227 LF	306	EA
				=====	
			TOTAL	897	EA

5369	CENTERLINE TEXTURING				
	38326 LF / 100 LF PER STA			384	STA

8251	RE PM W/ RET REQ TY I(Y)(4")(BRK)(100 MIL)				
	PASS	10 LF/40 LF	5004 LF	1250	LF
	SINGLE NO PASS	10 LF/40 LF	21095 LF	5280	LF
				=====	
			TOTAL	6530	EA

8251	RE PM W/ RET REQ TY I(Y)(4")(SLD)(100 MIL)				
	SINGLE NO PASS		21095 LF	21095	LF
	DOUBLE NO PASS		12227 LF X 2	24454	LF
				=====	
			TOTAL	45549	LF

Project Number: RMC 6256 01 001

County: Fayette, etc.

Highway: US 77, Etc.

B A S I S O F E S T I M A T E

ITEM	DESCRIPTION	RATE	BASIS	QUANTITY	UNIT
------	-------------	------	-------	----------	------

HIGHWAY: US 77
CONTROL: 0268-01
COUNTY : FAYETTE
LIMITS : SOUTH OF LA GRANGE TO 0.17 MI NORTH OF FM 2436
AND
0.35 MI SOUTH OF FM 956 TO NORTH OF SCHULENBURG
LENGTH : 3.4 MILES AND 3.1 MILES

672	REFL PAV MRKR TY II-A-A				
	PASS	1 EA/80 LF	1415 LF	18	EA
	SINGLE NO PASS	1 EA/40 LF	9240 LF	231	EA
	DOUBLE NO PASS	1 EA/40 LF	24075 LF	602	EA
				=====	
			TOTAL	851	EA

5369	CENTERLINE TEXTURING				
	34730 LF / 100 LF PER STA			348	STA

8251	RE PM W/ RET REQ TY I(Y)(4")(BRK)(100 MIL)				
	PASS	10 LF/40 LF	1415 LF	360	LF
	SINGLE NO PASS	10 LF/40 LF	9240 LF	2340	LF
				=====	
			TOTAL	2700	LF

8251	RE PM W/ RET REQ TY I(Y)(4")(SLD)(100 MIL)				
	SINGLE NO PASS		9240 LF	9240	LF
	DOUBLE NO PASS		24075 LF X 2	48150	LF
				=====	
			TOTAL	57390	LF

Project Number: RMC 6256 01 001

County: Fayette, etc.

Highway: US 77, Etc.

B A S I S O F E S T I M A T E

ITEM	DESCRIPTION	RATE	BASIS	QUANTITY	UNIT
------	-------------	------	-------	----------	------

HIGHWAY: SH 185
CONTROL: 0432-02
COUNTY : VICTORIA
LIMITS : RM 0596+1.4016 to Calhoun County Line

LENGTH : 1.4 MILES

672	REFL PAV MRKR TY II-A-A				
	PASS	1 EA/80 LF	6488 LF	81	EA
	SINGLE NO PASS	1 EA/40 LF	1228 LF	31	EA
	DOUBLE NO PASS	1 EA/40 LF	262 LF	7	EA
				=====	
			TOTAL	119	EA
5369	CENTERLINE TEXTURING				
	7978 LF / 100 LF PER STA			80	STA
8251	RE PM W/ RET REQ TY I(Y)(4")(BRK)(100 MIL)				
	PASS	10 LF/40 LF	6488 LF	1622	LF
	SINGLE NO PASS	10 LF/40 LF	1228 LF	307	LF
				=====	
			TOTAL	1929	LF
8251	RE PM W/ RET REQ TY I(Y)(4")(SLD)(100 MIL)				
	SINGLE NO PASS		1228 LF	1228	LF
	DOUBLE NO PASS		262 LF X 2	524	LF
				=====	
			TOTAL	1752	LF

Project Number: RMC 6256 01 001

County: Fayette, etc.

Highway: US 77, Etc.

B A S I S O F E S T I M A T E

ITEM | DESCRIPTION | RATE | BASIS | QUANTITY | UNIT

HIGHWAY: SH 185
CONTROL: 0432-01
COUNTY : CALHOUN
LIMITS : SH 35 to Victoria County Line

LENGTH : 8.2 MILES

672	REFL PAV MRKR TY II-A-A				
	PASS	1 EA/80 LF	33833 LF	423	EA
	SINGLE NO PASS	1 EA/40 LF	8284 LF	207	EA
	DOUBLE NO PASS	1 EA/40 LF	1147 LF	29	EA
				=====	
			TOTAL	659	EA
5369	CENTERLINE TEXTURING				
	43264 LF / 100 LF PER STA			433	STA
8251	RE PM W/ RET REQ TY I(Y)(4")(BRK)(100 MIL)				
	PASS	10 LF/40 LF	33833 LF	8458	LF
	SINGLE NO PASS	10 LF/40 LF	8284 LF	2071	LF
				=====	
			TOTAL	10529	LF
8251	RE PM W/ RET REQ TY I(Y)(4")(SLD)(100 MIL)				
	SINGLE NO PASS		8284 LF	8284	LF
	DOUBLE NO PASS		1147 LF X 2	2294	LF
				=====	
			TOTAL	10578	LF