

NOTIFICATION OF ADDENDUM

ADDENDUM NO. 1

DATED 3/26/2012

Control	6240-95-001
Project	RMC - 624095001
Highway	SH0072
County	LIVE OAK

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: RMC - 624095001

CONTROL: 6240-95-001

COUNTY: LIVE OAK

LETTING: 04/04/2012

REFERENCE NO: 0326

PROPOSAL ADDENDUMS

- X PROPOSAL COVER
- X BID INSERTS (SH. NO.: SHEET 1-1)
- X GENERAL NOTES (SH. NO.: SHEETS A & C)

- _ SPEC LIST (SH. NO.:)
- _ SPECIAL PROVISIONS:)
- ADDED:

DELETED:

- _ SPECIAL SPECIFICATIONS:
- ADDED:

DELETED:

- _ OTHER:

DESCRIPTION OF ABOVE CHANGES
(INCLUDING PLANS SHEET CHANGES)

NUMBER OF DAYS CHANGED FROM 18 TO 24.

BID ITEM 502-2001-033 CHANGED FROM 1 MONTH TO 2 MONTHS.

REVISIONS TO GENERAL NOTES SHEETS A & C.

REVISIONS TO PLAN SHEETS 3, 4 & 7.

Control	6240-95-001
Project	RMC - 624095001
Highway	SH0072
County	LIVE OAK

PROPOSAL TO THE TEXAS TRANSPORTATION COMMISSION

2004 SPECIFICATIONS

WORK CONSISTING OF FLEXIBLE PAVEMENT REPAIR LIVE OAK COUNTY, TEXAS

The quantities in the proposal are approximate. The quantities of work and materials may be increased or decreased as considered necessary to complete the work as planned and contemplated.

This project is to be completed in 24 working days and will be accepted when fully completed and finished to the satisfaction of the Executive Director or designee.

Provide a proposal guaranty in the form of a Cashier's Check, Teller's Check (including an Official Check) or Bank Money Order on a State or National Bank or Savings and Loan Association, or State or Federally chartered Credit Union made payable to the Texas Transportation Commission in the following amount:

FIFTEEN THOUSAND (Dollars) (\$15,000)

A bid bond may be used as the required proposal guaranty. The bond form may be detached from the proposal for completion. The proposal may not be disassembled to remove the bond form. The bond must be in accordance with Item 2 of the specifications.

Any addenda issued amending this proposal and/or the plans that have been acknowledged by the bidder, become part of this proposal.

By signing the proposal the bidder certifies:

1. the only persons or parties interested in this proposal are those named and the bidder has not directly or indirectly participated in collusion, entered into an agreement or otherwise taken any action in restraint of free competitive bidding in connection with the above captioned project.
2. in the event of the award of a contract, the organization represented will secure bonds for the full amount of the contract.
3. the signatory represents and warrants that they are an authorized signatory for the organization for which the bid is submitted and they have full and complete authority to submit this bid on behalf of their firm.
4. that the certifications and representations contained in the proposal are true and accurate and the bidder intends the proposal to be taken as a genuine government record.

• **Signed: ****

(1) _____ (2) _____ (3) _____

Print Name:

(1) _____ (2) _____ (3) _____

Title:

(1) _____ (2) _____ (3) _____

Company:

(1) _____ (2) _____ (3) _____

- Signatures to comply with Item 2 of the specifications.

**Note: Complete (1) for single venture, through (2) for joint venture and through (3) for triple venture.

* **When the working days field contains an asterisk (*) refer to the Special Provisions and General Notes.**

NOTICE TO CONTRACTORS

ANY CONTRACTORS INTENDING TO BID ON ANY WORK TO BE AWARDED BY THIS DEPARTMENT MUST SUBMIT A SATISFACTORY “AUDITED FINANCIAL STATEMENT” AND “EXPERIENCE QUESTIONNAIRE” AT LEAST TEN DAYS PRIOR TO THE LETTING DATE.

UNIT PRICES MUST BE SUBMITTED IN ACCORDANCE WITH ITEM 2 OF THE STANDARD SPECIFICATIONS OR SPECIAL PROVISION TO ITEM 2 FOR EACH ITEM LISTED IN THIS PROPOSAL.

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	351	2013		FLEXIBLE PAVEMENT STRUCTURE REPAIR(4") DOLLARS CENTS and	SY	34,423.000	1
	500	2001	005	MOBILIZATION DOLLARS CENTS and	LS	1.000	2
	502	2001	033	BARRICADES, SIGNS AND TRAFFIC HAN- DLING DOLLARS CENTS and	MO	2.000	3
	662	2115		WK ZN PAV MRK SHT TERM (TAB) TY Y-2 DOLLARS CENTS and	EA	1,524.000	4
	672	2015	034	REFL PAV MRKR TY II-A-A DOLLARS CENTS and	EA	509.000	5
	6834	2001		PORTABLE CHANGEABLE MESSAGE SIGN DOLLARS CENTS and	DAY	14.000	6
	8251	2005	005	RE PM W/RET REQ TY I(W)4"(SLD)(090MIL) DOLLARS CENTS and	LF	53,146.000	7
	8251	2014	005	RE PM W/RET REQ TY I(Y)4"(BRK)(090MIL) DOLLARS CENTS and	LF	4,088.000	8
	8251	2017	005	RE PM W/RET REQ TY I(Y)4"(SLD)(090MIL) DOLLARS CENTS and	LF	24,346.000	9

Project Number: RMC 624095001

County: Live Oak

Highway: SH 72

Control: 6240-95-001

GENERAL NOTES:

General Notes

Find, for your information and convenience, tools such as forms, software, materials, and various other information provided by the Department at <http://www.dot.state.tx.us/business/>. Please note that these tools are updated periodically and your attention is directed to the latest edition.

Work on this contract shall commence upon the issuance of a work order by the Director of Maintenance and shall continue for 24 working days.

In the event of a called evacuation, emergencies, impending adverse weather or as directed, do not perform any work without written authorization. The District reserves the right to suspend all work in support of evacuations or emergencies occurring from other parts of the state. Any work performed, other than work directed by the Department, is unauthorized work in accordance with Item 5.

Sweep, clean and remove any construction waste, surplus materials or debris from the roadway and right of way at the end of each day unless otherwise approved. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

The asphalt season for the placement of asphalt surface courses is March 15 to November 15 unless otherwise approved.

Cut existing pavement using a saw or other approved method to ensure a neat transverse and/or longitudinal line to assure a smooth tie-in with new pavement. Cut to a minimum depth of the final lift thickness. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Promptly pick up and properly dispose of paper and other materials used for pavement joints.

All pavement markings shall be in accordance with the latest edition of Texas MUTCD

Project Number: RMC 624095001

County: Live Oak

Highway: SH 72

Control: 6240-95-001

ITEM 2

It is recommended that prospective bidders examine the specified work locations with the Engineer to view the nature of the work, the need for close coordination with the various utilities, traffic control considerations, and other factors influencing the prosecution of the work.

ITEM 5

Field verify all dimensions and notify Engineer prior to initiating any work.

Verify the locations of utilities, underground or overhead, shown within the limits of the right-of-way. Adhere to OSHA Standards when working within the vicinity of overhead power lines. Coordinate with the utility companies and notify the Engineer of any possible conflicts. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Notify the Engineer immediately of utility conflicts in accordance with Item 5.5.B. Refer to Item 4.3 for consideration of differing site conditions.

The responsibility for the construction surveying on this contract will be in accordance with Item 5.6.C, "Method C".

Establish and mark the location of existing standard pavement markings including but not limited to edge lines, transitions, passing and no passing zones, gore areas, etc.

Project Number: RMC 624095001

County: Live Oak

Highway: SH 72

Control: 6240-95-001

ITEM 7

The work performed for Item 7.7, “Public Safety and Convenience” will not be measured or paid for directly, but will be subsidiary to pertinent Items.

When working at street, farm-to-market, state highway, and county road intersections, schedule work to minimize intersection closures. During nonworking hours, all public road intersections will be open to the traveling public.

The total disturbed area for this project is 0 acres. The disturbed area in this project, all project locations in the Contract, and Contractor project specific locations (PSLs), within 1 mile of the project limits, for the Contract will further establish the authorization requirements for storm water discharges. The Department will obtain an authorization to discharge storm water from the Texas Commission on Environmental Quality (TCEQ) for the construction activities shown on the plans. The Contractor is to obtain any required authorization from the TCEQ for any Contractor PSLs for construction support activities on or off ROW. When the total area disturbed for all projects in the Contract and PSLs within 1 mile of the project limits exceeds 5 acres, provide a copy of the Contractor NOI for PSLs on the ROW to the Engineer.

Comply with the Texas Aggregate Quarry and Pit Safety Act for waste areas or material source areas resulting from this project.

ITEM 8

Prepare the progress schedule using the Critical Path Method (CPM). Submit (2) two 11” x 17” hard copies and an electronic file of the original or updated progress schedule. Submit the original progress schedule seven (7) days before the Preconstruction Conference. (For Item 8.2)

Submit an updated progress schedule as directed to show proposed major changes, changes affecting compliance with the contract requirements, or changes affecting the critical path/controlling item of work. (For Item 8.2)

Working days will be computed and charge in accordance with Article 8.3.A.4, “Standard Workweek”.

Work above traffic is not allowed.

Lane closures are not permitted Monday through Friday before 8 AM unless approved.

Nighttime work is not allowable.

Notify the Engineer at least 48 hours in advance of weekend work.

Project Number: RMC 624095001

County: Live Oak

Highway: SH 72

Control: 6240-95-001

ITEM 9

Submit the approved forms to request compensation for material-on-hand (MOH) at least three (3) working days prior to the end of the month. Include any requests from subcontractors, suppliers, or fabricators.

ITEM 340

Provide aggregates with a minimum surface aggregate classification (SAC) of “B” unless otherwise shown. SAC requirements apply to aggregates used on all final roadway surfaces, including shoulders.

Use crushed gravel screenings with or in lieu of stone screenings.

Use a cut-off chute when placing hot-mix asphalt on narrow width locations unless approved.

The laboratory-molded density for this project will be 97% in accordance with test method TEX-207-F for the Type C HMA.

All Type “C” hot mix shall have a PG 76-22 binder. Grade “dumping” will not be allowed.

Hot mix will be subjected to standard Hamberg testing.

ITEM 351

Use of motor grader will not be permitted unless approved.

The daily work area will be limited in length to that which can be brought up to original grade in the same workday. Open cuts in the roadway will not be allowed after working hours

ITEM 354

Reclaimable asphalt material (R.A.P.) may be retained only if incorporated into the project. Incorporate the R.A.P. into the pavement structure, into the backfill for pavement edges, into temporary structures, or as approved. Any excess R.A.P. will be stockpiled on the East right of way of FM 2049, 1800' North of the intersection of SH 72 and FM 2049.

Project Number: RMC 624095001

County: Live Oak

Highway: SH 72

Control: 6240-95-001

ITEM 500

"Materials on Hand" payments are not considered when determining partial payments.

ITEM 502

Furnish additional barricades, signs, and traffic handling as directed. The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

Traffic control for daytime lane closures shall be in accordance with TCP (2-2)12.

When advanced warning flashing arrow panels are specified, furnish one (1) standby unit in good condition at the job site for immediate use.

The Contractor's Responsible Person (CRP) or his representative(s) shall be located within one hour of traveling time to the project site. The Contractor shall notify the Engineer in writing of the name, physical address, and telephone number of this employee or these employees. The Engineer shall furnish this information to local law enforcement officials.

Maintain traffic control devices by taking corrective action as soon as possible. Complete corrective action within 48 hours of written notification regardless of the day of the week involved unless otherwise directed.

Provide a positive means of communication between flaggers unless otherwise approved.

Attach stop/slow paddle to a staff with a minimum length of 6 feet to the bottom of the sign.

The use of a pilot vehicle in conjunction with flaggers will be permitted. If used, provide positive and unrestricted communication between the driver of the pilot vehicle and the flaggers.

The work performed will not be measured or paid for directly, but will be subsidiary to pertinent Items.

ITEM 506

Designate in writing a Contractor Responsible Person (CRP) for implementing, maintaining, and reviewing environmental requirements.

Project Number: RMC 624095001

County: Live Oak

Highway: SH 72

Control: 6240-95-001

ITEM 662

Use temporary flexible-reflective roadway marker tabs at the beginning and end of no passing zones as shown on the TCP (7-1)-98 for seal coats and WZ(STPM)-03 for hot mix overlays.

ITEM 6834

Furnish the portable changeable message signs displaying the correct message at least seven (7) days prior to beginning work or as directed.

The Contractor's Responsible Person (CRP) will maintain full control of messages at all times.

The Engineer will provide the sign message text to use at each sign.

Provide cellular phone connection.

A minimum of 2 PCMS will be required. However, additional units may be necessary depending on the work in progress.

Standby time will not be measured or paid for directly, but will be subsidiary to pertinent Items.

ITEM 8251

Establish and mark the location of existing standard pavement markings including but not limited to edge lines, transitions, passing and no passing zones, gore areas, etc.

Place pavement markings no later than 14 calendar days after the placement of the surface. When inclement weather prohibits placement of the markings, the 14-day period may be extended until weather permits proper application.

Project Number: RMC 624095001

County: Live Oak

Highway: SH 72

Control: 6240-95-001

*****SPECIFICATION DATA*****

*ITEM 341 -D-GR HMA (QCQA) TY C SAC-B PG76-22-----440 LBS/SY/IN

*TACK COAT (ALL TYPES)-----0.03 - 0.05 GAL/SY

*FOR THE CONTRACTOR'S INFORMATION ONLY, NON-PAY.
