

NOTIFICATION OF ADDENDUM

ADDENDUM NO. 1

DATED 11/19/2013

Control	6265-02-001
Project	RMC - 626502001
Highway	SH0019
County	TRINITY

Ladies/Gentlemen:

Attached please find an addendum on the above captioned project. Included in the attachment is an addendum notification which details the changes and the respective proposal pages which were added and/or changed.

Except for new bid insert pages, it is unnecessary to return any of the pages attached.

Bid insert pages must be returned with the bid proposal submitted to the Department, unless your firm is submitting a bid using a computer print out. The computer print out must be changed to reflect the new bid item information.

Contractors and material suppliers, etc. who have previously been furnished informational proposals are not being furnished a copy of the addendum. If you have a subcontractor on the above project, please advise them of this addendum. Acknowledgment of this addendum is not requested if your company has been issued a proposal stamped "This Proposal Issued for Informational Purposes."

You are required to acknowledge receipt of this addendum on the Addendum Acknowledgement form contained in your bid proposal by placing a mark in the box next to the respective addendum.

Failure to Acknowledge receipt of this addendum in your bid proposal will result in your bid not being read.

SUBJECT: PLANS AND PROPOSAL ADDENDUMS

PROJECT: RMC - 626502001

CONTROL: 6265-02-001

COUNTY: TRINITY

LETTING: 12/05/2013

REFERENCE NO: 1119

PROPOSAL ADDENDUMS

_ PROPOSAL COVER

_ BID INSERTS (SH. NO.:

X GENERAL NOTES (SH. NO.: GENERAL NOTES (SH. NO.: 1-3 OF 3)

X SPEC LIST (SH. NO.: 1 OF 2

X SPECIAL PROVISIONS:

ADDED: 000--2839

DELETED: 000--2711

_ SPECIAL SPECIFICATIONS:

ADDED:

DELETED:

X OTHER: GENERAL NOTES ADDED TO PROPOSAL

SPECIAL PROVISION UPDATED

DESCRIPTION OF ABOVE CHANGES

(INCLUDING PLANS SHEET CHANGES)

County: Trinity

Control: 6265-02-001

Highway: SH 19, ETC.

GENERAL NOTES:

Project Description: This project consists of performing tree trimming and brush removal on various roads in Trinity County. This project also consists of removing trees as directed.

TxDOT Project Supervisor – The project will be managed by Danny Luna, Trinity County Maintenance Supervisor, at (936) 642-1132.

Department approved safety vests shall be worn by all workers on TxDOT right-of-way. Only workers actively engaged in the operation of a chainsaw, chipper, or similar device shall be exempt from wearing safety vests. Non-compliance with any of these requirements shall be grounds for suspension of work.

Remove dirt, silt, rocks, debris and other foreign matter that accumulates in structures due to the Contractor's operations as directed. Keep stream channels open at all times. This work will not be paid for directly, but will be subsidiary to pertinent Items.

Contract Time – The number of working days for this project shall be 160 days or until contract funds are expended.

Item 502: Barricades, Signs and Traffic Handling

Traffic Control Plan (TCP):

Furnish and maintain all warning signs, flaggers, channelizing devices, etc. required for traffic control on this contract in accordance with Item 502.1 & 502.2. This work will not be paid for directly but will be considered subsidiary to the various bid items.

For protection of the traveling public, direct traffic through the work area using signs, flaggers and other devices. Required signs are shown in the plans on the Barricade And Construction Standards and Traffic Control Plan Sheets. The latest edition of the "Texas Manual On Uniform Traffic Control Devices" shall also be used as a guide for handling traffic on this project.

Restrict construction work to single lane widths with only minor disruptions in traffic flow. Lane closures shall conform to the traffic control plan for lane closures as shown in the plans. No overnight closures will be permitted.

Provide temporary Rumble Strips as shown on WZ(RS)-12 when lane closures are necessary.

Provide a flashing arrow panel and a truck-mounted attenuator to supplement required signs and devices for each lane closure.

Provide adequate flaggers to protect the traveling public when working on or near a roadway carrying traffic. All flaggers shall wear hardhats and reflective vests.

County: Trinity**Control:** 6265-02-001**Highway:** SH 19, ETC.

Install “Be Prepared to Stop” (CW20-7B) and “Flagger Ahead” (CW22-7D) signs when flaggers are present. Position the signs where good visibility and traffic control can be maintained.

Provide one high-intensity yellow, rotating dome-lite on all equipment such as distributors, spreader boxes, lay-down machines, rollers, backhoes, road graders, loaders, etc. Mount lights high enough to be visible from all directions and operating when the equipment is within 30 ft. of the travel way. On all other equipment such as trucks, trailers, automobiles, etc., use emergency flashers while within the work zone.

Item 752: Tree and Brush Removal

Notify the engineer or his representative at least 24 hours prior to beginning work.

All work, except emergency work, is to be completed between October 2nd and February 14th to insure compliance with the Migratory Bird Treaty Act (MBTA). Emergency work is any work required to eliminate a potential hazard(s) to the traveling public or from causing property damage.

Dispose of all vegetative matter and any other materials removed from State Rights-of-Way in accordance with applicable environmental laws, rules, regulations and requirements in the contract.

Complete at least 1 mile of tree trimming, brush and tree removal per day.

Trim branches, limbs and brush to a distance of 30 feet from the edge of pavement and a height of 20 feet above the pavement unless otherwise directed.

Trees to be removed shall be marked by the State with a red, white or orange “X”, painted on the trunk.

Remove trees as designated. Tree removal for this contract will be used on an as needed basis. The engineer will send the contractor written notification requiring him to move in and begin tree removal each time there are a minimum of 10 trees to be removed. After completion of the required tree removal the contractor may again move out, and this procedure will continue for the duration of the contract.

Pick up and remove all trees and limbs felled from right-of-way on the same day, unless otherwise approved.

Remove trees that are already down in the right-of-way. Cut and measure trees that have fallen from private property at the right-of-way line. These trees will be paid for in the same manner as trees that are to be felled and removed.

Grind all limbs and protruding roots. Grind all stumps to a depth of 8 inches below the ground level. Backfill any resulting holes to the level of the surrounding ground.

Project Number: RMC 6265-02-001

Sheet

County: Trinity

Control: 6265-02-001

Highway: SH 19, ETC.

Remove a tree in increments when cutting the trees at ground level may endanger overhead utility lines or damage private property.

Trees that have fallen onto the right-of-way from private property will be cut and measured at the right-of-way line.

Removal of brush, limbs, debris, and trees less than 4 inches in diameter are considered brush and will be subsidiary to Item 752.

CONTROL : 6265-02-001
PROJECT : RMC - 626502001
HIGHWAY : SH0019
COUNTY : TRINITY

TEXAS DEPARTMENT OF TRANSPORTATION

GOVERNING SPECIFICATIONS AND SPECIAL PROVISIONS

ALL SPECIFICATIONS AND SPECIAL PROVISIONS APPLICABLE TO THIS PROJECT
ARE IDENTIFIED AS FOLLOWS:

STANDARD SPECIFICATIONS: ADOPTED BY THE TEXAS DEPARTMENT OF
----- TRANSPORTATION JUNE 1, 2004.
STANDARD SPECIFICATIONS ARE INCORPORATED
INTO THE CONTRACT BY REFERENCE.

ITEMS 1 TO 9 INCL., GENERAL REQUIREMENTS AND COVENANTS
ITEM 752 TREE AND BRUSH REMOVAL

SPECIAL PROVISIONS: SPECIAL PROVISIONS WILL GOVERN AND TAKE
----- PRECEDENCE OVER THE SPECIFICATIONS ENUMERATED
HEREON WHEREVER IN CONFLICT THEREWITH.

SPECIAL PROVISION "DEPARTMENT DIVISION MAILING AND PHYSICAL ADDRESS"
(000---011)

SPECIAL PROVISION "PARTNERING" (000--2329)

SPECIAL PROVISION "SCHEDULE OF LIQUIDATED DAMAGES" (000--2332)

SPECIAL PROVISION "NONDISCRIMINATION" (000--2607)

SPECIAL PROVISION "IMPORTANT NOTICE TO CONTRACTORS" (000--2839)

SPECIAL PROVISION TO ITEM 1 (001---015)

SPECIAL PROVISIONS TO ITEM 2 (002---017)(002---044)

SPECIAL PROVISIONS TO ITEM 3 (003---023)(003---033)

SPECIAL PROVISIONS TO ITEM 4 (004---017)(004---019)

SPECIAL PROVISION TO ITEM 5 (005---004)

SPECIAL PROVISIONS TO ITEM 6 (006---030)(006---047)

SPECIAL PROVISION TO ITEM 7 (007---918)

SPECIAL PROVISIONS TO ITEM 9 (009---012)(009---015)

SPECIAL SPECIFICATIONS:

GENERAL: THE ABOVE-LISTED SPECIFICATION ITEMS ARE THOSE UNDER WHICH
----- PAYMENT IS TO BE MADE. THESE, TOGETHER WITH SUCH OTHER
PERTINENT ITEMS, IF ANY, AS MAY BE REFERRED TO IN THE ABOVE-
LISTED SPECIFICATION ITEMS, AND INCLUDING THE SPECIAL
PROVISIONS LISTED ABOVE, CONSTITUTE THE COMPLETE SPECIFI-
CATIONS FOR THIS PROJECT.

SPECIAL PROVISION

000--2839

Important Notice to Contractors

By the 20th day of each month, report to the Engineer the number of incidents and injuries that occurred on the project the previous month. Report:

- the total number of incidents and injuries for the Contractor and all subcontractors, and
- the number of Contractor and subcontractor-related incidents and injuries that involved a third party.

An “incident” is defined as any work-related occurrence that caused damage only to vehicles, equipment, materials, etc.

An “injury” is defined as an OSHA recordable injury.

Acquire an Electronic Project Records System (EPRS) account to report incidents and injuries. Submit an EPRS User Access Request Form (Form 2451) to request an account. This form can be found at <http://www.txdot.gov/business/resources/doing-business/prequalification.html>.

Report injuries and incidents using the EPRS website located at <https://apps.dot.state.tx.us/apps/eprs/InjuryIncident/InjryIncdt.aspx>.

Failure to submit this information to the Engineers by the 20th day of each month will result in the Department taking actions including, but not limited to withholding estimates and suspending the work. This report will not be paid for directly, but will be considered subsidiary to Items of the contract.