

CSJ: 0006-07-085 Pre-Bid Questions and Answers

7/24/2020

1. In the General Notes under Item 677 - "Removal methods shall be approved by the engineer".
Q: Is mechanical method going to be an approved method?
Yes
2. Are there any PI requirements for the material to be used as Embankment?
no
3. Trailer Mounted Flashing Arrow Boards are shown on Plan Sheet #13. Are those units subsidiary to the Traffic Control Pay Item?
yes
4. Are the Portable Changeable Message Signs shown on Plan Sheet 30 subsidiary to the Temporary Queue Detection System Type 2? Or will an Bid Item be added for those signs?
 - a. Yes they are subsidiary
5. In the SW3P Plan Sheets, reference is made to a Lined Concrete Washout unit. We have not been able to locate a detail. Can a detail be provided and will a Bid Item be added for these erosion control units?
 - a. The lined washout shall be as specified in the plans, but no detail will be provided because it is dependent on the contractor's operation. The washout is subsidiary to the various bid items.