

## PRE-LETTING QUESTIONS AND ANSWERS

CONTROL: 6420-95-001	COUNTY: CASS	AREA OFFICE: Mt. Pleasant
PROJECT: BPM 642095001	LET DATE: October 2022	AREA ENGINEER: Wendy L. Starkes, P.E.
HIGHWAY: SH0155		

DOCUMENT LAST UPDATED ON: 9/26/2022 3:57 PM

#	DATE	QUESTION	ANSWER
1	9/21/2022	Addenda #1 has been requested by Atlanta District	Waiting for approval from Maintenance Division
2	9/22/2022	***ADDENDUM***	An addendum has been created for Cass CSJ 6420-95-001, and has been uploaded to TxDOT website/EBS/ICX.
3	9/23/2022	Are we setting perimeter barricades at each of these 15 sites or just using the appropriate daily TCP?	Barricades will be in accordance with the plans and specifications and will be set up as work is being performed at each site.
4	9/23/2022	If we do need to set perimeter barricades, do they need to stay in place until acceptance of the project or can we move them from site to site as we go?	Barricades will be in accordance with the plans and specifications and will be set up as work is being performed at each site.
5	9/23/2022	Site 4, sheet 39 – Bid Item shows item 785 Bridge Joint Repair (Polymer) - 500 LF - plan sheet says clean & seal joints – is Item 785 for cleaning & resealing the existing header joints with Class 7 sealant?	Joint repair work will be performed at this location will be in accordance with Item 785.
6	9/23/2022	Site 4 – there is no detail given if we are replacing header joints?	Existing polymer joint material will be removed and replaced under Item 785.
7	9/23/2022	There is no plan details for Item 438 Clean & Seal Existing Joints Class 3?	Work will be performed in accordance with Item 438, no detail is needed.
8	9/23/2022	Is there a schedule / timeline showing what TXDOT had at each of the 15 sites?	No
9	9/23/2022	Looking at the work at the sites and the quantity of TMA required for each site, the TMA quantity seems low. Some of the site with 1 TMA are not going to be completed in 1 day.	TMA's will be paid per day used in accordance with SS 6185. TMA's are not a plan quantity item.
10	9/23/2022	Site 6, sheet 42 – plan sheets show clean & seal joints but there is no quantity given and the other 2 sites gets us to plan quantity – are we going to do sealing at this site?	No clean and seal joint is estimated at this location. If, at the time, the engineer decides that the joints need to be cleaned then it will handled in accordance with Item 4.4 "Changes In The Work."
11	9/23/2022	Site 11, sheet 47 – note 6 on sheet says to place flowable fill underneath toe wall but no quantity for flowable fill is given for this site, are we doing this work?	No flowable fill is estimated at this location. If, at the time, the engineer decides that flowable fill is needed then it will handled in accordance with Item 4.4 "Changes In The Work."
12	9/23/2022	Site 15, sheet 52 – are there plan sheet that show on many piles are at this site that require epoxy injection? Bridge description says it is a 7 span bridge, drawings show 5 spans?	It is a 7-span bridge. There is no details for total number of piles. It is estimated that there is 250 LF of crack repair needed.
13	9/23/2022	Item 778-6021 bid item shows 15 LF – plan sheets show site 3 at 15 LF & site 12 with another 10 LF	Plans are being reviewed. An addendum will be processed to correct if an error is confirmed.
14	9/23/2022	Can we use any of the broken up riprap under Item 104-6009 for Item 432-6033?	Riprap placed will need to meet specifications of Item 432. Item 432.2.3.3 "Common" states "When shown on the plans or approved, material may consist of broken concrete..." The plans do not specify approval for the use of broken up concrete.
15	9/26/2022	***ADDENDUM #2***	An addendum (#2) has been created for Cass CSJ 6420-95-001, and has been uploaded to TxDOT website/EBS/ICX.
16			
17			
18			
19			
20			