



NOTE: DECK CLEAN AND SEAL EXISTING JOINTS AT ALL JOINT LOCATIONS IN ACCORDANCE WITH ITEM 438. USE DETAIL "B" ON THE CLEANING AND SEALING EXISTING BRIDGE JOINTS REPAIR DETAILS FOR REFERENCE.

NOTE: Spot Clean and Paint Bearings in accordance with item 446 up to 300 SF.

NOTE: REPAIR PAN GIRDER HOLES USING PAN GIRDER REPAIR DETAILS IN ACCORDANCE WITH ITEM 429.

REPAIR GIRDER STEMS PER TYPICAL GIRDER STEM REPAIR DETAIL (SEE PHOTO #4).

EXTERIOR GIRDERS SHALL BE CLEANED, PREPARED, AND FINISHED AT ALL EXTERIOR DRAIN HOLES AS DIRECTED BY THE ENGINEER. THIS WORK IS ESTIMATED AT 10 SF PER EXTERIOR DRAIN HOLE, AND SHALL BE PERFORMED IN ACCORDANCE WITH ITEM 427, SURFACE FINISHES FOR CONCRETE.

Sta. 825+55 - 833+85
18 Span Bridge (3 Continuous Steel I-Beam Main Spans and 15 Concrete Pan Girder Approach Spans)
On Concrete Substructure

DATE: 8/31/2021 2:16:09 PM FILE: T:\BIDDING\2021\206_Pecan_Bayou.dgn

This document is released for informational purposes under the authority of:
Dan A. Hohmann, P.E.
Engineering Seal # 97588
8/31/2021
It is not to be used for regulatory approval, permit, bidding, or construction purposes.

ITEM	CODE	DESCRIPTION	QUANT	UNIT
401	6001	FLOWABLE BACKFILL	2	CY
429	6007	CONC STR REPAIR (VERTICAL & OVERHEAD)	84	SF
429	6001	CLEANING AND SEALING EXISTING JOINTS	593	LF
446	6010	CLEAN AND PAINT EXIST STR (SYSTEM I-A)	1	LS
429	6023	CONC STR REPAIR (PAN GIRDER HOLE REPR)	150	EA
427	6006	EPOXY WATERPROOF FINISH	720	SF

SH 206 @
PECAN BAYOU
230420045203021
COLEMAN CO.



CONT	SECT	JOB	HIGHWAY
0288	01	039, etc.	SH 16, etc.
DIST	COUNTY	SHEET NO.	
BWD	COMANCHE, ETC.	134	