

## Pre-Bid Questions

<b>Last Updated:</b>	3/28/2019
<b>Project:</b>	NH 2019(977), etc.
<b>Control:</b>	0049-06-079, etc.
<b>Highway:</b>	SH 6
<b>Let Date:</b>	April 2019
<b>From:</b>	Falls County Line, etc.
<b>To:</b>	FM 1644 West, etc.
<b>County:</b>	Robertson, etc.
<b>District:</b>	Bryan
<b>Addendums:</b>	None issued

### Question 1:

On plan sheet 49, DRIVEWAY AND INTERSECTION DETAILS, a one course surface treatment is shown. There are no bid items shown for this surface treatment. Is this subsidiary to the 530 items?

### Response 1:

The one course surface treatment is subsidiary to Item 530. Asphalt type, rock type and estimated quantities are shown in the Basis of Estimate.

### Question 2:

Note 2 on sheet 49 states that additional ACP may be required to construct driveway to desired slope. Can you please provide clarification on the depths of the driveways/intersections?

### Response 2:

Additional ACP may be required to achieve a 20:1 driveway slope at some driveway locations. The depth ranges from 1" to 4" with an average depth of 2" for all driveways.

### Question 3:

On what surface and during what sequence of construction will the work zone non-removable stripe be installed?

### Response 3:

The work zone non-removable striping will be installed on the final riding surface. It is the intent to install the work zone stripe as the job progresses so that the short term tabs are not in place for more than the 14 calendar days allowed in the specification. Thermoplastic stripe will be installed after the entire overlay is complete.