

Pre-Bid Questions

Last Updated:	3/31/2022
Project:	BR 1702 (439)
Control:	0917-30-057
Highway:	CR 211 / CR 272
Let Date:	April 2022
From:	Various
To:	Various
County:	Burleson
District:	Bryan
Addenda:	None issued

Question 1:

The plan set does not include a CCSS or any standard sheets for crash cushions. Will there be an addendum?

Response 1:

TxDOT is aware of the discrepancy, please bid the project as advertised. Any quantity or item errors will be adjusted under the contractor provisions for Item 4.4 after letting and award of the contract.

Question 2:

Regarding bid item # 407 6001 Sheet Piling (PZ – 27) : Two suppliers have asked if alternate profiles with equal or better properties would be permitted, and if cold rolled sheet piles can be used?

Response 2:

We will consider alternate designs and materials after the award and authorization of the contract. Bidders are asked to bid the items as shown. We do not guarantee acceptance of any alternative proposals.

Question 3:

Question regarding bid item 508 6001 Constructing Detours: Is this the same as the temporary pavement shown on sheets 14 and 15 of the CR 211 traffic control plan? There is no detail in the plans that is specifically identified as a detour.

Response 3:

Yes, Item 508-6001 is compensation for the temporary pavement shown on sheets 14 and 15.

Question 4:

Are the earthwork quantities required to accommodate the temporary pavement areas on CR

211 included in the bid items for roadway excavation and embankment?

Response 4:

Per spec item 508 of the "Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges", this embankment is included in the payment for "Constructing Detours".

From Article 508.5

"The price bid for "Constructing Detours" or for Constructing Detours by Type as shown on the plans is full compensation for furnishing all materials required, including embankment, base, and surfacing; excavation and hauling of excavated material; sprinkling and compacting; furnishing, installing, and removing drainage structures; removal of detour; disposal of materials; and equipment, labor, tools, and incidentals".