

CSJ 0447-05-075 - FM 774 Pre-Bid Questions - 6/1/2020

Date Received	Date Responded	Question	Response
5/13/2020	5/28/2020	General Notes for Item 5 reference that a 3D model is available for our use. Doesn't seem like this type of project would have such a thing. Is this included in error or is this really available?	<p>Cross sections and a 3D pdf are available for the FM 136 location for bidding. The 3D design files can be provided for construction.</p> <p>For the FM 774 location, conventional earthwork items were not utilized and cross sections are not available.</p> <p>Cross sections and 3D pdf for the FM 136 location are provided.</p>
5/13/2020	5/28/2020	General notes under Item 247. The Last 2 sentences seem contradictory. Is ride quality going to be required or not on the Flexbase widening?	Ride quality is applicable to travel lanes only. It is not required or applicable on widened shoulder sections.
5/15/2020	5/28/2020	Where is the 340 feet of tree trimming and underbrush removal (Item 752) located on FM 774?	There is 380 LF of Item 752 Tree Trimming and Brush Removal in the contract located on FM 136 from Station 43+36 to station 47+16. See plan sheets 21 and 49 for reference.
5/22/2020	5/28/2020	I'm wondering of cross sections of the project will be available to the contractor?	Cross sections are available for the widening work at the FM 136 location only.
5/27/2020	6/3/2020	Item 530 for concrete driveway (266 CY), what is the depth of concrete and the rebar detail, I cannot seem to find these in the plans or specifications.	Item 530 -6004 DRIVEWAYS (CONC) in the project is paid by the square yard for a total of 266 SY. The depth and rebar details are not included in the plans and specifications. The item should be bid as advertised.
5/27/2020	5/28/2020	In the general notes it states that this project has a 3D model in both XML and PDF format, can you send me both file versions?	<p>Cross sections and a 3D pdf are available for the FM 136 location for bidding. The 3D design files can be provided for construction. An XML was not completed.</p> <p>For the FM 774 location, conventional earthwork items were not utilized and cross sections are not available.</p> <p>Cross sections and 3D pdf for the FM 136 location are provided.</p>