CSJ 0507-04-045 FM 1069 Pre-Bid Questions - 8/4/2020			
Date Received	Date Responded	Question	Response
7/9/2020	7/20/2020	Are you able to give the locations of the 18 trees to be removed?	The trees to be removed under Item 100-6007 PREP ROW (TREE)(GREATER THAN 24" DIA) are all located on the NE end of the project limits between STA 648+73 and STA 661+73. There are 18 trees in the ROW between FM 1781 and Eller Ln. to be removed.
7/21/2020	7/31/2020	Bid Item 644 6080 SM RD SN SUP & AM TY TEMP Please clarify what is required….Remove the existing foundation? Is the Temp sign support with Telespar or Slip Base with Concrete and S80 pole?	The temporary item is in the contract for the placement of the existing signs on temporary supports while the roadway work is being completed. There are no support requirements for the temporary placement of the signs.
7/24/2020	8/4/2020	In the plans pages 10-11 are in there twice and sheets 8-9 are missing.	An addendum has been completed to add sheets 8 & 9 to the plan set. Please see the FTP site for the addendum information and added plan sheets.
7/28/2020	7/31/2020	Item 134 Backfill (Ty A or B) - In general notes its calling for (R.A.P) is this correct and if so is TxDot providing the material?	TxDOT will not be providing RAP material. RAP as mentioned is for the use of Ty B, potentially from the 1' cut in on the existing roadway. Item is for TY A or TY B. TY A is from a source outside of the ROW.
7/28/2020	7/28/2020	Item 316 - General Notes are calling for a vacuum sweeper. Will this be required?	Item 316 should be bid based on the requirements in the General Notes.
7/29/2020	7/31/2020	General note says use rap for backfill is this required or can we use on site since bid item is A or B.	Item is for TY A or TY B. TY A is from a source outside of the ROW.
7/29/2020	7/31/2020	General Note says tree trimming subsidiary but there is a bid item for 121 LF.	Tree trimming wil be paid through Item 752-6022 Tree Trimming and Brush Removal for a total of 121 LF.
7/29/2020	8/4/2020	Driveway detail sheets are missing pages 8/9 I believe.	An addendum has been completed to add sheets 8 & 9 to the plan set. These sheets include all driveway details. Please see the FTP site for the addendum information and added plan sheets.