

EARTHWORK TOTALS		
LOCATION	EXCAVATION (ROADWAY) ITEM 110-6001	EMBANKMENT FINAL (ORD COMP)(TY-C) ITEM 132-6005
	(CY)	(CY)
LOOP F	12520.7	11753.4
LOOP J	6773.4	6152.3
EAST SPINE RD	8471.7	7717.5
WEST SPINE RD	3348.4	3110.4
LOOP D	2524.3	2341.6
LOOP C	226.2	381.4
PARKING LOT #2	902.0	902.0
PARKING LOT #11	1,168.5	1,168.5
PARKING LOT #16	737.7	737.7
TOTAL	36,672.9	34,264.8