

EAST SPINE RD CSJ:0198-47-096

Station	Cut End Area	Fill End Area	EXCAVATION (ROADWAY) ITEM 110-6001	EMBANKMENT FINAL (ORD COMP)(TY-C) ITEM 132-6005
	(SF)	(SF)	(CY)	(CY)
0+00	76.2	67.9		-
0+50	74.5	66.3	139.5	124.3
1+00	72.1	65.7	135.7	122.2
1+50	73.2	65.6	134.5	121.6
2+00	N/A	N/A	N/A	N/A
2+50	N/A	N/A	N/A	N/A
3+00	N/A	N/A	N/A	N/A
3+50	73.4	65.5		
4+00	73.0	65.3	135.6	121.1
4+50	70.8	63.8	133.1	119.5
5+00	73.1	65.0	133.2	119.3
5+50	75.2	66.5	137.3	121.8
6+00	71.4	65.9	135.7	122.6
6+50	74.1	66.7	134.7	122.8
7+00	73.0	66.3	136.2	123.1
7+50	73.6	66.3	135.7	122.8
8+00	74.5	66.6	137.1	123.1
8+50	74.1	66.3	137.6	123.1
9+00	73.0	66.2	136.2	122.7
9+50	71.6	65.8	133.9	122.2
10+00	73.1	66.9	134.0	122.9
10+50	72.5	66.6	134.8	123.6
11+00	71.8	65.9	133.6	122.7
11+50	70.3	64.7	131.6	120.9
12+00	74.7	66.1	134.3	121.1
12+50	72.5	64.7	136.3	121.1
13+00	73.5	65.4	135.2	120.5
13+50	65.5	63.2	128.7	119.1
14+00	68.5	64.4	124.1	118.1
14+50	75.6	67.1	133.4	121.8
15+00	67.7	64.1	132.7	121.5
15+50	70.2	64.8	127.7	119.4
16+00	75.8	67.6	135.2	122.6
16+50	74.6	67.2	139.3	124.8
17+00	76.0	67.7	139.4	124.9
17+50	75.0	67.7	139.8	125.4
18+00	70.6	65.2	134.8	123.1
18+50	70.4	65.2	130.6	120.7
19+00	71.6	65.7	131.5	121.2

19+50	69.6	65.1	130.7	121.1
20+00	70.8	66.0	130.0	121.4
20+50	70.1	65.5	130.5	121.8
21+00	71.5	65.5	131.1	121.3
21+50	73.9	66.7	134.6	122.4
22+00	72.2	66.7	135.3	123.5
22+50	71.7	66.5	133.2	123.3
23+00	71.5	66.1	132.6	122.8
23+50	69.2	64.9	130.3	121.3
24+00	74.8	67.5	133.3	122.6
24+50	71.7	65.9	135.6	123.5
25+00	73.3	68.1	134.3	124.1
25+50	74.6	69.0	136.9	126.9
26+00	77.1	69.3	140.5	128.1
26+50	76.2	68.3	141.9	127.4
27+00	76.0	67.7	140.9	125.9
27+50	75.0	67.4	139.8	125.1
28+00	75.3	67.4	139.2	124.8
28+50	76.2	67.9	140.3	125.3
29+00	78.4	68.8	143.1	126.6
29+50	77.1	68.9	144.0	127.5
30+00	72.3	66.4	138.3	125.3
30+50	73.6	66.9	135.1	123.4
31+00	70.6	65.8	133.5	122.9
31+50	68.7	64.1	129.0	120.3
32+00	64.2	61.1	123.1	115.9
32+50	68.3	63.6	122.7	115.5
33+00	69.8	65.0	127.9	119.1
33+50	71.4	65.9	130.7	121.2
EAST SPINE SUBTOTAL			8,471.7	7,717.5