

LOOP F CSJ:0198-47-096

Station	Cut End Area	Fill End Area	EXCAVATION (ROADWAY) ITEM 110-6001	EMBANKMENT FINAL (ORD COMP)(TY-C) ITEM 132-6005
	(SF)	(SF)	(CY)	(CY)
13+00	73.6	67.6		
13+50	74.6	68.6	137.2	126.1
14+00	72.7	66.8	136.4	125.4
14+50	64.5	74.8	127.0	131.1
15+00	67.8	73.2	122.5	137.0
15+50	68.2	67.8	125.9	130.6
16+00	65.3	74.8	123.6	132.0
16+50	63.5	71.3	119.3	135.3
17+00	69.2	64.8	122.9	126.0
17+50	65.5	63.6	124.7	118.9
18+00	69.0	65.4	124.5	119.4
18+50	75.0	68.9	133.3	124.4
19+00	76.3	67.9	140.1	126.7
19+50	75.8	67.5	140.8	125.4
20+00	73.2	67.4	138.0	124.9
20+50	64.8	63.1	127.8	120.8
21+00	72.9	65.6	127.5	119.2
21+50	63.5	63.9	126.3	119.9
22+00	75.7	67.4	128.9	121.6
22+50	74.5	67.3	139.1	124.7
23+00	74.4	66.6	137.9	124.0
23+50	72.2	66.1	135.7	122.9
24+00	69.2	65.0	130.9	121.4
24+50	73.6	66.4	132.2	121.7
25+00	69.0	65.1	132.0	121.8
25+50	72.8	66.4	131.3	121.8
26+00	76.0	67.7	137.8	124.2
26+50	72.4	66.2	137.4	124.0
27+00	74.6	67.1	136.1	123.4
27+50	N/A	N/A	N/A	N/A
28+00	N/A	N/A	N/A	N/A
28+50	N/A	N/A	N/A	N/A
29+00	N/A	N/A	N/A	N/A
29+50	N/A	N/A	N/A	N/A
30+00	N/A	N/A	N/A	N/A
30+50	N/A	N/A	N/A	N/A
31+00	75.0	67.1		
31+50	75.5	67.7	139.4	124.8

32+00	55.5	54.5	121.3	113.1
32+50	59.2	56.3	106.2	102.6
33+00	60.2	56.2	110.6	104.2
33+50	71.5	66.1	121.9	113.2
34+00	73.0	67.3	133.8	123.5
34+50	72.6	65.8	134.8	123.2
35+00	72.2	65.6	134.1	121.7
35+50	68.8	64.0	130.6	120.0
36+00	57.9	55.4	117.3	110.6
36+50	56.6	54.9	106.0	102.1
37+00	58.8	56.2	106.9	102.9
37+50	61.4	56.8	111.3	104.6
38+00	56.8	55.3	109.4	103.8
38+50	68.0	63.9	115.6	110.4
39+00	66.1	63.1	124.2	117.6
39+50	67.7	64.0	123.9	117.7
40+00	60.6	56.8	118.8	111.9
40+50	62.2	57.1	113.7	105.5
41+00	60.4	56.4	113.5	105.1
41+50	60.4	56.4	111.9	104.4
42+00	57.9	55.4	109.5	103.5
42+50	61.0	57.8	110.1	104.8
43+00	75.0	66.8	125.9	115.4
43+50	69.8	64.3	134.1	121.4
44+00	72.1	64.9	131.4	119.6
44+50	69.0	63.8	130.6	119.2
45+00	71.9	65.4	130.5	119.6
45+50	75.9	67.8	136.9	123.3
46+00	75.5	67.4	140.2	125.2
46+50	71.3	65.3	135.9	122.9
47+00	71.4	65.4	132.1	121.0
47+50	60.4	56.4	122.0	112.8
48+00	57.7	55.8	109.4	103.9
48+50	60.4	56.4	109.4	103.9
49+00	73.1	66.0	123.6	113.3
49+50	59.8	68.3	123.1	124.4
50+00	61.9	57.9	112.7	116.9
50+50	60.1	56.2	113.0	105.6
51+00	60.8	56.2	111.9	104.1
51+50	67.0	63.8	118.3	111.1
52+00	65.6	68.9	122.8	122.9
52+50	67.0	65.5	122.8	124.4
53+00	68.4	64.8	125.4	120.6
53+50	70.0	64.9	128.1	120.1
54+00	66.5	63.3	126.4	118.7
54+50	74.9	67.0	130.9	120.6

55+00	75.8	67.5	139.5	124.5
55+50	72.5	68.1	137.3	125.6
56+00	72.8	65.9	134.5	124.1
56+50	70.0	64.9	132.2	121.1
57+00	67.1	63.4	126.9	118.8
57+50	67.3	63.2	124.4	117.2
58+00	68.6	63.9	125.8	117.7
58+50	67.5	65.4	126.0	119.7
59+00	70.3	65.8	127.6	121.5
59+50	69.7	65.3	129.6	121.4
60+00	71.1	66.1	130.4	121.7
60+50	72.4	65.9	132.9	122.2
61+00	75.4	67.8	136.9	123.8
61+50	66.3	63.5	131.2	121.6
62+00	68.8	64.7	125.1	118.7
62+50	73.9	66.5	132.1	121.5
63+00	72.6	65.6	135.6	122.3
63+50	66.8	63.3	129.1	119.4
64+00	72.3	65.8	128.8	119.5
64+50	69.9	64.5	131.7	120.6
65+00	68.7	64.0	128.3	119.0
65+50	66.1	63.3	124.8	117.9
66+00	68.6	64.5	124.7	118.3
66+50	67.4	63.9	125.9	118.9
LOOP F SUBTOTAL			12,520.7	11,753.4