

LOOP J CSJ:0198-47-096

Station	Cut End Area	Fill End Area	EXCAVATION (ROADWAY) ITEM 110-6001	EMBANKMENT FINAL (ORD COMP)(TY-C) ITEM 132-6005
	(SF)	(SF)	(CY)	(CY)
0+00	77.0	68.4		-
0+50	75.9	68.0	141.6	126.3
1+00	78.4	68.8	142.9	126.6
1+50	75.1	67.4	142.1	126.1
2+00	76.5	68.4	140.4	125.8
2+50	76.3	68.0	141.5	126.3
3+00	76.9	68.5	141.9	126.4
3+50	76.1	67.8	141.7	126.2
4+00	76.0	67.8	140.8	125.6
4+50	76.0	67.8	140.7	125.6
5+00	76.0	67.8	140.7	125.6
5+50	76.0	67.8	140.7	125.6
6+00	76.0	67.8	140.7	125.6
6+50	76.0	67.8	140.7	125.6
7+00	76.1	67.9	140.8	125.6
7+50	76.0	67.8	140.8	125.6
8+00	76.0	67.8	140.7	125.6
8+50	75.1	66.9	139.9	124.7
9+00	75.7	67.4	139.7	124.4
9+50	64.5	63.6	129.8	121.3
10+00	73.2	66.7	127.5	120.6
10+50	70.9	65.4	133.4	122.3
11+00	68.2	64.4	128.8	120.2
11+50	67.4	63.8	125.6	118.7
12+00	68.2	64.0	125.6	118.3
12+50	67.2	63.2	125.4	117.8
13+00	64.6	62.2	122.0	116.1
13+50	75.5	67.2	129.7	119.8
14+00	74.5	67.1	138.9	124.4
14+50	73.9	66.5	137.4	123.7
15+00	74.5	67.0	137.4	123.6
15+50	72.1	66.4	135.7	123.5
16+00	76.0	67.8	137.1	124.3
16+50	75.7	68.3	140.5	126.0
17+00	72.4	65.7	137.1	124.1
17+50	67.5	62.9	129.5	119.1
18+00	75.5	67.2	132.4	120.5
18+50	76.0	67.9	140.3	125.1
19+00	73.7	65.8	138.6	123.8

19+50	72.1	65.7	135.0	121.8
20+00	72.3	65.5	133.7	121.5
20+50	73.6	66.0	135.1	121.8
21+00	66.0	61.6	129.3	118.1
21+50	71.0	64.8	126.9	117.0
22+00	66.7	63.3	127.5	118.6
22+50	66.2	62.7	123.1	116.7
23+00	64.9	62.9	121.4	116.3
23+50	76.8	67.6	131.2	120.8
24+00	72.8	68.6	138.5	126.1
24+50	77.1	70.8	138.8	129.1
25+00	76.1	67.8	141.9	128.3
LOOP J SUBTOTAL			6,773.4	6,152.3