

LOOP D CSJ:0198-47-096

Station	Cut End Area	Fill End Area	EXCAVATION (ROADWAY) ITEM 110-6001	EMBANKMENT FINAL (ORD COMP)(TY-C) ITEM 132-6005
	(SF)	(SF)	(CY)	(CY)
0+00				
0+50	76.0	67.8	70.4	62.8
1+00	69.9	63.7	135.1	121.8
1+50	68.6	64.1	128.2	118.3
2+00	60.3	56.9	119.4	112.0
2+50	60.0	55.9	111.4	104.4
3+00	59.5	55.8	110.6	103.4
3+50	59.5	55.7	110.2	103.2
4+00	60.1	56.3	110.7	103.7
4+50	60.0	55.9	111.2	103.9
5+00	59.6	55.4	110.7	103.1
5+50	73.4	66.6	123.1	113.0
6+00	57.6	54.4	121.3	112.0
6+50	56.1	54.3	105.3	100.6
7+00	58.0	55.2	105.6	101.4
7+50	57.5	54.8	106.9	101.9
8+00	70.3	65.5	118.3	111.4
8+50	60.0	56.0	120.6	112.5
9+00	59.9	55.9	111.0	103.6
9+50	61.8	56.6	112.7	104.2
10+00	61.4	56.4	114.1	104.6
10+50	76.2	67.8	127.4	115.0
11+00	74.8	66.9	139.8	124.7
LOOP D SUBTOTAL			2,524.3	2,341.6