

WEST SPINE RD CSJ:0198-47-096

Station	Cut End Area	Fill End Area	EXCAVATION (ROADWAY) ITEM 110-6001	EMBANKMENT FINAL (ORD COMP)(TY-C) ITEM 132-6005
	(SF)	(SF)	(CY)	(CY)
177+00	67.6	64.4		
177+50	70.2	65.8	127.6	120.6
178+00	71.9	64.8	131.6	120.9
178+50	67.6	63.9	129.2	119.2
179+00	71.0	65.4	128.3	119.7
179+50	65.5	62.8	126.4	118.7
180+00	69.7	64.6	125.2	118.0
180+50	70.7	65.5	130.0	120.5
181+00	69.5	64.7	129.8	120.6
181+50	71.3	65.3	130.4	120.4
182+00	70.4	65.1	131.2	120.7
182+50	72.0	65.5	131.9	120.9
183+00	72.3	65.6	133.6	121.4
183+50	66.9	63.7	128.9	119.7
184+00	69.2	64.5	126.0	118.7
184+50	69.9	65.1	128.8	120.0
185+00	69.3	65.1	128.9	120.6
185+50	69.7	65.2	128.7	120.6
186+00	68.5	64.5	128.0	120.1
186+50	69.5	64.9	127.8	119.8
187+00	68.6	64.5	127.9	119.8
187+50	71.5	65.5	129.7	120.4
188+00	73.3	66.2	134.1	121.9
188+50	56.8	56.5	120.5	113.6
189+00	73.3	66.2	120.5	113.6
189+50	69.6	64.0	132.3	120.6
190+00	72.3	65.0	131.4	119.4
<b>WEST SPINE SUBTOTAL</b>			<b>3,348.4</b>	<b>3,110.4</b>