



CSJ: 0195-03-100  
 Highway: IH 35  
 County: Denton

QUESTIONS/REQUEST	ANSWERS
6/10/2021	
The crash cushion summary sheet shows a reusable crash cushion is required, but the standard sheets are for sacrificial units. Can you please clarify?	Crash Cushion Summary is incorrect, sacrificial units should be used. Crash Cushion Summary Sheet can be replace per Item 4 if needed.
6/21/2021	
Looking at the above mentioned project, the crash cushion bid item# 545 6019 is for a Sacrificial unit, the Absorb M standard is attached in the plans but the Summary sheet is calling out a Reusable unit. Can you please confirm which should be quoted?	Crash Cushion Summary is incorrect, sacrificial units should be used. Crash Cushion Summary Sheet can be replace per Item 4 if needed.
6/22/2021	
Regarding item 512 PCTB, on sheet 18 of the plans under stage 2 it states to remove the PCTB, but there is no bid item for this. Can you please clarify if this PCTB is to be removed or if it is to remain?	Bid as shown, you are correct the Stage 2 does state to remove the PCTB, but the E&Q sheets nor summary sheets show the PCTB removal item/quantity. This is a plan error, the "0512 6053 PORT CTB (REMOVE)(F-SHAPE)(TY 1)" item was intended to be on the E&Q sheet and summary sheet. Bid the items shown, do <b>NOT</b> make the missing item subsidiary.
6/23/2021	
Can the cross sections, XSR files, contract time determination schedule, and any geotechnical information be uploaded for the above mentioned project?	Yes, these will be uploaded to the FTP site. Please note page 58 diagram for an example of how earthwork was calculated.