

Pre-Bid Question Form

Project: CATTLEGUARD REPLACEMENT
 Control: RMC 6373-23-001
 Highway: FM 2185
 County: CULBERSON

NO.	Question	Response
1	Wanted to confirm that once work is complete that you want these detours removed?	Remove as shown on sheet 5C and 8.
2	If we need to remove the detour does TXDOT have any need for the base material?	As proposed and per Item 508 the removed materials will become the property of the Contractor unless otherwise directed by the Engineer during construction.
3	The TCP detail / drawing on Sheet 23 doesn't seem to match the typical section on Sheet 4? Are we supposed to construct the detour to move traffic a specific distance from the cattle guard?	Yes, the minimum work zone width should be 42' and the temporary lane should not encroach this width.
4	Can we work multiple locations at a time or do we need to complete one before starting the next one?	As per note on sheet 8 , work will only be permitted at one location at a time or as directed and approved by the Engineer.