

Pre-bid Questions and Answers CSJ # 0027-12-158

8/22/2022	Bid Item Removing Conc (Riprap) 1,100 SY: Where is this located? I found 6.67 SY on sheet 96, but that was it.	Quantity was included to repair existing areas damaged during construction.
8/22/2022	General Notes Sheet P and Q have charts that show Frontage Road and Ramp closure information. Is there a chart for Main Lane closures also?	Acknowledged. Bid per plans.
8/22/2022	Can you please explain the portable traffic barrier? Item Port CTB (Fur & Inst)(Sgl slope)(TY 1) is 5,350 LF. The item for removal (Port CTB (Remove)(Sgl Slp)(TY 1) is 500 LF. That leaves 4,850 LF onsite, and not removed. You have an Item for Perm CTB (F-Shape)(TY 1) for 3,100 LF and TY 2 for 20 LF. Are you wanting to pin the portable barrier using the detail on sheet 75 C to create the permanent barrier? If so, that would be 5,350 LF (that we brought in) – 500 LF that is removed – 3,120 (F-Shape) = 1,730 LF that still needs to be removed	Acknowledged. Bid per plans. The single slope Portable CTB is not going to be used in place for the final median barrier. The final median barrier will be F-Shape CTB.
8/22/2022	General Notes Sheet S Item 512 says to use the TXDOT Stockpile located across IH 610 from Long Drive for the Portable Barrier used on the project? If that is your intent, shouldn't the bid item say designated source?	Port CTB (Fur & Inst)(Sgl slope)(TY 1) is the correct bid item.
8/22/2022	Where does the removal of the existing conduit that runs along both bridges pay for? Is there information on what this is? Is it alive or dead?	Refer to CTMS plan sheets Note 4 and Note 5.