

Pre-bid Questions and Answers CSJ # 0027-12-158

<p>9/1/2022</p>	<p>Addendum 1 added 13,000 SF of Temporary Spl Shoring (Cofferdam). The addendum didn't have any drawings or details regarding the cofferdam. My question is do we need this? If we are driving piles why do we need a cofferdam? Can this item be removed? If not, can you please provide some drawing/details? Also, this will affect the schedule. Can additional days be added?</p>	<p>Temporary Spl Shoring (Cofferdam) was added in Addendum 1 for construction of the bridge bents. Needs and location are to be determined by the contractor. If contractor proposes to use an alternate process to build the bents then they should bid accordingly.</p>
-----------------	---	---