

**CSJ 0367-02-082  
SH 87  
Galveston County**

**Pre-Letting Questions & Answers 2  
8/16/2022**

<b>Date Question Received</b>	<b>Questions / Answers</b>
8/12/2022	<p>Q. Since Cross Section are not available, please provide the calculations used (and assumptions made) to determine the quantity for item 110 6004 Excavation (Roadway and Channel).</p> <p>A. Typical dimensions used are 21.5-ft horizontal width, and 11.8-ft vertical height according to 2-ft crest, 2:1 surface slope. With 7.5-ft thickness of 30-in riprap, and 1-ft thickness of bedding stone, and corresponding 10,500-ft project limits, remainder quantity for excavating driveways and project start &amp; end transitions.</p>
8/12/2022	<p>Q. It looks to us like the intent of the contract is for there to be 30" individual stones, which means the Item Code &amp; Description are correct, but the general note should not be included since 432.2.3.3 does not require different materials that 432.2.3.4. Can you please confirm which sized stones are intended to be installed?</p> <p>A. For both item 432-6031 and 432-6036, bid according to General Notes, Item 432 2.3.3. Refer to sheet 49, note 7, "use of crushed concrete is not approved".</p>
8/12/2022	<p>Q. Can you please clarify the following what the dimension callouts are intended to represent? Is it supposed to be the width of the armor stone (from beachside of SSCB to beachside limit of armor stone)?</p> <p>A. Yes, dimension callouts are intended for width of armor stone, starting from beachside of SSCB towards the beach.</p>