

Pre-Letting Response(s)

Project Number: RMC: 6340-01-001

Date Last Updated: February 7, 2020

Date Question Received	Question	Response
02/07/20	<ol style="list-style-type: none"> 1. Item 432 – stone riprap – the bid item is for 8” common stone grouted – sheet 5 of the plans show 6” stone – general note sheet 3C shows no grout – wanted to confirm that we are bidding the 8” stone with grout? 2. Item 432 – we assume that the area to receive the stone is the same 350 SY that we are hand cleaning, is this correct? 3. Item 432 – if we were only placing the stone in this 350 SY area it appears the quantity for 8” stone is overstated – $350 \times 9 \times .67 / 27 = 78.17$ CY. The only measurement we have for the bridge is from sheet 9 showing the width of the bridge at 47.67’ – if we are only placing stone underneath the bridge structure on both sides then the 155 CY of stone riprap = $155 \times 27 = 4185$ CF / $.67 = 6246.26$ SF / $47.67' = 131.03' / 2$ sides = 65.51’ per side - Is the stone being placed only under the bridge? Sheet 5 shows only placing the stone on the flat part of the existing concrete riprap which would less than 65.51’ per side. 4. Item 788 – bid item is for Concrete Beam Repair – plan sheet 5 says concrete beam repair – sheets 9,9A,9B,9D all show beam repairs with carbon fiber on them – this doesn’t match the bid item? Will there be an addendum or do we need to bid the repairs with the carbon fiber? 5. The area where the beam repairs & bearing pad replacement are is pretty covered in soot – we only need to clean the beams that we are repairing and only in the area where we are placing the patching & carbon material, is this correct? 	<p style="color: red;">Bid as 8” common stone grouted as shown in plans bid description.</p> <p style="color: red;">Cleaning is the areas which get 8” stone riprap (grouted) as shown plans.</p> <p style="color: red;">Bid as shown in plans for 155 CY</p> <p style="color: red;">Item 788 covers Item 786 “carbon Fiber Polymer Rap”.</p> <p style="color: red;">Bid per plans.</p>
