

PROSPECTIVE BIDDER'S INQUIRIES

CSJ: 3248-01-007

Bid Opening Date: May 5, 2022

No.	QUESTION	TxDOT AREA OFFICE RECEIVED QUESTION FROM BIDDER	RESPONSE
		DATE	
1	Plan sheet #4 "Proposed Sequence of Construction" note #4 states 14" cement treatment to be performed in two equal lifts unless otherwise approved. Will TXDOT allow the work to be performed in one lift?	5/2/2022	The engineer can consider placement in a single lift if acceptable compaction efforts are demonstrated.
2	Plan sheet #8 "Prep Row Summary" note states to remove all limbs extending into row a minimum of 60' above natural ground. Plan sheet #124 "Typical Removal and Trim Detail" states to remove overhanging limbs a minimum of 60' above pavement edge elevation. Please clarify.	5/2/2022	The contractor shall trim trees inside of the prep ROW limits to a minimum height of 60' above pavement edge. Contractor shall remove the entire tree if any of the trunk is in the limits of the ROW.
3	Can you please post the engineers design time schedule for FM 1878 CSJ: 3248-01-007?	5/3/22	Posted to FTP site.
4			
5			