

PROSPECTIVE BIDDER'S INQUIRIES

CSJ: 0336-03-072

Bid Opening Date: June 1, 2022

No.	QUESTION	TxDOT AREA OFFICE RECEIVED QUESTION FROM BIDDER	RESPONSE
		DATE	
1	Please confirm the base for the crash cushions.	05/17/2022	Foundation Types mentioned in the standards (sheets 126 &127) will be accepted.
2	Request Time Determination schedule	5/18/2022	Posted to FTP site.
3	Can we use Precast Culvert for the Culverts Extensions?	5/18/2022	Provide cast-in-place box culverts as mentioned in general notes sheet H.
4	Please provide details for PREP ROW. Is it tree trimming for certain distance from the edge of the roadway to a certain height or a complete clearing all the way to Right of Way Line?	5/23/2022	The intent of the prep row is to limb the trees within the row at a height of 60' measured from the edge of the pavement vertically 60'.
5	It is my understanding by reading the response posted that there will only be trim trimming, and it will be everything from the edge of pavement going straight up 60'. Basically, anything overhanging the roadway. Is this correct?	5/27/2022	No. All limbs within the right of way will require trimming. The trimming will be measured at 60' above the elevation of the edge of roadway pavement.