

PROSPECTIVE BIDDER'S INQUIRIES

RMC: 6331-09-001 (Polk County) Drainage Repair

Bid Opening Date: 03/04/2020

No.	QUESTION	TxDOT MNT OFFICE RECEIVED QUESTION FROM BIDDER	RESPONSE
		DATE	
1	According to Sheet 6 of the plans, "Location F" is the location for item 467-6003 SET (REPLACE PIPE RUNNER ASSEMBLY). Sheets 48-50 address "Pipe Runner Installation Details (Location F)", but there are no specific details. The table on Sheet 50 illustrates pipe runner dimensions for 3 different culverts. Can you clarify the pipe runner dimensions for item 467-6003? The plan quantity is 2 EA.	02/26/2020	Please use the culvert information on Sheet 50 for STA 264+27. Item 467-6003 SET (REPLACE PIPE RUNNER ASSEMBLY) is to replace the entire assembly of pipe runners on both the upstream and downstream ends of the culvert. The existing culvert structure is 3 - 7'x6' box culverts.