

Project Q & A's

Letting: June 4, 2020 (1:00PM)

Project: RMC 636348001

CCSJ # 6363-48-001

Highway: IH20

County: Reeves

1. Location 2 to shows no TC plan. Will traffic be allowed drive on the bridge while it is jacked up at location #2? If so does any additional work need to be done to accommodate traffic? If so how will it be paid? **The Contractor must submit a jacking and shoring plan that can accommodate the dead load and live load in order to perform work under traffic. Please see Note 2 of Sheet 53. This is subsidiary to Item 0495.**
2. Location 3 appears to be washed out 3'-4' from when the project was designed. Will fill material be required and how will this be paid for? How will the removal of any miscellaneous debris material be paid for? **Existing embankment to be used as backfill below/around gabions. This will be subsidiary to gabion item. Removal of any miscellaneous debris will be subsidiary to the flowable backfill item.**
3. Location 3 Will all the dewatering that will be required to install the gabions be subsidiary to the gabions? **Yes, this will be subsidiary to gabion items.**