

## Project Q & A's 08/24/2020

Letting: September 4, 2020

Project: RMC 635529001

CCSJ # 6355 29 001

Highway: SH 115

County: Andrews

1.) In checking the quantities at location #2, I discovered two things:

a.) the width dimensions are shown as inches (12" & 24") in lieu of feet (12' & 24')

The dimensions are by feet not by inch.

b.) assuming the dimensions are intended to be shown as feet, the area of the mill & fill for location #2 is approx. 20,239 SY (3,339 tons), not 11,631 SY (1,920 tons).

Please see revised sheet on Addendum.

2.) The quantities for locations 3 – 8 cannot be accurately verified, because not all width or length dimensions are shown on the plans.

Please see revised sheet on Addendum.

3.) General Note for item 150 Blading mentions filling and grading low areas to drain and preserving topsoil in windrows until it can be replaced and seeded. Is it TXDOT's intent to require seeding on exposed terrain as subsidiary to the Blading item?

No, Txdot doesn't intent require seeding on exposed terrain as subsidiary.

4.) Location 2 @ NB SH 115 @ 1788 shows a work area of 11,631SY. The work areas shown on plan sheet 6 shows a greater area. Can you confirm that the quantity of 11,631SY is correct?

Please see revised sheet on Addendum.

5.) Location 3 @ SH158 EB on ramp and off ramp shows a work area 1,257SY. The work area shown on sheet 7 shows a greater area. Can you confirm that the quantity of 1,257SY is correct?

Please see revised sheet on Addendum