

PROSPECTIVE BIDDER'S INQUIRIES

CSJ: 6350-95-001

Bid Opening Date: 3/4/2020

No.	Question	Date Received	Response
1	Will Steel be an allowable substitute for concrete on this project?	2/27/2020	No alternate bid items were set up to allow for steel traffic barrier on this project. Bidders should bid using concrete barrier in accordance with the plans.
2	At the US 281 location there is a note regarding temp illumination. Will we be allowed to use the TY D ITS electrical service to power temp lighting at this location?	2/27/2020	No. The temporary illumination is not allowed to be powered through the Ty D ITS electrical service. The Contractor will need to provide for continuous temporary illumination to the circuits on either side of the new illumination pole foundation using the existing illumination circuitry. At no time will TxDOT allow any of the illumination circuits in the vicinity of the work area to be blacked out.
3	There are notes regarding a #14 tracer wire at this location. No bid item has been provided for a tracer wire.	2/27/2020	This item was inadvertently left out of the plans. An addendum will not be sought to correct this issue. The issue will be corrected during construction.
4	What is the intent of bid item 6003-6001 ITS SYSTEM SUPPORT EQUIPMENT @ 1 LS? Our understanding of this bid item is to provide spare ITS equipment to TxDOT as called out in the Gen notes. The Gen notes do not call for any spare equipment. Is it possible this item should have been ITS SYSTEM INTEGRATION and not ITS SYSTEM SUPPORT EQUIPMENT?	2/28/2020	The intent is for the Contractor to install the equipment listed in the General Notes under Item 6003. TxDOT will be supplying the material required for installation. No spare equipment will be required on this contract.

Document Revised on: 3/2/2020

TxDOT Public FTP at the Following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting%20Responses/>