

PROSPECTIVE BIDDER'S INQUIRIES

CSJ: 6410-63-001

Bid Opening Date: 9/7/2022

No.	Question	Date Received	Response	Response Date
1	On sheet 8, the General Notes, Typical Section No. 1, note 5 and also Flex Pavt Structure Repair (8") note 6 state to place "non-removable work zone pavement markings prior to opening lanes to traffic". There are currently no work zone non-removable pavement marking pay items. Can you clarify if this note is in error? Is the Department wanting the work zone pavement striped daily with something besides temporary tabs?	9/4/2022	The note on sheet 8 is in error. It should have said to use temporary tabs instead of non-removable pavement markings. The tabs are used on a daily basis and the TY I striping completed after the paving operation is completed for each individual location.	9/6/2022

Document Revised on: 9/6/2022

TxDOT Public FTP at the Following Address:

<https://ftp.dot.state.tx.us/pub/txdot-info/Pre-Letting Responses/>