

April 30, 2021  
TMC 6359-08-001, 6359-10-001,6359-11-001  
Henderson, Garza, Guadalupe Counties

**Contractor Question:**




I cannot find the information for item #80226012. I can find no reference to BRKT TYPE C on any of the specification sheets. Can you please provide further information on this item?

**TxDOT Answer:**

Line item 8022-6012 is for the delivery of the following material:

**TYPE C BRACKET, F/METAL GUARDRAIL POST,1 WAY YELLOW, TYPE E.**

This description code uses a naming convention that is no longer utilized in the current TxDOT standard sheets. Line item 8022-6012 refers to what is now called a Barrier Reflector (BRF) with the GF1 mounting bracket to attach to metal guard railing, see image below for location in the [D&OM \(1\) – 20 standard sheet](#). Please see the [Materials Producer List for Barrier Reflectors](#) to see the currently pre-approved products.

<b>BARRIER REFLECTORS (BRF)</b>			
	GF1	GF2	CTB
DEVICE			
	1. Barrier reflectors shall meet the requirements of DMS 8600. 2. Approved Barrier Reflectors are listed on the "Barrier Reflectors" Material Producer List at: <a href="http://www.txdot.gov">www.txdot.gov</a> .		
SHEETING	Yellow, White, Red		
NOTE	1. Reflective sheeting shall have a minimum dimension of 3 inches and minimum surface area of 9 square inches.		