



LONGVIEW AREA OFFICE, 4549-A WEST LOOP 281 | LONGVIEW, TEXAS 75604 | (903) 234-0532

July 27, 2020

Highway: Various – Safety Improvements

RMC: 0910-07-081

Project: STP 2B20(194)HES

County: GREGG

DS

Q1) Can TxDOT provide coordinates for the guardrail locations as some are difficult to find?

A1) GPS location were not captured for these locations. However, the Statewide Planning map used in conjunction with the location descriptions in the plans is helpful for finding these locations on a map. Use this url to get to the Statewide planning map.

<https://www.txdot.gov/inside-txdot/division/transportation-planning/maps/statewide-planning.html>

Q2) Can TxDOT provide the project time determination sheet?

A2) The time determination schedule (0910-07-081 100% TIMELINE.pdf) has been posted to the ftp site.

Q3) Will there be no pay for the removal of existing TAS's etc.? If not, what is the quantity of the unpaid work items for the contractor's information?

A3) The quantities for removing existing Terminal Anchor Sections (TAS) are included in Item 542. Removing Metal Beam Guard Fence (Bid Code 542-6001). Refer to note 1 on sheet 6. "[1] REMOVAL QUANTITY INCLUDES END TREATMENTS AND TRANSITIONS"

Q4) Plan note for item 150, but no pay item included in the plans.

A4) Bid per the plans.

Q5) Plan note for item 467 requires sod, but no item for either 467 or 162 in the plans.

A5) Bid per the plans.

Q6) Concerning the first note under item 540, are there locations where removal or replacement of "soil cement riprap" required?

A6) The note under Item 540 regarding soil cement riprap may be disregarded. The riprap noted in the plans is covered under Bid Codes 104-6028 REMOVING CONC (MISC) and 432-6041 RIPRAP (SPECIAL) on Sheet 4. Also see Notes [2] and [3] on the Metal Beam Guard Fence Summary on Sheet 6 regarding rip rap and removing concrete.

OUR VALUES: *People • Accountability • Trust • Honesty*

OUR MISSION: *Through collaboration and leadership, we deliver a safe, reliable, and integrated transportation system that enables the movement of people and goods.*

An Equal Opportunity Employer

Q7) Item 542 note states ACP mow strip removal is incidental, are there locations where ACP mow strips will need to be removed?

A7) Locations are not noted in the plans. Sites to be investigated by contractor prior to bidding. Bid per the plans.

Q8) Since most roadways just have one work location and can be performed with daily traffic control setups will end barricades be required on the project(s)?

A8) Bid per the plans.