

PRE-LETTING QUESTIONS AND ANSWERS

CONTROL: 6377-32-001 COUNTY: Archer, etc. AREA OFFICE: Multiple HIGHWAY: Various
 PROJECT: BPM 6377-32-001 LET DATE: 7/1/2021 AREA ENGINEER: Zach Husen, P.E.; Mike Hallum, P.E.; Callan Coltharp, P.E. EMAIL QUESTIONS TO: zachary.husen@txdot.gov; mike.hallum@txdot.gov; callan.coltharp@txdot.gov
****CHANGES FROM PREVIOUS VERSION HAVE BEEN HIGHLIGHTED BELOW**** PREVIOUS VERSION: N/A CURRENT VERSION: 2

#	DATE RECEIVED	STATUS	QUESTION	ANSWER
1	6/23/2021	In Progress	Is dead load and live load information available for bridge jacking at reference numbers 22 and 25?	I believe you are referring to Reference 20 & 25, since those are the structures on which we are replacing the elastomeric bearing pads. With that being said, please see the as-builts for References 20 & 25 in the FTP directory for this project. Dead load and live load information can be calculated using these as-builts.
2	6/23/2021	In Progress	Are as-built drawings available for reference numbers 22 and 25?	I believe you are referring to Reference 20 & 25, since those are the structures on which we are replacing the elastomeric bearing pads. With that being said, please see the as-builts for References 20 & 25 in the FTP directory for this project.
3	6/23/2021	In Progress	Are the bridges (22 & 25) to be raised under live load?	SS4002 references Item 495, which is subsidiary. Spec book Item 495.3.1 says: Prohibit traffic on the structure until the structure is supported by cribbing, falsework, or the final supports.
4	6/23/2021	In Progress	Can you provide details for the collar we are to place at the joint in the pile encasements?	Please see the attached "For Contractor Information Only" Concrete Collar Detail in the FTP directory for this project.
5	6/22/2021	In Progress	Sites 8 – 15 & 25 do not call for perimeter barricades – site 7 only has 23 SF of concrete structure repair, can this site be added to this list?	Reference #7 is in close proximity to References #1-#6, so the Contractor can use the same set of limit barricades to encompass References #1-#7.
6	6/22/2021	In Progress	Item 480-6002 – clean culverts – can the spoils be used to grade / fill in washouts around each location?	Yes, the spoils from the culvert cleaning operations may be used to fill in washouts around each location.
7	6/22/2021	In Progress	Item 7000-6001 – remove & disposal of driftwood – can the debris be mulched / chipped and disposed on site?	Yes, the debris removed from these references can be mulched and disposed of onsite.
8	6/22/2021	In Progress	Plan sheet 6 shows Item 104-6030 & Item 110-6002 & the corresponding sheets for each shows this work but there are not bid items in the proposal for these items?	Bid the items in the proposal & plans appropriately. Payment for missing items will be made
9	6/22/2021	In Progress	Item 4002 – did not see any information on the bearing pads for each site to know what size of bearing pads we need to get quotes on or any information on the weight of the structures to be lifted to calculate the required jacking system?	The bearing dimensions for References #20 and #25 can be found in the as-builts, which can be found in the FTP directory for this project. The weight of the structure can be determined from the as-builts as well. Please note, for Reference #20, we are only proposing to replace the bearings under the concrete I-beams, not the steel members.
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				