Control	**0923-00-067**
Project	**C 923-00-67**
Highway	**VA**
County	**BROWN**

ADDENDUM ACKNOWLEDGMENT

Each bidder is required to acknowledge receipt of an addendum issued for a specific project. This page is provided for the purpose of acknowledging an addendum.

FAILURE TO ACKNOWLEDGE RECEIPT OF AN ADDENDUM WILL RESULT IN THE BID NOT BEING READ.

In order to properly acknowledge an addendum place a mark in the box next to the respective addendum.

ADDENDUM NO. 1 ☐

ADDENDUM NO. 2 ☐

ADDENDUM NO. 3 ☐

ADDENDUM NO. 4 ☐

ADDENDUM NO. 5 ☐

In addition, the bidder by affixing their signature to the signature page of the proposal is acknowledging that they have taken the addendum(s) into consideration when preparing their bid and that the information contained in the addendum will be included in the contract, if awarded by the Commission or other designees.

This page intentionally left blank.

Control	**0923-00-067**
Project	**C 923-00-67**
Highway	**VA**
County	**BROWN**

PROPOSAL TO THE TEXAS TRANSPORTATION COMMISSION

2024 SPECIFICATIONS

WORK CONSISTING OF PREVENTIVE MAINTENANCE

BROWN COUNTY, TEXAS

The quantities in the proposal are approximate. The quantities of work and materials may be increased or decreased as considered necessary to complete the work as planned and contemplated.

This project is to be completed in 94 working days and will be accepted when fully completed and finished to the satisfaction of the Executive Director or designee.

Provide a proposal guaranty in the form of a Cashier's Check, Teller's Check (including an Official Check) or Bank Money Order on a State or National Bank or Savings and Loan Association, or State or Federally chartered Credit Union made payable to the Texas Transportation Commission in the following amount:

THIRTY-NINE THOUSAND (Dollars) **($39,000)**

A bid bond may be used as the required proposal guaranty. The bond form may be detached from the proposal for completion. The proposal may not be disassembled to remove the bond form. The bond must be in accordance with Item 2 of the specifications.

Any addenda issued amending this proposal and/or the plans that have been acknowledged by the bidder, become part of this proposal.

By signing the proposal the bidder certifies:

1. the only persons or parties interested in this proposal are those named and the bidder has not directly or indirectly participated in collusion, entered into an agreement or otherwise taken any action in restraint of free competitive bidding in connection with the above captioned project.
2. in the event of the award of a contract, the organization represented will secure bonds for the full amount of the contract.
3. the signatory represents and warrants that they are an authorized signatory for the organization for which the bid is submitted and they have full and complete authority to submit this bid on behalf of their firm.
4. that the certifications and representations contained in the proposal are true and accurate and the bidder intends the proposal to be taken as a genuine government record.

- **Signed: ****

(1) _____ (2) _____ (3) _____

Print Name:

(1) _____ (2) _____ (3) _____

Title:

(1) _____ (2) _____ (3) _____

Company:

(1) _____ (2) _____ (3) _____

- Signatures to comply with Item 2 of the specifications.

**Note: Complete (1) for single venture, through (2) for joint venture and through (3) for triple venture.

*** When the working days field contains an asterisk (*) refer to the Special Provisions and General Notes.**

NOTICE TO CONTRACTORS

ANY CONTRACTORS INTENDING TO BID ON ANY WORK TO BE AWARDED BY THIS DEPARTMENT MUST SUBMIT A SATISFACTORY "AUDITED FINANCIAL STATEMENT" AND "EXPERIENCE QUESTIONNAIRE" AT LEAST TEN DAYS PRIOR TO THE LETTING DATE.

UNIT PRICES MUST BE SUBMITTED IN ACCORDANCE WITH ITEM 2 OF THE STANDARD SPECIFICATIONS OR SPECIAL PROVISION TO ITEM 2 FOR EACH ITEM LISTED IN THIS PROPOSAL.

TEXAS DEPARTMENT OF TRANSPORTATION

BID BOND

KNOW ALL PERSONS BY THESE PRESENTS,

That we, (Contractor Name) _____

_____

Hereinafter called the Principal, and (Surety Name) _____

_____

a corporation or firm duly authorized to transact surety business in the State of Texas, hereinafter called the Surety, are held and firmly bound unto the Texas Department of Transportation, hereinafter called the Obligee, in the sum of not less than two percent (2%) of the department's engineer's estimate, rounded to the nearest one thousand dollars, not to exceed one hundred thousand dollars ($100,000) as a proposal guaranty (amount displayed on the cover of the proposal), the payment of which sum will and truly be made, the said Principal and the said Surety, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the principal has submitted a bid for the following project identified as:

Control	**0923-00-067**
Project	**C 923-00-67**
Highway	**VA**
County	**BROWN**

NOW, THEREFORE, if the Obligee shall award the Contract to the Principal and the Principal shall enter into the Contract in writing with the Obligee in accordance with the terms of such bid, then this bond shall be null and void. If in the event of failure of the Principal to execute such Contract in accordance with the terms of such bid, this bond shall become the property of the Obligee, without recourse of the Principal and/or Surety, not as a penalty but as liquidated damages.

Signed this _____ Day of _____ 20_____

By: _____

(Contractor/Principal Name)

_____

(Signature and Title of Authorized Signatory for Contractor/Principal)

*By: _____

(Surety Name)

_____

(Signature of Attorney-in-Fact)

*Attach Power of attorney (Surety) for Attorney-in-Fact

Impressed Surety Seal Only

C U T H E R E

This form may be removed from the proposal.

This page intentionally left blank.

BIDDER'S CHECK RETURN

IMPORTANT

The space provided for the return address must be completed to facilitate the return of your bidder's check. Care must be taken to provide a legible, accurate, and complete return address, including zip code. A copy of this sheet should be used for each different return address.

NOTE

Successful bidders will receive their guaranty checks with the executed contract.

RETURN BIDDERS CHECK TO (PLEASE PRINT):

Control	**0923-00-067**
Project	**C 923-00-67**
Highway	**VA**
County	**BROWN**

IMPORTANT

PLEASE RETURN THIS SHEET IN ITS ENTIRETY

Please acknowledge receipt of this check(s) at your earliest convenience by signing below in longhand, in ink, and returning this acknowledgement in the enclosed self addressed envelope.

Check Received By: _____ Date:_____

Title: _____

For (Contractor's Name): _____

Project _____ County_____

This page intentionally left blank.

NOTICE TO THE BIDDER

In the space provided below, please enter your total bid amount for this project. Only this figure will be read publicly by the Department at the public bid opening.

It is understood and agreed by the bidder in signing this proposal that the total bid amount entered below is not binding on either the bidder or the Department. It is further agreed that **the official total bid amount for this proposal will be determined by multiplying the unit bid prices for each pay item by the respective estimated quantities shown in this proposal and then totaling all of the extended amounts.**

$_____

Total Bid Amount

Control 0001-03-030
Project STP 2000(938)HES
Highway SH 20
County EL PASO

ALT	ITEM	DESC	SP	Bid Item Description	Unit	Quantity	Bid Price	Amount	Seq
	104	509		REMOV CONC (SDWLK)	SY	266.400	$10.000	$2,664.00	1

EXAMPLE

Total Bid Amount _____$2,664.00_____

Signed _____
Title _____
Date _____

Additional Signature for Joint Venture:

Signed _____
Title _____
Date _____

EXAMPLE OF BID PRICES SUBMITTED BY COMPUTER PRINTOUT

EXAMPLES

BID PRICES SUBMITTED BY HAND WRITTEN FORMAT

ALT	ITEM-CODE			UNIT BID PRICE ONLY WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC NO	S.P. NO.				
	190	026		RED OAK 1 1/2 - 1 3/4 GAL BB	EA	9.000	1
				EXAMPLE: One hundred fifty DLRS and No CENTS			

Unit price for each plant in place

	249	014		FLEX BASE(DEL)(DENSCOT)(TY A GR4 CL2)	TON	56,787.00	14
				EXAMPLE: Seven DLRS and Fifty three CENTS			

Unit price for each ton of Flexible Base

	430	001	001	CL A CONC FOR EXT STR (CULV)	CY	45.000	27
				EXAMPLE: Three hundred five DLRS and No CENTS			

Unit price for each cubic yard of Concrete

	610	007	001	RDWY ILL ASSEM(TY ST 50T-8-8)(.4 KW)S	EA	13.000	7
				EXAMPLE: Fourteen hundred sixteen DLRS and Thirty seven CENTS			

Unit price of each Roadway Illumination Assembly

This page intentionally left blank.

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	100	7002		PREPARING ROW DOLLARS and CENTS	STA	2.000	1
	110	7002		EXCAV (CHANNEL) DOLLARS and CENTS	CY	58.000	2
	132	7005		EMBANK (FNL)(OC)(TY C) DOLLARS and CENTS	CY	1,700.000	3
	164	7007		BROADCAST SEED (TEMP_WARM_COOL) DOLLARS and CENTS	SY	1,400.000	4
	401	7001		FLOWABLE BACKFILL DOLLARS and CENTS	CY	102.000	5
	403	7001		TEMPORARY SPL SHORING DOLLARS and CENTS	SF	360.000	6
	420	7059		CL C CONC(PILE ENCASEMENT) DOLLARS and CENTS	LF	9.250	7
	420	7067		CL C CONC (MISC) DOLLARS and CENTS	CY	17.500	8
	420	7146		CL C CONC (WINGWALLS) DOLLARS and CENTS	CY	40.000	9
	428	7001		PENETRATING CONCRETE SURFACE TREATMENT DOLLARS and CENTS	SY	184.000	10
	429	7001		CONC STR REPAIR(CLEAN & COAT WTH EPOXY) DOLLARS and CENTS	SF	32.000	11

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	429	7007		CONC STR REPAIR (VERTICAL & OVER-HEAD) DOLLARS and CENTS	SF	542.000	12
	429	7010		CONC STR REPAIR (PAN GIRDER HOLE REPR) DOLLARS and CENTS	EA	107.000	13
	432	7002		RIPRAP (CONC)(5 IN) DOLLARS and CENTS	CY	25.200	14
	432	7041		RIPRAP (STONE PROTECTION)(12 IN) DOLLARS and CENTS	CY	60.000	15
	432	7045		RIPRAP (STONE PROTECTION)(24 IN) DOLLARS and CENTS	CY	283.000	16
	432	7048		RIPRAP (STONE PROTECTION)(36 IN) DOLLARS and CENTS	CY	402.500	17
	438	7004		CLEANING AND SEALING EXIST JOINTS (CL3) DOLLARS and CENTS	LF	351.750	18
	438	7007		CLEANING AND SEALING EXIST JOINTS (CL7) DOLLARS and CENTS	LF	1,062.000	19
	467	7199		SET (TY I)(S= 8 FT)(HW= 10 FT)(3:1)(C) DOLLARS and CENTS	EA	4.000	20
	480	7002		CLEAN EXIST CULVERTS DOLLARS and CENTS	CY	89.000	21
	495	7003		RAISING EXIST STRUCT (REF NO. 1) DOLLARS and CENTS	EA	1.000	22

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	495	7004		RAISING EXIST STRUCT (REF NO. 2) DOLLARS and CENTS	EA	1.000	23
	499	7001		ADJUST STL SHOES DOLLARS and CENTS	EA	1.000	24
	500	7001		MOBILIZATION DOLLARS and CENTS	LS	1.000	25
	502	7001		BARRICADES, SIGNS AND TRAFFIC HAN-DLING DOLLARS and CENTS	MO	6.000	26
	503	7001		PORTABLE CHANGEABLE MESSAGE SIGN DOLLARS and CENTS	DAY	5.000	27
	505	7001		TMA (STATIONARY) DOLLARS and CENTS	DAY	121.000	28
	506	7039		TEMP SEDMT CONT FENCE (INSTALL) DOLLARS and CENTS	LF	900.000	29
	506	7041		TEMP SEDMT CONT FENCE (REMOVE) DOLLARS and CENTS	LF	900.000	30
	658	7056		INSTL OM ASSM (OM-2Y)(WC)GND DOLLARS and CENTS	EA	4.000	31
	735	7060		DRIFTWOOD REMOVAL DOLLARS and CENTS	CY	4.500	32
	776	7024		REPLACE(STEEL RAIL) DOLLARS and CENTS	LF	60.000	33
	778	7004		CONCRETE RAIL REPLACEMENT (IN-KIND) DOLLARS and CENTS	LF	25.000	34

ALT	ITEM-CODE			UNIT BID PRICE ONLY. WRITTEN IN WORDS	UNIT	APPROX QUANTITIES	DEPT USE ONLY
	ITEM NO	DESC CODE	S.P. NO.				
	780	7002		CNC CRACK REPAIR (DISCRETE)(INJECT) DOLLARS and CENTS	LF	79.000	35
	4010	7003		STEEL BRIDGE ZONE PAINTING REF STR #2 DOLLARS and CENTS	EA	1.000	36
	4010	7004		STEEL BRIDGE ZONE PAINTING REF STR #3 DOLLARS and CENTS	EA	1.000	37
	4010	7005		STEEL BRIDGE ZONE PAINTING REF STR #4 DOLLARS and CENTS	EA	1.000	38
	4010	7006		STEEL BRIDGE ZONE PAINTING REF STR #5 DOLLARS and CENTS	EA	1.000	39

CERTIFICATION OF INTEREST IN OTHER BID PROPOSALS FOR THIS WORK

By signing this proposal, the bidding firm and the signer certify that the following information, as indicated by checking “Yes” or “No” below, is true, accurate, and complete.

A. Quotation(s) have been issued in this firm's name to other firm(s) interested in this work for consideration for performing a portion of this work.

_____ YES

_____ NO

B. If this proposal is the low bid, the bidder agrees to provide the following information prior to award of the contract.

1. Identify firms which bid as a prime contractor and from which the bidder received quotations for work on this project.
2. Identify all the firms which bid as a prime contractor to which the bidder gave quotations for work on this project.

ENGINEER SEAL

Control	**0923-00-067**
Project	**C 923-00-67**
Highway	**VA**
County	**BROWN**

The enclosed Texas Department of Transportation Specifications, Special Specifications, Special Provisions, General Notes and Specification Data in this document have been selected by me, or under my responsible supervision as being applicable to this project. Alteration of a sealed document without proper notification to the responsible engineer is an offense under the Texas Engineering Practice Act.



The seal appearing on this document was authorized by

Jason H. Scantling, P.E.

JULY 25, 2024

County: Brown

Highway: Various **Control:** 0923-00-067

GENERAL NOTES

TEST TO BE IN ACCORDANCE WITH
TEXAS DEPARTMENT OF TRANSPORTATION
STANDARD TEST METHODS.

ENVIRONMENTAL GENERAL NOTES

The Contractor will not be allowed to store equipment, materials, incidentals, hazardous chemicals, petroleum products, concrete washouts, etc. in the Department's R.O.W. without written permission from the Engineer.

See the "Environmental" section of the plans for additional information.

To prevent spread of Zebra Mussels and other exotic species:

1. Spray/rinse all equipment and vehicles, using hot and/or high-pressure water as soon as possible after exiting the waterbody.
2. Drain all water from receptacles before leaving the area, and
3. Allow all equipment to dry completely before use in another waterbody
4. If zebra mussels are encountered at the project location, contractor will not transport any equipment from the site and will notify the TxDOT project engineer immediately.

For more detailed information, see: https://tpwd.texas.gov/fishboat/boat/protect_water/

TEXAS ONE CALL

Fiber optic cable systems, gas lines, underground power lines, water lines, sewer lines, and other various utilities may be buried within the project limits. Protection of these utility systems is of extreme importance since any break could disrupt service to users resulting in business interruption and loss of revenue and profits. The Contractor will telephone Texas One Call at 1-800-344-8377 (a 24-hour number), to determine if utilities are buried anywhere on the project in accordance with all UNDERGROUND FACILITY DAMAGE PREVENTION AND SAFETY laws. This action; however, will in no way be interpreted as relief of responsibilities under the terms of the Contract as set out in the plans and specifications. Coordinate the repair of all damages caused by daily operations and have facilities restored to service in a timely manner as directed at no additional cost to TxDOT.

GENERAL

Unless specifically noted as applying to only a certain project or projects, these general notes will apply to all projects associated to this contract.

County: Brown

Highway: Various **Control:** 0923-00-067

Contractor questions on this project are to be addressed to the following individual(s):

Name	Email Address
Chris Graf, P.E.	Chris.Graf@txdot.gov
Jordan Perry, P.E.	jordan.perry@txdot.gov

Contractor questions will be accepted through email, phone, and in person by the above individual(s).

Questions may also be submitted via the Letting Pre-Bid Q&A web page. This webpage can be accessed from the Notice to Contractors dashboard located at the following Address:
https://tableau.txdot.gov/views/ProjectInformationDashboard/NoticetoContractors

All contractor questions will be reviewed by the Engineer. All questions and any corresponding responses that are generated will be posted through the same Letting Pre-Bid Q&A web page.

The Letting Pre-Bid Q&A web page for each project can be accessed by using the dashboard to navigate to the project you are interested in by scrolling or filtering the dashboard using the controls on the left. Hover over the blue hyperlink for the project you want to view the Q&A for and click on the link in the window that pops up.

The term "Article" or "Section" referred to hereon is defined in the forward of the *Standard Specifications for Construction and Maintenance of Highways, Streets, And Bridges* adopted by the Texas Department of Transportation September 2024.

ITEM 6 CONTROL OF MATERIALS

In accordance with **Section 6.10.1.2**, the Contractor will dispose of all painted steel at a steel recycling or smelting facility and a receipt will be required. In lieu of this, the Contractor has the option to either show proof that the paint is lead free or show proof that the lead paint has been abated by an abatement certified company. The Department will not be obligated for the cost of paint testing and/or abatement materials, processes, personnel, incidentals, etc.

The following structures have been identified to have lead paint present:
23-141-0-0251-05-022
23-167-0-0055-01-033
23-141-0-2199-01-001
23-025-0-0054-07-030
23-068-0-0007-14-013
23-215-0-0011-12-058
23-215-0-1031-01-011

ITEM 7 LEGAL RELATIONS AND RESPONSIBILITIES

No significant traffic generator events identified.

ITEM 8 PROSECUTION AND PROGRESS

Working days will be computed and charged in accordance with Section 8.3.1.4. “Standard Workweek”.

Work will not be performed without time being charged unless otherwise exempted by the Section as defined above.

Contractor shall complete all repairs prior to moving to next structure.

PROJECT SCHEDULES

Bar graph scheduling will be required to be submitted and maintained monthly by the Contractor unless otherwise directed by the Engineer. (8.5.2.)

For monthly submittals, the Contractor will provide the schedule in an Adobe Acrobat compatible format (PDF file). If the Engineer requests the schedule in an electronic format, the Contractor will submit a schedule that is fully compatible with Primavera P6 Professional Release 15.

ITEM 9 MEASUREMENT AND PAYMENT

Monthly estimates will be computed from the 26th of the previous month through the 25th of the current month unless otherwise approved in writing by the Engineer.

ITEM 401 FLOWABLE BACKFILL

All flowable backfill will be “Non-Excavatable” unless otherwise specified.
Adequate lead pressure shall be maintained with flowable fill in order to sufficiently fill voids under riprap. Access holes may be required down slope in order to verify suitable backfilling operations.

Use a minimum of four (4) sacks cement per cubic yard.

Type I Cement is required if accelerator is used.

ITEM 420 CONCRETE SUBSTRUCTURES

All Class C Concrete has been measured for plan quantity payment.

ITEM 421 HYDRAULIC CEMENT CONCRETE

Furnish dome lids with 4" x 8" cylinder test molds.

Strength testing equipment is not required for Contract controlling test.

ITEM 427 SURFACE FINISHES FOR CONCRETE

Surface Area II will receive a rub finish

ITEM 429 CONCRETE STRUCTURE REPAIR

Clean debris from all abutment and interior bent caps. This work will be subsidiary to Item 429.

Submit repair materials to the Engineer. Materials must be capable of overhead repairs.

If required, drill and install anchor bars using TY III Class "C" epoxy adhesive meeting DMS-6100 "Epoxy Adhesives."

Prior to repairing concrete, field verify repair method and quantity.

Place silane over all repairs in accordance with the epoxy waterproofing & silane details sheet.

ITEM 432 RIPRAP

Locations and quantities may be varied as directed by the Engineer to accommodate field conditions.

Use dry riprap for the stone protection item. Stones shall be graded so as not to obstruct full channel flow. Filter fabric is required.

Limit excavation to within 1' of riprap. If excavation exceeds these limits without the Engineer's approval, riprap will be extended to the limits of the disturbance. No additional compensation will be allowed for this work.

ITEM 438 CLEANING AND SEALING JOINTS

Clean all joints full depth from top of the slab to the top of cap. This includes joints that have end diaphragms sitting on caps.

Clean all caps of loose material.

Clean all steel and concrete with a 5000 psi water pressure blast and allow to dry thoroughly prior to placing joint material and sealant.

Clean and seal pan girder joints in accordance with Clean & Seal Joints Details (Pan Girder) Detail "B".

Use detail "A" for class 7 clean and seal joints.

Use detail “B” for class 3 clean and seal joints.

ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING

The Contractor will be required to keep all TCP devices clean. If notified by the Engineer to clean the TCP devices, the Contractor will have until the end of that daylight period to comply. Failure to comply will result in a suspension of all work until the TCP devices are clean. Time will not be suspended.

The Contractor Force Account “Safety Contingency” that has been established for this project is intended to be utilized for work zone enhancements, to improve the effectiveness of the Traffic Control Plan, that could not be foreseen in the project planning and design stage. These enhancements will be mutually agreed upon by the Engineer and the Contractor’s Responsible Person based on weekly or more frequent traffic management reviews on the project. The Engineer may choose to use existing bid items if it does not slow the implementation of enhancement.

The Contractor will be responsible for maintaining the edge of the roadway throughout the project in a traversable condition and/or as directed by the Engineer. Salvaged milling may be used as directed by the Engineer. This work will not be paid for directly and will be considered subsidiary to Item 502 “Barricades, Signs, and Traffic Handling”.

All devices shown on the TCP Standards are required and considered subsidiary to Item 502 unless specifically outlined elsewhere in the plans.

All signs will be constructed in accordance with the details shown in the current Standard Highway Sign Designs for Texas manual.

ITEM 505 TRUCK MOUNTED ATTENUATOR (TMA) AND TRAILER ATTENUATOR (TA)

Provide the number of vehicles with truck mounted attenuators (TMA) listed in the table below. The Contractor will be responsible for determining if one or more of these operations will be ongoing at the same time to determine the total number of TMAs needed for the project.

STANDARD / PHASE	# TMA'S REQUIRED
TCP(1-1)	1
TCP(1-2)	1
TCP(1-4)	1

See sheet “TCP SUMMARY” in plans for estimated quantities.

ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS

The Contractor should anticipate multiple mobilizations for the installation of BMP’s on this project.

The Engineer will determine actual time and placement locations of BMP's and temporary measures.

Contractor will not install BMPs until locations are approved by the Engineer.

Stockpile sites may be cleared of cover vegetation, but the vegetation root system will not be destroyed.

CONTROL : 0923-00-067
PROJECT : C 923-00-67
HIGHWAY : VA
COUNTY : BROWN

TEXAS DEPARTMENT OF TRANSPORTATION

GOVERNING SPECIFICATIONS AND SPECIAL PROVISIONS

ALL SPECIFICATIONS AND SPECIAL PROVISIONS APPLICABLE TO THIS PROJECT ARE IDENTIFIED AS FOLLOWS:

STANDARD SPECIFICATIONS: ADOPTED BY THE TEXAS DEPARTMENT OF TRANSPORTATION SEPTEMBER 1, 2024. STANDARD SPECIFICATIONS ARE INCORPORATED INTO THE CONTRACT BY REFERENCE.

ITEMS 1 TO 9 INCL., GENERAL REQUIREMENTS AND COVENANTS
ITEM 100 PREPARING RIGHT OF WAY <103><752>
ITEM 110 EXCAVATION <132>
ITEM 132 EMBANKMENT <100><110><160><204><210><216><400>
ITEM 164 SEEDING FOR EROSION CONTROL <162><166><168>
ITEM 401 FLOWABLE BACKFILL <421>
ITEM 403 TEMPORARY SPECIAL SHORING <410><411>
ITEM 420 CONCRETE SUBSTRUCTURES <400><404><421><422><426><427> <440><441><448>
ITEM 428 PENETRATING CONCRETE SURFACE TREATMENT <427>
ITEM 429 CONCRETE STRUCTURE REPAIR <421><431><440><780>
ITEM 432 RIPRAP <247><420><421><431><440>
ITEM 438 CLEANING AND SEALING JOINTS <454>
ITEM 467 SAFETY END TREATMENT <400><420><421><432><440><442><445> <460><464>
ITEM 480 CLEANING EXISTING CULVERTS
ITEM 495 RAISING EXISTING STRUCTURES <420><429><442><448>
ITEM 499 ADJUSTING STEEL SHOES <429><442><448>
ITEM 500 MOBILIZATION
ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING <503><505><510>
ITEM 503 PORTABLE CHANGEABLE MESSAGE SIGN
ITEM 505 TRUCK-MOUNTED ATTENUATOR (TMA) AND TRAILER ATTENUATOR (TA)
ITEM 506 TEMPORARY EROSION, SEDIMENTATION, AND ENVIRONMENTAL CONTROLS <161><432><556>
ITEM 658 DELINEATOR AND OBJECT MARKER ASSEMBLIES <445>
ITEM 735 DEBRIS REMOVAL <734><738>
ITEM 752 TREE AND BRUSH REMOVAL
ITEM 776 METAL RAIL REPAIR <429><441><445><446><448><450>
ITEM 778 CONCRETE RAIL REPAIR <427><429><450><776>
ITEM 780 CONCRETE CRACK REPAIR

SPECIAL PROVISIONS: SPECIAL PROVISIONS WILL GOVERN AND TAKE
---------- PRECEDENCE OVER THE SPECIFICATIONS ENUMERATED
HEREON WHEREVER IN CONFLICT THEREWITH.

SPECIAL LABOR PROVISIONS FOR STATE PROJECTS (000---005)
WAGE RATES
SPECIAL PROVISION "NONDISCRIMINATION" (000---001)
SPECIAL PROVISION "NOTICE OF CONTRACTOR PERFORMANCE EVALUATIONS"
(000---016)
SPECIAL PROVISION "CERTIFICATE OF INTERESTED PARTIES (FORM 1295)"
(000---017)
SPECIAL PROVISION "IMPORTANT NOTICE TO CONTRACTORS" (000---018)
SPECIAL PROVISION "SMALL BUSINESS ENTERPRISE IN STATEFUNDED PROJECTS"
(000---019)

SPECIAL SPECIFICATIONS:

ITEM 4010 STEEL BRIDGE ZONE PAINTING

GENERAL: THE ABOVE-LISTED SPECIFICATION ITEMS ARE THOSE UNDER WHICH
------- PAYMENT IS TO BE MADE. THESE, TOGETHER WITH SUCH OTHER
PERTINENT ITEMS, IF ANY, AS MAY BE REFERRED TO IN THE ABOVE-
LISTED SPECIFICATION ITEMS, AND INCLUDING THE SPECIAL
PROVISIONS LISTED ABOVE, CONSTITUTE THE COMPLETE SPECIFI-
CATIONS FOR THIS PROJECT.

Control	**0923-00-067**
Project	**C 923-00-67**
Highway	**VA**
County	**BROWN**

SMALL BUSINESS ENTERPRISE REQUIREMENTS

The following goal for small business enterprises is established:

SBE
0.0%

CHILD SUPPORT STATEMENT

Under Section 231.006, Family Code, the vendor or applicant certifies that the individual or business entity named in this contract, bid, or application is not ineligible to receive the specified grant, loan, or payment and acknowledges that this contract may be terminated and payment may be withheld if this certification is inaccurate.

CONFLICT OF INTEREST CERTIFICATION

Pursuant to Texas Government Code Section 2261.252(b), the Department is prohibited from entering into contracts in which Department officers and employees have a financial interest.

By signing the Contract, the Contractor certifies that it is not prohibited from entering into a Contract with the Department as a result of a financial interest as defined under Texas Government Code Section 2261.252(b), and that it will exercise reasonable care and diligence to prevent any actions or conditions that could result in a conflict of interest with the Department.

The Contractor also certifies that none of the following individuals, nor any of their family members within the second degree of affinity or consanguinity, owns 1% or more interest or has a financial interest as defined under Texas Government Code Section 2261.252(b) in the Contractor:

- Any member of the Texas Transportation Commission; and
- The Department's Executive Director, General Counsel, Chief of Procurement and Field Support Operations, Director of Procurement, and Director of Contract Services.

Violation of this certification may result in action by the Department.

E-VERIFY CERTIFICATION

Pursuant to Texas Transportation Code §223.051, all TxDOT contracts for construction, maintenance, or improvement of a highway must include a provision requiring Contractors and subcontractors to use the U.S. Department of Homeland Security's E-Verify system to determine employment eligibility. By signing the contract, the Contractor certifies that prior to the award of the Contract:

- the Contractor has registered with and will, to the extent permitted by law, utilize the United States Department of Homeland Security's E-Verify system during the term of the Contract to determine the eligibility of all persons hired to perform duties within Texas during the term of the agreement; and
- the Contractor will require that all subcontractors also register with and, to the extent permitted by law, utilize the United States Department of Homeland Security's E-Verify system during the term of the subcontract to determine the eligibility of all persons hired to perform duties within Texas during the term of the agreement.

Violation of this requirement constitutes a material breach of the Contract, subjects a subcontractor to removal from the Contract, and subjects the Contractor or subcontractors to possible sanctions in accordance with Title 43, Texas Administrative Code, Chapter 10, Subchapter F, "Sanctions and Suspension for Ethical Violations by Entities Doing Business with the Department."

Certification Regarding Disclosure of Public Information

Pursuant to Subchapter J, Chapter 552, Texas Government Code, contractors executing a contract with a governmental body that results in the expenditure of at least $1 million in public funds must:

1) preserve all contracting information* as provided by the records retention requirements applicable to Texas Department of Transportation (TxDOT) for the duration of the contract,
2) on request of TxDOT, promptly provide any contracting information related to the contract that is in the custody or possession of the entity, and
3) on completion of the contract, either:
    A. provide, at no cost to TxDOT, all contracting information related to the contract that is in the custody or possession of the entity, or
    B. preserve the contracting information related to the contract as provided by the records retention requirements applicable to TxDOT

The requirements of Subchapter J, Chapter 552, Government Code, may apply to this contract, and the contractor or vendor agrees that the contract can be terminated if the contractor or vendor knowingly or intentionally fails to comply with a requirement of that subchapter.

By entering into Contract, the Contractor agrees to:

- provide, or make available, to TxDOT and any authorized governmental investigating or auditing agency all records, including electronic and payment records related to the contract, for the same period provided by the records retention schedule applicable to TxDOT, and
- ensure that all subcontracts include a clause requiring the same.

* As defined in Government Code §552.003, "Contracting information" means the following information maintained by a governmental body or sent between a governmental body and a vendor, contractor, potential vendor, or potential contractor:

1) information in a voucher or contract relating to the receipt or expenditure of public funds by a governmental body;
2) solicitation or bid documents relating to a contract with a governmental body;
3) communications sent between a governmental body and a vendor, contractor, potential vendor, or potential contractor during the solicitation, evaluation, or negotiation of a contract;
4) documents, including bid tabulations, showing the criteria by which a governmental body evaluates each vendor, contractor, potential vendor, or potential contractor responding to a solicitation and, if applicable, an explanation of why the vendor or contractor was selected; and
5) communications and other information sent between a governmental body and a vendor or contractor related to the performance of a final contract with the governmental body or work performed on behalf of the governmental body.

CERTIFICATION TO NOT BOYCOTT ISRAEL

Pursuant to Texas Government Code §2271.002, the Department must include a provision requiring a written verification affirming that the Contractor does not boycott Israel, as defined in Government Code §808.001, and will not boycott Israel during the term of the contract. This provision applies to a contract that:

1) is with a Contractor that is not a sole proprietorship,
2) is with a Contractor with 10 or more full-time employees, and
3) has a value of $100,000 or more.

By signing the contract, the Contractor certifies that it does not boycott Israel and will not boycott Israel during the term of this contract. “Boycott” means refusing to deal with, terminating business activities with, or otherwise taking any action that is intended to penalize, inflict economic harm on, or limit commercial relations specifically with Israel, or with a person or entity doing business in Israel or in an Israeli-controlled territory, but does not include an action made for ordinary business purposes.

Violation of this certification may result in action by the Department.

CERTIFICATION TO NOT BOYCOTT ENERGY COMPANIES

Pursuant to Texas Government Code §2274.002, the Department must include a provision requiring a written verification affirming that the Contractor does not boycott energy companies, as defined in Government Code §809.001, and will not boycott energy companies during the term of the contract. This provision applies to a contract that:

1) is with a Contractor that is not a sole proprietorship,
2) is with a Contractor with 10 or more full-time employees, and
3) has a value of $100,000 or more.

By signing the contract, the Contractor certifies that it does not boycott energy companies and will not boycott energy companies during the term of this contract. “Boycott” means taking any action that is intended to penalize, inflict economic harm on, or limit commercial relations with a company because the company: (1) engages in the exploration, production, utilization, transportation, sale, or manufacturing of fossil fuel-based energy and does not commit or pledge to meet environmental standards beyond applicable federal and state law; or (2) does business with a company described by (1).

Violation of this certification may result in action by the Department.

CERTIFICATION TO NOT DISCRIMINATE AGAINST FIREARM ENTITIES OR FIREARM TRADE ASSOCIATIONS

Pursuant to Texas Government Code §2274.002, the Department must include a provision requiring a written verification affirming that the Contractor:

1) does not have a practice, policy, guidance, or directive that discriminates against a firearm entity or firearm trade association, as defined in Government Code §2274.001, and
2) will not discriminate against a firearm entity or firearm trade association during the term of the contract.

This provision applies to a contract that:

1) is with a Contractor that is not a sole proprietorship,
2) is with a Contractor with 10 or more full-time employees, and
3) has a value of $100,000 or more.

By signing the contract, the Contractor certifies that it does not discriminate against a firearm entity or firearm trade association as described and will not do so during the term of this contract. "Discriminate against a firearm entity or firearm trade association" means, with respect to the entity or association, to: (1) refuse to engage in the trade of any goods or services with the entity or association based solely on its status as a firearm entity or firearm trade association; (2) refrain from continuing an existing business relationship with the entity or association based solely on its status as a firearm entity or firearm trade association; or (3) terminate an existing business relationship with the entity or association based solely on its status as a firearm entity or firearm trade association. "Discriminate against a firearm entity or firearm trade association" does not include: (1) the established policies of a merchant, retail seller, or platform that restrict or prohibit the listing or selling of ammunition, firearms, or firearm accessories; (2) a company's refusal to engage in the trade of any goods or services, decision to refrain from continuing an existing business relationship, or decision to terminate an existing business relationship to comply with federal, state, or local law, policy, or regulations or a directive by a regulatory agency, or for any traditional business reason that is specific to the customer or potential customer and not based solely on an entity 's or association's status as a firearm entity or firearm trade association.

Violation of this certification may result in action by the Department.

PROHIBITION ON CERTAIN TELECOMMUNICATIONS EQUIPMENT OR SERVICES

The Federal Register Notice issued the Final Rule and states that the amendment to 2 CFR 200.216 is effective on August 13, 2020. The new 2 CFR 200.471 regulation provides clarity that the telecommunications and video surveillance costs associated with 2 CFR 200.216 are unallowable for services and equipment from these specific providers. OMB's Federal Register Notice includes the new 2 CFR 200.216 and 2 CFR 200.471 regulations.

https://www.federalregister.gov/documents/2020/08/13/2020-17468/guidance-for-grants-and-agreements

Per the Federal Law referenced above, use of services, systems, or services or systems that contain components produced by any of the following manufacturers is strictly prohibited for use on this project. Therefore, for any telecommunications, CCTV, or video surveillance equipment, services or systems cannot be manufactured by, or have components manufactured by:

- Huawei Technologies Company,
- ZTE Corporation (any subsidiary and affiliate of such entities),
- Hyatera Communications Corporation,
- Hangzhou Hikvision Digital Technology Company,
- Dahua Technology Company (any subsidiary and affiliate of such entities).

Violation of this prohibition will require replacement of the equipment at the contractor's expense.

Special Provision to Item 000
Special Labor Provisions for State Projects

1. GENERAL

This is a "Public Works" Project, as provided under Government Code, Chapter 2258, "Prevailing Wage Rates," and is subject to the provisions of the statute. No provisions in the Contract are intended to conflict with the provisions of the statute.

The Commission has ascertained and indicated in the Special Provisions the regular rate of per diem wages prevailing in each locality for each craft or type of worker. Apply the wage rates contained in the Specifications as minimum wage rates for the Contract.

2. MINIMUM WAGES, HOURS, AND CONDITIONS OF EMPLOYMENT

All workers necessary for the satisfactory completion of the work are within the purview of the Contract.

Whenever and wherever practical, give local citizens preference in the selection of labor.

Do not require any worker to lodge, board, or trade at a particular place, or with a particular person, as a condition of employment.

Do not charge or accept a fee of any from any person who obtains work on the project. Do not require any person who obtains work on the project to pay any fee to any other person or agency obtaining employment for the person on the project.

Do not charge for tools or equipment used in connection with the duties performed, except for loss or damage of property. Do not charge for necessary camp water.

Do not charge for any transportation furnished to any person employed on the project.

The provisions apply where work is performed by piece work and station work. The minimum wage paid will be exclusive of equipment rental on any shipment that the worker or subcontractor may furnish in connection with their work.

Take responsibility for carrying out the requirements of this Specification and ensure that each subcontractor working on the project complies with its provisions.

Any form of subterfuge, coercion, or deduction designated to evade, reduce, or discount the established minimum wage scales will be considered a violation of the Contract.

The Fair Labor Standards Act established one and one-half (1-1/2) pay for overtime in excess of 40 hr. worked in 1 week. Do not consider time consumed by the worker in going to and returning from the place of work as part of the hours of work. Do not require or permit any worker to work more than 40 hr. in 1 week, unless the worker receives compensation at a rate not less than 1-1/2 times the basic rate of pay for all hours worked in excess of 40 hr. in the workweek.

The general rates of per diem wages prevailing in this locality for each class and type of workers whose services are considered necessary to fulfill the Contract are indicated in the Special Provisions, and these rates govern as minimum wage rates on this Contract. A penalty of $60 per calendar day or portion of a calendar day for each worker who is paid less than the stipulated general rates of per diem wages for any work done under the Contract will be deducted. The Department, upon receipt of a complaint by a worker,

will determine within 30 days whether good cause exists to believe that the Contractor or a subcontractor has violated wage rate requirements and notify the parties involved of the findings. Make every effort to resolve the alleged violation within 14 days after notification. The next alternative is submittal to binding arbitration in accordance with the provisions of the Texas General Arbitration Act (Article 224 et seq., "Revised Statutes").

Notwithstanding any other provision of the Contract, covenant and agree that the Contractor and its subcontractors will pay each of their employees and contract labor engaged in any way in work under the Contract, a wage not less than what is generally known as the "federal minimum wage" in accordance with 29 USC § 206 as that statute may be amended from time to time.

Pay any worker employed whose position is not listed in the Contract, a wage not less than the per diem wage rate established in the Contract for a worker whose duties are most nearly comparable.

3. RECORD AND INSPECTIONS

Keep copies of weekly payrolls for review. Require subcontractors to keep copies of weekly payrolls for review. Show the name, occupation, number of hours worked each day, and per diem wage paid each worker together with a complete record of all deductions made from such wages. Keep records for a period of 3 yr. from the date of completion of the Contract.

Where the piece-work method is used, indicate on the payroll for each person involved:

- quantity of piece work performed,
- price paid per piece-work unit, and
- total hours employed.

The Engineer may require the Contractor to file an affidavit for each payroll certifying that payroll is a true and accurate report of the full wages due and paid to each person employed.

Post or make available to employees the prevailing wage rates from the Contract. Require subcontractors to post or make available to employees the prevailing wage rates from the Contract.

The wage rates listed herein are those predetermined by the Secretary of Labor and State Statue and listed in the United States Department of Labor's (USDOL) General Decisions dated 01-05-2024 and are the minimum wages to be paid accordingly for each specified classification. To determine the applicable wage rate zone, a list entitled "TEXAS COUNTIES IDENTIFIED BY WAGE RATE ZONES" is provided in the contract. Any wage rate that is not listed herein and not in the USDOL's general decision, must be requested by the contractor through the completion of an Additional Classification and Wage Rate Request and be submitted for approval. IMPORTANT NOTICE FOR STATE PROJECTS: only the controlling wage rate zone applies to the contract. Effective 01-05-2024.

CLASS. #	CLASSIFICATION DESCRIPTION	ZONE TX02 *(TX20240002)	ZONE TX03 *(TX20240003)	ZONE TX04 *(TX20240004)	ZONE TX05 *(TX20240005)	ZONE TX06 *(TX20240006)	ZONE TX07 *(TX20240007)	ZONE TX08 *(TX20240008)	ZONE TX24 *(TX20240024)	ZONE TX25 *(TX20240025)	ZONE TX27 *(TX20240027)	ZONE TX28 *(TX20240028)	ZONE TX29 *(TX20240029)	ZONE TX30 *(TX20240030)	ZONE TX37 *(TX20240037)	ZONE TX38 *(TX20240038)	ZONE TX42 *(TX20240042)
1428	Agricultural Tractor Operator						$12.69					$12.35			$11.75		
1300	Asphalt Distributor Operator	$14.87	$13.48	$13.88	$15.72	$15.58	$15.55	$15.72	$13.28	$15.32	$15.62	$14.36	$14.25	$14.03	$13.75	$14.06	$14.40
1303	Asphalt Paving Machine Operator	$13.40	$12.25	$12.35	$13.87	$14.05	$14.36	$14.20	$13.26	$13.99	$14.68	$12.92	$13.44	$12.53	$14.00	$14.32	$12.99
1106	Asphalt Raker	$12.28	$10.61	$12.02	$14.21	$11.65	$12.12	$11.64	$11.44	$12.69	$12.05	$11.34	$11.67	$11.40	$12.59	$12.36	$11.78
1112	Batching Plant Operator, Asphalt																
1115	Batching Plant Operator, Concrete																
1214	Blaster																
1615	Boom Truck Operator						$18.36										
1444	Boring Machine Operator																
1305	Broom or Sweeper Operator	$11.21	$10.33	$10.08	$11.99		$11.04	$11.62		$11.74	$11.41	$10.30		$10.23	$10.60	$12.68	$11.05
1144	Communications Cable Installer																
1124	Concrete Finisher, Paving and Structures	$13.55	$12.46	$13.16	$12.85	$12.64	$12.56	$12.77	$12.44	$14.12	$13.04	$13.38	$12.64	$12.80	$12.79	$12.98	$13.32
1318	Concrete Pavement Finishing Machine Operator				$16.05		$15.48			$16.05		$19.31				$13.07	
1315	Concrete Paving, Curing, Float, Texturing Machine Operator											$16.34				$11.71	
1333	Concrete Saw Operator				$14.67					$14.48	$17.33					$13.99	
1399	Concrete/Gunite Pump Operator																
1344	Crane Operator, Hydraulic 80 tons or less				$18.22		$18.36			$18.12	$18.04	$20.21			$18.63	$13.86	
1345	Crane Operator, Hydraulic Over 80 Tons																
1342	Crane Operator, Lattice Boom 80 Tons or Less	$16.82	$14.39	$13.85	$17.27		$15.87			$17.27		$14.67			$16.42	$14.97	$13.87
1343	Crane Operator, Lattice Boom Over 80 Tons				$20.52		$19.38			$20.52		$17.49			$25.13	$15.80	
1306	Crawler Tractor Operator	$13.96	$16.63	$13.62	$14.26		$15.67			$14.07	$13.15	$13.38			$14.60	$13.68	$13.50
1351	Crusher or Screen Plant Operator																
1446	Directional Drilling Locator						$11.67										
1445	Directional Drilling Operator				$20.32		$17.24										
1139	Electrician	$20.96		$19.87	$19.80		$26.35		$20.27	$19.80		$20.92				$27.11	$19.87
1347	Excavator Operator, 50,000 pounds or less	$13.46	$12.56	$13.67	$17.19		$12.88	$14.38	$13.49	$17.19		$13.88			$14.09	$12.71	$14.42
1348	Excavator Operator, Over 50,000 pounds		$15.23	$13.52	$17.04		$17.71			$16.99	$18.80	$16.22				$14.53	$13.52
1150	Flagger	$9.30	$9.10	$8.50	$10.28	$8.81	$9.45	$8.70		$10.06	$9.71	$9.03	$8.81	$9.08	$9.90	$10.33	$8.10
1151	Form Builder/Setter, Structures	$13.52	$12.30	$13.38	$12.91	$12.71	$12.87	$12.38	$12.26	$13.84	$12.98	$13.07	$13.61	$12.82	$14.73	$12.23	$12.25
1160	Form Setter, Paving & Curb	$12.36	$12.16	$13.93	$11.83	$10.71	$12.94			$13.16	$12.54	$11.33	$10.69		$13.33	$12.34	$13.93
1360	Foundation Drill Operator, Crawler Mounted				$17.99					$17.99						$17.43	
1363	Foundation Drill Operator, Truck Mounted		$16.86	$22.05	$21.51		$16.93			$21.07	$20.20	$20.76		$17.54	$21.39	$15.89	$22.05
1369	Front End Loader Operator, 3 CY or Less	$12.28	$13.49	$13.40	$13.85		$13.04	$13.15	$13.29	$13.69	$12.64	$12.89			$13.51	$13.32	$12.17
1372	Front End Loader Operator, Over 3 CY	$12.77	$13.69	$12.33	$14.96		$13.21	$12.86	$13.57	$14.72	$13.75	$12.32			$13.19	$13.17	$13.02
1329	Joint Sealer																
1172	Laborer, Common	$10.30	$9.86	$10.08	$10.51	$10.71	$10.50	$10.24	$10.58	$10.72	$10.45	$10.30	$10.25	$10.03	$10.54	$11.02	$10.15
1175	Laborer, Utility	$11.80	$11.53	$12.70	$12.17	$11.81	$12.27	$12.11	$11.33	$12.32	$11.80	$11.53	$11.23	$11.50	$11.95	$11.73	$12.37
1346	Loader/Backhoe Operator	$14.18	$12.77	$12.97	$15.68		$14.12			$15.18	$13.58	$12.87		$13.21	$14.13	$14.29	$12.90
1187	Mechanic	$20.14	$15.47	$17.47	$17.74	$17.00	$17.10			$17.68	$18.94	$18.58	$17.00	$16.61	$18.46	$16.96	$17.47

CLASS. #	CLASSIFICATION DESCRIPTION	ZONE TX02 *(TX20240002)	ZONE TX03 *(TX20240003)	ZONE TX04 *(TX20240004)	ZONE TX05 *(TX20240005)	ZONE TX06 *(TX20240006)	ZONE TX07 *(TX20240007)	ZONE TX08 *(TX20240008)	ZONE TX24 *(TX20240024)	ZONE TX25 *(TX20240025)	ZONE TX27 *(TX20240027)	ZONE TX28 *(TX20240028)	ZONE TX29 *(TX20240029)	ZONE TX30 *(TX20240030)	ZONE TX37 *(TX20240037)	ZONE TX38 *(TX20240038)	ZONE TX42 *(TX20240042)
1380	Milling Machine Operator	$15.54	$14.64	$12.22	$14.29		$14.18			$14.32	$14.35	$12.86			$14.75	$13.53	$12.80
1390	Motor Grader Operator, Fine Grade	$17.49	$16.52	$16.88	$17.12	$18.37	$18.51	$16.69	$16.13	$17.19	$18.35	$17.07	$17.74	$17.47	$17.08	$15.69	$20.01
1393	Motor Grader Operator, Rough	$16.15	$14.62	$15.83	$16.20	$17.07	$14.63	$18.50		$16.02	$16.44	$15.12	$16.85	$14.47	$17.39	$14.23	$15.53
1413	Off Road Hauler			$10.08	$12.26		$11.88			$12.25		$12.23			$13.00	$14.60	
1196	Painter, Structures					$21.29	$18.34						$21.29			$18.62	
1396	Pavement Marking Machine Operator	$16.42		$13.10	$13.55		$19.17	$12.01		$13.63	$14.60	$13.17		$16.65	$10.54	$11.18	$13.10
1443	Percussion or Rotary Drill Operator																
1202	Piledriver															$14.95	
1205	Pipelayer		$11.87	$14.64	$13.17	$11.17	$12.79		$11.37	$13.24	$12.66	$13.24	$11.17	$11.67		$12.12	$14.64
1384	Reclaimer/Pulverizer Operator	$12.85			$11.90		$12.88			$11.01		$10.46					
1500	Reinforcing Steel Worker	$13.50	$14.07	$17.53	$16.17		$14.00			$16.18	$12.74	$15.83		$17.10		$15.15	$17.72
1402	Roller Operator, Asphalt	$10.95		$11.96	$13.29		$12.78	$11.61		$13.08	$12.36	$11.68			$11.71	$11.95	$11.50
1405	Roller Operator, Other	$10.36		$10.44	$11.82		$10.50	$11.64		$11.51	$10.59	$10.30		$12.04	$12.85	$11.57	$10.66
1411	Scraper Operator	$10.61	$11.07	$10.85	$12.88		$12.27		$11.12	$12.96	$11.88	$12.43		$11.22	$13.95	$13.47	$10.89
1417	Self-Propelled Hammer Operator																
1194	Servicer	$13.98	$12.34	$14.11	$14.74		$14.51	$15.56	$13.44	$14.58	$14.31	$13.83		$12.43	$13.72	$13.97	$14.11
1513	Sign Erector																
1708	Slurry Seal or Micro-Surfacing Machine Operator																
1341	Small Slipform Machine Operator									$15.96							
1515	Spreader Box Operator	$12.60		$13.12	$14.71		$14.04			$14.73	$13.84	$13.68		$13.45	$11.83	$13.58	$14.05
1705	Structural Steel Welder															$12.85	
1509	Structural Steel Worker						$19.29									$14.39	
1339	Subgrade Trimmer																
1143	Telecommunication Technician																
1145	Traffic Signal/Light Pole Worker						$16.00										
1440	Trenching Machine Operator, Heavy						$18.48										
1437	Trenching Machine Operator, Light																
1609	Truck Driver Lowboy-Float	$14.46	$13.63	$13.41	$15.00	$15.93	$15.66			$16.24	$16.39	$14.30	$16.62	$15.63	$14.28	$16.03	$13.41
1612	Truck Driver Transit-Mix				$14.14					$14.14							
1600	Truck Driver, Single Axle	$12.74	$10.82	$10.75	$13.04	$11.61	$11.79	$13.53	$13.16	$12.31	$13.40	$10.30	$11.61		$11.97	$11.46	$10.75
1606	Truck Driver, Single or Tandem Axle Dump Truck	$11.33	$14.53	$11.95	$12.95		$11.68		$14.06	$12.62	$11.45	$12.28		$13.08	$11.68	$11.48	$11.10
1607	Truck Driver, Tandem Axle Tractor withSemi Trailer	$12.49	$12.12	$12.50	$13.42		$12.81	$13.16		$12.86	$16.22	$12.50			$13.80	$12.27	$12.50
1441	Tunneling Machine Operator, Heavy																
1442	Tunneling Machine Operator, Light																
1706	Welder		$14.02		$14.86		$15.97		$13.74	$14.84					$13.78		
1520	Work Zone Barricade Servicer	$10.30	$12.88	$11.46	$11.70	$11.57	$11.85	$10.77		$11.68	$12.20	$11.22	$11.51	$12.96	$10.54	$11.67	$11.76

Notes:

*Represents the USDOL wage decision.

Any worker employed on this project shall be paid at the rate of one and one half (1-1/2) times the regular rate for every hour worked in excess of forty (40) hours per week.

For reference, the titles and descriptions for the classifications listed here are detailed further in the AGC of Texas' *Standard Job Classifications and Descriptions for Highway, Heavy, Utilities, and Industrial Construction in Texas* posted on the AGC's Web site for any contractor.

TEXAS COUNTIES IDENTIFIED BY
WAGE RATE ZONES: 2, 3, 4, 5, 6, 7, 8, 24, 25, 27, 28, 29, 30, 37, 38, 42

County Name	Zone	County Name	Zone	County Name	Zone	County Name	Zone
Anderson	28	Donley	37	Karnes	27	Reagan	37
Andrews	37	Duval	30	Kaufman	25	Real	37
Angelina	28	Eastland	37	Kendall	7	Red River	28
Aransas	29	Ector	2	Kenedy	30	Reeves	8
Archer	25	Edwards	8	Kent	37	Refugio	27
Armstrong	2	El Paso	24	Kerr	27	Roberts	37
Atascosa	7	Ellis	25	Kimble	37	Robertson	7
Austin	38	Erath	28	King	37	Rockwall	25
Bailey	37	Falls	28	Kinney	8	Runnels	37
Bandera	7	Fannin	28	Kleberg	27	Rusk	4
Bastrop	7	Fayette	27	Knox	37	Sabine	28
Baylor	37	Fisher	37	Lamar	28	San Augustine	28
Bee	27	Floyd	37	Lamb	37	San Jacinto	38
Bell	7	Foard	37	Lampasas	7	San Patricio	29
Bexar	7	Fort Bend	38	LaSalle	30	San Saba	37
Blanco	27	Franklin	28	Lavaca	27	Schleicher	37
Borden	37	Freestone	28	Lee	27	Scurry	37
Bosque	28	Frio	27	Leon	28	Shackelford	37
Bowie	4	Gaines	37	Liberty	38	Shelby	28
Brazoria	38	Galveston	38	Limestone	28	Sherman	37
Brazos	7	Garza	37	Lipscomb	37	Smith	4
Brewster	8	Gillespie	27	Live Oak	27	Somervell	28
Briscoe	37	Glasscock	37	Llano	27	Starr	30
Brooks	30	Goliad	29	Loving	37	Stephens	37
Brown	37	Gonzales	27	Lubbock	2	Sterling	37
Burleson	7	Gray	37	Lynn	37	Stonewall	37
Burnet	27	Grayson	25	Madison	28	Sutton	8
Caldwell	7	Gregg	4	Marion	28	Swisher	37
Calhoun	29	Grimes	28	Martin	37	Tarrant	25
Callahan	25	Guadalupe	7	Mason	27	Taylor	2
Cameron	3	Hale	37	Matagorda	27	Terrell	8
Camp	28	Hall	37	Maverick	30	Terry	37
Carson	2	Hamilton	28	McCulloch	37	Throckmorton	37
Cass	28	Hansford	37	McLennan	7	Titus	28
Castro	37	Hardeman	37	McMullen	30	Tom Green	2
Chambers	38	Hardin	38	Medina	7	Travis	7
Cherokee	28	Harris	38	Menard	37	Trinity	28
Childress	37	Harrison	42	Midland	2	Tyler	28
Clay	25	Hartley	37	Milam	28	Upshur	4
Cochran	37	Haskell	37	Mills	37	Upton	37
Coke	37	Hays	7	Mitchell	37	Uvalde	30
Coleman	37	Hemphill	37	Montague	37	Val Verde	8
Collin	25	Henderson	28	Montgomery	38	Van Zandt	28
Collingsworth	37	Hidalgo	3	Moore	37	Victoria	6
Colorado	27	Hill	28	Morris	28	Walker	28
Comal	7	Hockley	37	Motley	37	Waller	38
Comanche	37	Hood	28	Nacogdoches	28	Ward	37
Concho	37	Hopkins	28	Navarro	28	Washington	28
Cooke	37	Houston	28	Newton	28	Webb	3
Coryell	7	Howard	37	Nolan	37	Wharton	27
Cottle	37	Hudspeth	8	Nueces	29	Wheeler	37
Crane	37	Hunt	25	Ochiltree	37	Wichita	5
Crockett	8	Hutchinson	37	Oldham	37	Wilbarger	37
Crosby	2	Irion	2	Orange	38	Willacy	30
Culberson	8	Jack	28	Palo Pinto	28	Williamson	7
Dallam	37	Jackson	27	Panola	28	Wilson	7
Dallas	25	Jasper	28	Parker	25	Winkler	37
Dawson	37	Jeff Davis	8	Parmer	37	Wise	25
Deaf Smith	37	Jefferson	38	Pecos	8	Wood	28
Delta	25	Jim Hogg	30	Polk	28	Yoakum	37
Denton	25	Jim Wells	27	Potter	2	Young	37
DeWitt	27	Johnson	25	Presidio	8	Zapata	30
Dickens	37	Jones	25	Rains	28	Zavala	30
Dimmit	30			Randall	2		

01/05/2024

Special Provision to Item 000
Nondiscrimination

1. DESCRIPTION

All recipients of federal financial assistance are required to comply with various nondiscrimination laws, including Title VI of the Civil Rights Act of 1964, as amended (Title VI). Title VI forbids discrimination against anyone in the United States on the grounds of race, color, or national origin by any agency receiving federal funds.

The Texas Department of Transportation, as a recipient of federal financial assistance, and under Title VI and related statutes, ensures that no person will on the grounds of race, religion (where the primary objective of the financial assistance is to provide employment in accordance with 42 USC 2000d-3), color, national origin, sex, age, or disability be excluded from participation in, be denied the benefits of, or otherwise be subjected to discrimination under any Department programs or activities.

2. DEFINITION OF TERMS

Where the term "Contractor" appears in the following six nondiscrimination clauses, the term "Contractor" is understood to include all parties to Contracts or agreements with the Department.

3. NONDISCRIMINATION PROVISIONS

During the performance of this Contract, the Contractor agrees as follows.

3.1. **Compliance with Regulations**. The Contractor must comply with the Regulations pertinent to nondiscrimination in federally assisted programs of the United States Department of Transportation 49 CFR 21, as they may be amended from time to time, (hereinafter referred to as the Regulations), which are herein incorporated by reference and made a part of this Contract.

3.2. **Nondiscrimination**. The Contractor, regarding the work performed during the Contract, must not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The Contractor must not participate either directly or indirectly in the discrimination prohibited by Section 21.5 of the Regulations, including employment practices when the Contract covers a program set forth in Appendix B of the Regulations.

3.3. **Solicitations for Subcontracts, Including Procurements of Materials and Equipment**. In all solicitations either by competitive bidding or negotiation made by the Contractor for work to be performed under a subcontract, including procurements of materials or leases of equipment, the Contractor must notify each potential subcontractor or supplier of the Contractor's obligations under this Contract and the Regulations relative to nondiscrimination on the grounds of race, color, or national origin.

3.4. **Information and Reports**. The Contractor must provide all information and reports required by the Regulations or directives issued pursuant thereto, and must permit access to its books, records, accounts, other sources of information, and facilities as may be determined by the Recipient or the Department to be pertinent to ascertain compliance with such Regulations, orders, and instructions. Where any information required of a Contractor is in the exclusive possession of another who fails or refuses to furnish this information, the Contractor must so certify to the Recipient, or the Department as appropriate, and must set forth what efforts it has made to obtain the information.

3.5. **Sanctions for Noncompliance**. In the event of the Contractor's noncompliance with the nondiscrimination provisions of this Contract, the Recipient must impose such Contract sanctions as it or the Department may

determine to be appropriate, including, but not limited to actions defined in Article 7.1., “Ethics,” or Article 5.1., “Authority of Engineer.”

3.6. **Incorporation of Provisions**. The Contractor must include the provisions of Sections 3.1–3.6 in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Regulations or directives issued pursuant thereto. The Contractor must take such action with respect to any subcontract or procurement as the Recipient or the Department may direct as a means of enforcing such provisions, including sanctions for noncompliance: Provided, however, that, in the event a Contractor becomes involved in, or is threatened with, litigation with a subcontractor or supplier as a result of such direction, the Contractor may request the Recipient to enter into such litigation to protect the interests of the Recipient, and, in addition, the Contractor may request the United States to enter into such litigation to protect the interests of the United States.

Special Provision 000
Important Notice to Contractors

1. GENERAL

In accordance with Texas Transportation Code §223.012, the Engineer will evaluate Contractor performance based on quality, safety, and timeliness of the project.

2. DEFINISIONS

2.1. **Project Recovery Plan (PRP)**. A formal, enforceable plan developed by the Contractor, in consultation with the District, that documents the cause of noted quality, safety, and timeliness issues and specifies how the Contractor proposes to correct project-specific performance deficiencies.

In accordance with 43 TAC §9.23, the District will request a PRP if the Contractor's performance on a project is below the Department's acceptable standards and will monitor the Contractor's compliance with the established plan.

2.2. **Corrective Action Plan (CAP)**. A formal, enforceable plan developed by the Contractor, and proposed for adoption by the Construction Division or Maintenance Division, that documents the cause of noted quality, safety, and timeliness issues and specifies how the Contractor proposes to correct statewide performance deficiencies.

3. CONTRACTOR EVALUATIONS

In accordance with 43 TAC §9.23, the Engineer will schedule evaluations at the following intervals, at minimum:

- interim evaluations at or within 30 days after the anniversary of the Notice to Proceed, for Contracts extending beyond 1 yr. and
- final evaluation, upon project closeout.

In case of a takeover agreement, neither the Surety nor its performing Contractor will be evaluated.

In addition to regularly scheduled evaluations, the Engineer may schedule an interim evaluation at any time to formally communicate issues with quality, safety, or timeliness. Upon request, work with the Engineer to develop a PRP to document expectations for correcting deficiencies.

Comply with the PRP as directed. Failure to comply with the PRP may result in additional remedial actions available to the Engineer under Item 5, "Control of the Work." Failure to meet a PRP to the Engineer's satisfaction may result in immediate referral to the Performance Review Committee for consideration of further action against the Contractor.

The Engineer will consider and document any events outside the Contractor's control that contributed to the failure to meet performance standards or comply with a PRP, including consideration of sufficient time.

Follow the escalation ladder if there is a disagreement regarding an evaluation or disposition of a PRP. The Contractor may submit additional documentation pertaining to the dispute. The District Engineer's decision on a Contractor's evaluation score and recommendation of action required in a PRP or follow-up for noncompliance is final.

4. DIVISION OVERSIGHT

Upon request of the Construction Division or Maintenance Division, develop and submit for Division approval a proposed CAP to document expectations for correcting deficiencies in the performance of projects statewide.

Comply with the CAP as directed. The CAP may be modified at any time up to completion or resolution after written approval of the premise of change from the Division. Failure to meet an adopted or revised adopted CAP to the Division's satisfaction within 120 days will result in immediate referral to the Performance Review Committee for consideration of further action against the Contractor.

The Division will consider and document any events outside the Contractor's control that contributed to the failure to meet performance standards or comply with a CAP, including consideration of sufficient time and associated costs as appropriate.

5. PERFORMANCE REVIEW COMMITTEE

The Performance Review Committee, in accordance with 43 TAC §9.24, will review at minimum all final evaluations, history of compliance with PRPs, any adopted CAPs including agreed modifications, any information about events outside a Contractor's control contributing to the Contractor's performance, and any documentation submitted by the Contractor and may recommend one or more of the following actions:

- take no action,
- reduce the Contractor's bidding capacity,
- prohibit the Contractor from bidding on one or more projects,
- immediately suspend the Contractor from bidding for a specified period of time, by reducing the Contractor's bidding capacity to zero, or
- prohibit the Contractor from being awarded a Contract on which they are the apparent low bidder.

The Deputy Executive Director will determine any further action against the Contractor.

6. APPEALS PROCESS

In accordance with 43 TAC §9.25, the Contractor may appeal remedial actions determined by the Deputy Executive Director.

Special Provision 000
Certificate of Interested Parties (Form 1295)

Submit Form 1295, "Certificate of Interested Parties," in the following instances:

- at Contract execution for Contracts awarded by the Commission,
- at Contract execution for Contracts awarded by the District Engineer or Chief Engineer with an award amount of $1 million or more,
- at any time an existing Contract awarded by the District Engineer or Chief Engineer increases in value to $1 million or more because of changes in the Contract,
- at any time there is an increase of $1 million or more to an existing Contract (e.g., change orders, extensions, and renewals), and
- at any time there is a change to the information in Form 1295, when the form was filed for an existing Contract.

Form 1295 and instructions for completing and filing the form are available on the Texas Ethics Commission website.

Special Provision 000
Important Notice to Contractors

Table 1
Daily Contract Administration Liquidated Damages

For Dollar Amount of Original Contract		Dollar Amount of Daily Contract Administration Liquidated Damages per Working Day
From More Than	To and Including	
0	1,000,000	618
1,000,000	3,000,000	832
3,000,000	5,000,000	940
5,000,000	15,000,000	1,317
15,000,000	25,000,000	1,718
25,000,000	50,000,000	2,411
50,000,000	Over 50,000,000	4,265

In addition to the amount shown in Table 1, the liquidated damages will be increased by the amount shown in Item 8 of the General Notes for Road User Cost (RUC), when applicable.

Special Provision to Item 000
Small Business Enterprise in State-Funded Projects

1. DESCRIPTION

The purpose of this Special Provision is to implement the Department's policy of ensuring that SBEs have an opportunity to participate in the performance of Contracts. If the SBE goal is greater than zero, Section 2.1., "Article A—SBE Goal is Greater than Zero," will apply to this Contract; otherwise, Section 2.2., "Article B—No SBE Goal," will apply. The percentage goal for SBE participation in the work to be performed under this Contract will be in accordance with the proposal.

2. DEFINITIONS

A Small Business Enterprise (SBE) is a firm certified as such by the Department. Firms certified as Historically Underutilized Businesses (HUBs) by the Texas Comptroller of Public Accounts and as Disadvantaged Business Enterprises (DBEs) by the Texas Uniform Certification Program automatically qualify as SBEs.

2.1. **Article A—SBE Goal is Greater than Zero**.

2.1.1. **Policy**. The Department is committed to providing contracting opportunities for small businesses. Therefore, it is the Department's policy to develop and maintain a program to facilitate contracting opportunities for small businesses. Consequently, the requirements of the Department's SBE Program apply to this Contract as follows.

The Contractor will make a good faith effort to meet the SBE goal for this Contract.

The Contractor and any subcontractors will not discriminate on the basis of race, color, national origin, age, disability, or sex in the award and performance of this Contract. These nondiscrimination requirements must be incorporated into any subcontract and purchase order.

After a conditional award is made to the low Bidder, the Department will determine the adequacy of a Contractor's efforts to meet the Contract goal, in accordance with Section 2.1.2., "Contractor's Responsibilities." If the requirements in accordance with Section 2.1.2., "Contractor's Responsibilities," are met, the Contract will be forwarded to the Contractor for execution.

The Contractor's performance in meeting the SBE goal during the construction period of the Contract will be monitored by the Department.

2.1.2. **Contractor's Responsibilities**. These requirements must be satisfied by the Contractor. An SBE Contractor may satisfy the SBE requirements by performing at least 25% of the Contract work with their own organization in accordance with Item 8, "Prosecution and Progress."

The Contractor must complete an SBE Commitment Agreement Form for each SBE-certified firm the Contractor intends to use to satisfy the SBE goal. The SBE Commitment Agreement Form must be submitted to the Department's Civil Rights Division (CIV) in Austin, Texas, no later than 5 P.M. on the 10th business day, excluding national holidays, after the conditional award of the Contract. When requested, additional time not to exceed 7 business days, excluding national holidays, may be granted based on documentation submitted by the Contractor.

A Contractor that cannot meet the Contract goal, in whole or in part, must document the good faith efforts taken to meet the SBE goal. The Department will consider as good faith efforts all documented explanations

that are submitted and that describe a Contractor's failure to meet an SBE goal or obtain SBE participation, including:

- advertising in general circulation, trade association, and minority- or women-focused media regarding subcontracting opportunities,
- dividing the Contract work into reasonable portions in conformance with standard industry practices,
- documenting reasons for rejection or meeting with the rejected SBE to discuss the rejection,
- providing qualified SBEs with adequate information pertinent to bonding, insurance, plans, Specifications, scope of work, and the requirements of the Contract,
- negotiating in good faith with qualified SBEs, not rejecting qualified SBEs that are also the lowest responsive Bidder; and
- using the services of available minorities and women; community organizations; Contractor groups; local, state, and federal business assistance offices; and other organizations that provide support services to SBEs.

The good faith effort documentation is due at the time and place in accordance with this Section. CIV will evaluate the Contractor's documentation. If it is determined that the Contractor has failed to meet the good faith effort requirements, the Contractor will be given an opportunity for reconsideration by the Department.

Should the Bidder to which the Contract is conditionally awarded refuse, neglect, or fail to meet the SBE goal or demonstrate to the Department's satisfaction sufficient efforts to obtain SBE participation, the proposal guaranty filed with the bid will become the property of the State, not as a penalty, but as liquidated damages.

The Contractor must not terminate an SBE subcontractor submitted on a commitment agreement for a Contract with an assigned goal without the prior written consent of the Department.

The Contractor must designate an SBE contact person who will administer the Contractor's SBE program and who will be responsible for submitting reports, maintaining records, and documenting good faith efforts to use SBEs.

The Contractor must inform the Department of the representative's name, title, and telephone number within 10 days of beginning work.

2.1.3. **Eligibility of SBEs**. The Department certifies the eligibility of SBEs.

Firms certified as SBEs are listed in the Department's online directory located at https://txdot.txdotcms.com/.

Only firms certified at the time of letting or at the time the commitments are submitted are eligible to be used in the information furnished by the Contractor in accordance with Section 2.1.2., "Contractor's Responsibilities."

Certified HUBs and DBEs are eligible as SBEs.

The Department's SBE Program is governed by 43 TAC, Chapter 9, Subchapter K, "Small Business Enterprise (SBE) Program."

2.1.4. **Determination of SBE Participation**. SBE participation will be counted toward meeting the SBE goal in this Contract in accordance with the following.

A Contractor will receive credit for all payments actually made to an SBE for work performed and costs incurred in accordance with the Contract, including all subcontracted work.

An SBE Contractor or subcontractor may not subcontract more than 75% of a Contract. The SBE must perform no less than 25% of the value of the Contract work with their own organization in accordance with Item 8.

An SBE may lease equipment consistent with standard industry practice. An SBE may lease equipment from the prime Contractor if a rental agreement, separate from the subcontract specifying the terms of the lease arrangement, is approved by the Department before the SBE starting the work in accordance with the following.

- If the equipment is of a specialized nature, the lease may include the operator. If the practice is generally acceptable with the industry, the operator may remain on the lessor's payroll. The operator of the equipment must be subject to the full control of the SBE, for a short term, and involve a specialized piece of heavy equipment readily available at the jobsite.
- For equipment that is not specialized, the SBE must provide the operator and be responsible for all payroll and labor compliance requirements.

2.1.5. **Records and Reports**. The Contractor must submit monthly reports of SBE payments (including payments to HUBs and DBEs) to the Area Engineer's Office after work begins. These reports will be due within 15 days after the end of a calendar month.

These reports will be required until all SBE subcontracting or supply activity is completed. The SBE Progress Report must be used for monthly reporting. Upon completion of the Contract and before receiving the final payment, the Contractor must submit the SBE Final Report to the Area Engineer's Office and a copy to the District Construction Office. These forms may be obtained from CIV and reproduced as necessary. The Department may verify the amounts being reported as paid to SBEs by randomly requesting copies of invoices and cancelled checks paid to SBEs. When the SBE goal requirement is not met, documentation supporting good faith efforts, in accordance with Section 2.1.2., "Contractor's Responsibilities," must be submitted with the SBE Final Report.

SBE subcontractors and suppliers should be identified on the monthly report by SBE certification number, name, and the amount of actual payment made to each during the monthly period. These reports are required regardless of whether SBE activity has occurred in the monthly reporting period.

All such records must be retained for 3 yr. following completion of the Contract work and be available at reasonable times and places for inspection by authorized representatives of the Department.

2.1.6. **Compliance of Contractor**. To ensure compliance with SBE requirements of this Contract, the Department will monitor the Contractor's efforts to involve SBEs during the performance of this Contract. This will be accomplished by a review of monthly reports submitted by the Contractor indicating their progress in achieving the SBE Contract goal and by compliance reviews conducted by the Department.

A Contractor's failure to comply with the requirements of this Special Provision will constitute a material breach of this Contract. In such a case, the Department reserves the right to employ remedies as the Department deems appropriate in the terms of the Contract.

2.2. **Article B—No SBE Goal.**

2.2.1. **Policy**. It is the Department's policy that SBEs will have an opportunity to participate in the performance of Contracts.

2.2.2. **Contractor's Responsibilities**. If there is no SBE goal, the Contractor must offer SBEs an opportunity to participate in the performance of Contracts and subcontracts. If an SBE is used, the requirements in accordance with Section 2.1.4., "Determination of SBE Participation," will apply.

2.2.3. **Prohibit Discrimination**. The Contractor and any subcontractor will not discriminate on the basis of race, color, national origin, religion, age, disability, or sex in the award and performance of Contracts. These nondiscrimination requirements must be incorporated into any subcontract and purchase order.

2.2.4. **Records and Reports**. The Contractor must submit annual reports pertinent to SBEs (including HUBs and DBEs) to the Area Engineer's Office by August 31 or at project completion, whichever comes first.

These reports will be required until all SBE subcontracting or supply activity is completed. The SBE Progress Report must be used for reporting. Upon completion of the Contract and before receiving the final payment, the Contractor must submit the SBE Final Report to the Area Engineer's Office and a copy to the District Construction Office. These forms may be obtained from CIV and reproduced as necessary. The Department may verify the amounts being reported as paid to SBEs by randomly requesting copies of invoices and cancelled checks paid to SBEs.

SBE subcontractors and suppliers should be identified on the report by SBE certification cumber, name, and the amount of actual payment made.

All such records must be retained for 3 yr. following completion of the Contract work and be available at reasonable times and places for inspection by authorized representatives of the Department.

Special Specification 4010
Steel Bridge Zone Painting

1. DESCRIPTION

Clean and paint portions of steel members as shown on the plans and as directed.

2. MATERIALS

Provide the paints and paint systems as shown on the plans. The paint must be compatible with existing coating. Use differing colors for each individual coat with enough contrast between colors to distinguish the various steps in the painting process.

2.1. **Paint Systems**. Paint systems for spot and zone painting as specified on the plans.

2.1.1. **System I (Overcoating, One Coat)**. Provide an overcoating system in accordance with DMS-8105, "Paint, One Coat Overcoat," and the manufacturer's specifications.

2.1.2. **System II**. Provide paint in accordance with DMS-8101, "Structural Steel Paints—Performance.

2.2. **System III-A**. Provide paint in accordance with DMS-8101. Provide organic zinc (OZ) prime coat (stripe coat of prime is required), epoxy intermediate stripe coat, epoxy intermediate full coat, and urethane appearance coat.

2.3. **Special Paint Systems**. Provide paint in conformance with the requirements shown on the plans.

2.4. **Water**. Provide potable water for water blasting steel. Water from municipal supplies approved by the Texas Department of Health will not require testing. When water is provided from another source, test for chlorides and provide water with a maximum concentration of 500 parts per million or mg per L.

3. EQUIPMENT

Provide equipment to contain debris, provide access, prepare steel surfaces for paints, and apply paints.

3.1. **Pressure Washer**. Provide high-pressure water blasting equipment to clean steel with minimum-rated blasting pressure of 6,000 psi at a minimum of 4 gpm. Provide a rotary-type nozzle rated for minimum 6,000 psi water pressure.

3.2. **Abrasive Blasting Equipment**. Provide abrasive blasting equipment with a non-recyclable abrasive.

3.3. **Power Hand Tools**. Provide power hand tools equipped with high-efficiency particulate air (HEPA) filter vacuums when shown on the plans.

4. CONSTRUCTION

4.1. **Responsibility for Hazards**. Collect all debris, rust products, and existing coatings.

4.2. **Access**. Provide safe access to all parts of the work for proper inspection.

Remove debris, tree limbs, bushes, grass, and other items that will interfere with the cleaning and painting operations as directed. Remove vertical clearance signs, and erect and maintain temporary ground-mounted

signs matching the content and letter size on the existing sign unless otherwise directed. Re-attach permanent clearance signs as directed.

4.3. **Containment**. Submit a plan that details the procedures and equipment proposed to keep public property, private property, and the environment from being adversely affected by the cleaning and painting operations.

Store, characterize, and dispose of all recovered debris in accordance with 30 TAC 335, "Industrial Solid Waste and Municipal Hazardous Waste." Alternatively, universal waste rules may be used.

Discharge liquids in accordance with the TCEQ Texas Pollution Discharge Elimination Program (30 TAC 305, "Effluent Guidelines and Standards for TPDES Permits") and the Texas Surface Water Quality Standards (30 TAC 307). Alternatively, liquids may be captured, stored, and characterized for disposal at an authorized facility in accordance with 30 TAC 315, "Pretreatment Regulation for Existing and New Sources of Pollution," or 30 TAC 335, "Industrial Solid Waste and Municipal Hazardous Waste."

Use a skimmer when cleaning and painting over bodies of water. Remove any blast or paint material the skimmer collects the day the release occurs. Correct the containment problem that allowed the release before continuing work.

Erect enclosures around areas that will be abrasive blast cleaned with an impermeable bottom to contain all removed material and blast materials.

4.4. **Surface Preparation**. Prepare surfaces to be painted in conformance with the paint manufacturer's specifications and the following. All coating systems require at a minimum general preparation, scraping, vacuuming, and water blasting. For zinc-based primers, the additional step of abrasive blasting is required.

4.4.1. **General Preparation**. Clean far enough into existing paint to ensure removal of all contaminants. Feather edges of sound paint around cleaned areas.

Ensure all surfaces to be painted are completely free of oil, grease, moisture, dirt, sand, welding contamination (slag or acid residue), loose or flaking mill scale, rust, paint, weld spatter, and any other conditions that will prevent the paint from forming a continuous, uniform, and tightly adhering film.

Do not damage adjacent materials, such as concrete, during surface preparation or painting.

Completely remove pack rusts.

Remove all rust and debris under curved surfaces of bearing components by an approved method.

4.4.2. **Scraping**. Use hand scrapers to loosen and remove flaking rust, paint, and debris from surface. Collect all removed debris for disposal. Use chisels or other small scraping devices to prepare surfaces of confined spaces. Follow the adhering paint perimeter with a scraper or putty knife to ensure remaining paint is tightly adhered.

4.4.3. **Abrasive Blast Cleaning**. Abrasive blast steel surfaces to obtain a "near-white" metal appearance. Meet the surface preparation requirements of SSPC-SP 10, unless otherwise shown on the plans. All abrasives must meet SSPC-AB1, AB2, or AB3 as appropriate.

4.4.4. **Vacuuming**. Use a vacuum on scraped surfaces to collect remaining dust and small particles.

4.4.5. **Water Blasting**. Use a high-pressure water blaster to thoroughly clean prepared surfaces. Keep the nozzle tip no more than 6 in. from the steel surface being cleaned where corrosion is present on steel, and no more than 12 in. from soundly adhering painted surfaces, unless otherwise directed. For cleaning steel bearings, keep the nozzle tip no more than 2 in. from the surface being cleaned.

Probe the perimeter of peeled areas of paint with a putty knife to ensure remaining paint is tightly adhered.

4.4.6. **Tape Test**. Perform the following tape test, as necessary to determine cleanliness, on any surface before painting:

- press a strip of filament tape onto the surface by rubbing with moderate thumb pressure four times, leaving approximately 2 in. of one end of the tape free from the surface, and
- grasp the free end and remove the tape from the surface with a sharp pull.

The surface will be considered contaminated and not adequately cleaned if visible particles cling to the tape.

4.5. **Drying**. Allow surfaces to thoroughly dry before applying coatings. Use oil-free compressed air to blow out tightly confined locations such as joints and crevices.

4.6. **Paint Systems**. Apply paint systems in conformance with the manufacturer's specifications and applied at the specified DFT and as shown on the plans.

4.6.1. **System I (Overcoating, One Coat)**. Apply at least 4.0 mils dry film thickness (DFT) maintenance overcoat to all surfaces to be painted.

4.6.2. **System II**. Zinc primer system consisting of multiple coats.

- **Prime Coat**. Apply 3.5–10.0 mils DFT of primer in at least two coats.
- **Appearance Coat**. Apply 2.0–5.0 mils DFT of appearance coat.

4.6.3. **System III-A**. Zinc primer system consisting of multiple coats.

- **Prime Coat**. Apply 3.5–10.0 mils DFT of primer in at least 2 coats.
- **Stripe Coat of Prime**. Apply stripe coat of prime coating.
- **Stripe Coat of Intermediate**. Apply stripe coat of epoxy intermediate coating.
- **Intermediate Coat**. Apply at least 2.0 mils DFT epoxy intermediate coating.
- **Appearance Coat**. Apply 2.0–5.0 mils DFT of appearance coat.

4.6.4. **Special Paint System**. Apply paint as shown on the plans.

Apply stripe coat as indicated on the plans.

4.7. **Application**.

4.7.1. **Environment**. Do not coat when the steel or air temperature is below 50°F or when the steel or air temperature is expected to drop below 50°F within 2 hr. after application. Follow product data sheets for temperature requirements for all other paints.

Do not apply paint to any surface with discernible moisture. Do not apply paint to any surface when steel is within 5°F of the dewpoint. Do not apply any paint when impending weather conditions might result in injury to fresh paint.

4.7.2. **Method**. Apply each coat of paint to clean, dry, and firm surfaces complying with all Specification requirements. Ensure surfaces to be painted are free of all forms of contamination. Ensure each coat fully cures to form a smooth, continuous, and tightly adhering film of uniform thickness and appearance, free of sags, runs, pinholes, holidays, overspray, or other defects, before applying the next coat.

Trace the transition between no-paint areas, or inner paint coats, and remaining surface paint with first new coat utilizing a brush, working the first coat into the seam between coats.

Apply coats in conformance with the manufacturer's specifications.

5. MEASUREMENT

This Item will be measured by the lump sum or by each structure, structure unit, or group of structures as shown on the plans.

6. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the price of "Steel Bridge Zone Painting" for the system specified and, when paid per structure, for the structure description by reference number. "Steel Bridge Zone Painting" includes the areas shown on the plans. This price is full compensation for paint; cleaning; painting; removal of vegetative obstructions; waste debris and water containment; disposal of waste; and all materials, equipment, labor, tools, and incidentals necessary to complete the work.