

TRAFFIC

-Transition Panel

Transition-

by rear panel.

ponel overlopped

the Engineer.

MEDIAN BARRIER BACKUP

Bi-directional with typical offset shown, Offset plus transition panel will be amitted for uni-directional application,

Bose width of borrier should be topered

to prevent potential enogging for uni-

directional application as directed by

/usc/d481303

ACC:

TRAFFIC

TYPE B

BACKUP OPTION

DESIGN SPEED BAYS (MPH) 40 OR LESS 3 45 4 50 5 55 6 60 7 65 9 70 10

The specified number of boys is based upon 66's maximum deceleration force for impact at a specific design speed. Additional boys may be added if special considerations worrant and site conditions will accommodate additional lenoth.

Permonent G.R.E.A.T. units are available in 2'-0", 2'-6", or 3'-0" widths to 12 bays. Unit width, number of bays, and backup type shall be specified elsewhere in the plans.

The Type CZ unit is available in 2'-0' or 2'-6' widths with 3 or 6 boys only.

BACKUP TYPES

- * TYPE A TENSION STRUT: Consists of diagonal struts, connections, and occessories, as detailed by the Manufacturer, located at the rear of the G.R.E.A.T. unit. Typical application is for G.R.E.A.T. units attached to double-face guardrall. When used, a 4'-0'x 4'-0'x 3'-0' concrete toe anchor block shall be provided beneath the front portion of the concrete pad, except where the G.R.E.A.T. unit is to be placed on continuously reinforced concrete povement or bridge deck (7' minimum, 4,000 p.s.l.) or non-reinforced concrete povement (8' minimum, 4,000 p.s.l.)
- TYPE B CAST-IN-PLACE CONCRETE WALL BACKUP: If cost-In-place structures such as bridge parapets, columns, or special walls are used as backup structures, then intermediate walls shall be provided between the structures and the G.R.E.A.T. unit. Intermediate walls shall be equal in height and width to the G.R.E.A.T. unit and reinforced with a steel cage. A cast-In-place transition section from standard C.T.B. or S.S.C.B. may be used in lieu of the Type D Backup (Type B Option). Special caution should be exercised in the design and detail of the transition of should be exercised in the design and detail of the transition from the standard barrier section to the standard backup section. Details for the intermediate walls, cost-in-place transition sections from C.T.B. or S.S.C.B. to concrete wall backup, or other modifications will be shown elsewhere in the plans. Concrete wall backups may be used on continuously reinforced concrete pavement or bridge deck (7° minimum, 4,000 p.s.i.) or non-reinforced concrete pavement (8° minimum, 4,000 p.s.i.) In those cases, all vertical steel will be doweled (5 inch minimum) into existing decks or located and placed prior to pouring proposed decks as approved by the Engineer.
- TYPE C WIDE FLANCE BACKUP: Consists of two 74 inch WF steel posts erected vertically at rear of G.R.E.A.T. unit. Details for the connections and accessories for the wide flange backup will be provided by the Manufacturer.
- TYPE D MEDIAN BARRIER BACKUP: Typical application is for G.R.E.A.T. units 2'-0' width attached to standard permanent C.T.B. The designer must specify bi-directional applications to provide for placement of transition panels. These places are installed with a unit offset to eliminate snagging potential at barrier end of G.R.E.A.T. Special connection details will be provided by the Manufacturer. The Designer should specify either C.T.B. or S.S.C.B. median barrier application to allow the Manufacturer to supply the appropriate transition panel.
- TYPE CZ CONSTRUCTION ZONE BACKUP: Consists of a steel base and tension strut backup as integral parts of the G.R.E.A.T. unit. Anchorage requirements are as follows:

WITH FOUNDATION TYPE	ANCHOR WITH				
Winimum six inch concrete	6.5 Inch studs or 18 Inch threaded rad and Mfr. epoxy				
Minimum three inch asphalt over minimum three inch concrete	18 Inch threaded rod and Mfr. epoxy				
Minimum six inch asphalt over base	18 Inch threaded rod and Wfr.				
Minimum three inch asphalt over base	Anchor plns				
Minimum eight Inch asphalt on non-base type surface	18 Inch threaded rod and Mfr.				

Details for a precast portable concrete pod are available from the Manufacturer. The pod, with proper anchor boits, may be used as a substitute foundation as approved by the Engineer.

If the unit is anchored to applial, it should be relocated to fresh, undisturbed asphalt and re-anchored after each impact to ensure adequate future performance. A zero clearance between the backup and barrier wall is recommended. In no case should this distance exceed it inches.

GENERAL NOTES

- Details of components for the G.R.E.A.T. and backups and reinforcing details will be shown on shop drawings furnished to the Engineer.
- Concrete shall be class "S" with a minimum compressive strength of 4,000 p. s. l.
- If the cross-slope varies more than 2% over the length of the system, the concrete pod will require levelling. Max. permissible cross-slope is 8%.
- The Installation area should be free from all curbs, elevated objects, depressions, or any other features which may affect unit performance.
- The G.R.E.A.T. system shall be parallel with the barrier or \(\xi\) of merging barriers.
- Unit width selected should be adequate to protect on erront vehicle travelling at 15 degrees to the roadway from the face or corner of the potential hazard.
- For all permanent steel backups, (Types A.C. and D) the distance between the face of backup and the barrier wall should not exceed 14 Inches In any case.



GUARD RAIL ENERGY ABSORBING TERMINAL

GREAT-94

		_							
K 8M ME	WAY 1994	TOU		a- ta	BCD	a.	\neg	ec m. 462	
and stated		STARE!	25	FROM M PILET		Æ	•	3000	
				6					
			TIME		-	#ct +	-	-	
			-			_			