



*See As Built (Comp.)*

*See As Built*

Note to Contractor:  
 The existing 12" sewer, has been plugged at manhole upstream, therefore this line is and will be inactive of the time of construction.  
 Notify Mr. Frank Gerun of the Hwy. Dept. (Tel. UN 9 3211) 48 hrs prior to starting work.

Approval for:  
 Texas Highway Department  
 Houston Urban Office  
 \_\_\_\_\_  
 Engineer - Manager  
 Hwy. Dept. Perm. No. 67-3944  
 U-318(s)

PROP. 12" SANITARY SEWER RELOCATION ON YELLOWSTONE BETWEEN ARDMORE AND PEERLESS STATE HIGHWAY 288

**JOB NO. 3084**  
 CITY OF HOUSTON  
 DEPARTMENT OF PUBLIC WORKS

APPROVAL: \_\_\_\_\_  
 SANITARY SEWERS  
 WATER DEPT.

CITY ENGINEER: \_\_\_\_\_  
 TRAFFIC & TRANSPORTATION

CITY SUPERVISOR: \_\_\_\_\_  
 ASST. DIRECTOR OF PUBLIC WORKS DIRECTOR OF PUBLIC WORKS

SUBMITTED: \_\_\_\_\_  
 SCALE: 1" = 40' Horiz. 1" = 4' Vert.  
 DATE: MAY 13 - 1966  
 SURV. BY: HWY. DEPT.  
 F. B. NO. \_\_\_\_\_

DESIGNED BY: A. G. S.  
 DRAWN BY: H. J.  
 SHEET NO. 1 OF 1 SHEETS  
 DWG. NO. 14915

BACKFILL: Backfill shall be compacted by any means other than water tamping to a density of not less than 100% of the adjacent undisturbed soil. Cost of this compaction to be included in price bid per foot of sewer.

(Revised 8/10/67)

*See As Built # 14915*