


The following TCEQ requirements (Form TCEQ-0592A, Rev. 7/15/15) are applicable to all work that disturbs 5 or more acres in the contributing zone of the Edwards Aquifer in Hays, Travis and/or Williamson Counties and must be adhered to by the Contractor and all Subcontractors:

1. A written notice of construction must be submitted to the TCEQ regional office at least 48 hours prior to the start of any ground disturbance or construction activities. This notice must include:
 - the name of the approved project;
 - the activity start date; and
 - the contact information of the prime contractor.
2. All contractors conducting regulated activities associated with this project should be provided with complete copies of the approved Contributing Zone Plan (CZP) and the TCEQ letter indicating the specific conditions of its approval. During the course of these regulated activities, the contractor(s) should keep copies of the approved plan and approval letter on-site.
3. No hazardous substance storage tank shall be installed within 150 feet of a water supply source, distribution system, well, or sensitive feature.
4. Prior to beginning any construction activity, all temporary erosion and sedimentation (E&S) control measures must be properly installed and maintained in accordance with the manufacturers specifications. If inspections indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations. These controls must remain in place until the disturbed areas have been permanently stabilized.
5. Any sediment that escapes the construction site must be collected and properly disposed of before the next rain event to ensure it is not washed into surface streams, sensitive features, etc.
6. Sediment must be removed from the sediment traps or sedimentation basins when it occupies 50% of the basin's design capacity.
7. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from being discharged offsite.
8. All excavated material that will be stored on-site must have proper E&S controls.
9. If portions of the site will have a cease in construction activity lasting longer than 14 days, soilstabilization in those areas shall be initiated as soon as possible prior to the 14th day of inactivity. If activity will resume prior to the 21st day, stabilization measures are not required. If drought conditions or inclement weather prevent action by the 14th day, stabilization measures shall be initiated as soon as possible.
10. The following records should be maintained and made available to the TCEQ upon request:
 - the dates when major grading activities occur;
 - the dates when construction activities temporarily or permanently cease on a portion of the site; and
 - the dates when stabilization measures are initiated.
11. The holder of any approved CZP must notify the appropriate regional office in writing and obtain approval from the executive director prior to initiating any of the following:
 - A. any physical or operational modification of any best management practices (BMPs) or structure(s), including but not limited to temporary or permanent ponds, dams, berms, silt fences, and diversionary structures;
 - B. any change in the nature or character of the regulated activity from that which was originally approved;
 - C. any change that would significantly impact the ability to prevent pollution of the Edwards Aquifer; or
 - D. any development of land previously identified as undeveloped in the approved contributing zone plan.

DATE: 9/21/2020 12:55:14 PM
FILE: \\txdot\projectwiseon\ine.com\TXDOT4\Documents\14 - AUS_Standards\District Design_Standards\Approved\TCEQ-CZ-19(AUS).dgn

TCEQ REGIONAL OFFICE			
Austin Regional Office 12100 Park 35 Circle Bldg A, Room 179 Austin, Texas 78753 Phone: (512) 339-2929 Fax: (512) 339-3795			
			<i>Austin District Standard</i>
TCEQ REQUIREMENTS FOR THE CONTRIBUTING ZONE OF THE EDWARDS AQUIFER (DISTURBING 5 OR MORE ACRES)			
TCEQ-CZ-19(AUS)			
©TxDOT 2020			
REVISIONS			
01/10/14: REQUIREMENTS AND ADDRESS UPDATED	CONT	SECT	JOB
01/21/16: REQUIREMENTS UPDATED	DIST	COUNTY	SHEET NO.
09/24/19: UPDATED RELEASE YEAR			